

6677 Busch Blvd. Columbus, OH 43229 614.846.5757

October 30, 2020

Mr. Andrew R. Wheeler, EPA Administrator Environmental Protection Agency 1200 Pennsylvania Avenue, N.W. Mail Code 5304-P Washington, DC 20460

Subject: Cardinal Power Plant – Alternative Closure Demonstration

Dear Administrator Wheeler:

Cardinal Operating Company hereby submits this request to the U.S. Environmental Protection Agency (EPA) for approval for a site-specific alternative deadline to initiate closure pursuant to 40 CFR § 257.103(f)(1) for the Bottom Ash Pond located at Cardinal Power Plant in Brilliant, Ohio.

Cardinal is requesting an extension pursuant to 40 CFR § 257.103(f)(1) to allow the impoundment to continue receiving CCR and non-CCR waste streams after April 11, 2021, in order to segregate and retrofit the pond into two separate reservoirs. One reservoir will be retrofitted with a State compliant NPDES liner, designed to receive low volume wastes only. The second reservoir will be retrofitted with a CCR compliant liner, designed to receive CCR wastes only.

Enclosed is a demonstration prepared by Sargent & Lundy that addresses all of the criteria in 40 CFR § 257.103(f)(1)(i)-(iii) and contains the compliance documentation required by 40 CFR § 257.103(f)(1)(i). As allowed by the agency, in lieu of hard copies of these documents, electronic files were submitted to Kristen Hillyer, Frank Behan, and Richard Huggins via email.

If you have any questions regarding this submittal, please contact Nick Kasper at (614) 681-5160 or <u>nkasper@ohioec.org</u>.

Sincerely,

TC Malban

Thomas M. Alban Vice President

cc: Kristen Hillyer Frank Behan Richard Huggins



Cardinal Power Plant Bottom Ash Pond Complex

Demonstration for a Site-Specific Alternative to Initiation of Closure Deadline

Report SL-015687 Revision 0 October 29, 2020 Issue Purpose: Client Comment Project No.: 13770-007

55 East Monroe Street Chicago, IL 60603-5780 USA 312-269-2000 www.sargentlundy.com



LEGAL NOTICE

This workplan was prepared by Sargent & Lundy, L.L.C. (S&L) expressly for the sole use of Buckeye Power, Inc. (Client) in accordance with the contract agreement between S&L and Client. This workplan was prepared using the degree of skill and care ordinarily exercised by engineers practicing under similar circumstances. Client acknowledges: (1) S&L prepared this workplan subject to the particular scope limitations, budgetary and time constraints, and business objectives of Client; (2) information and data provided by others, including Client, may not have been independently verified by S&L; and (3) the information and data contained in this workplan are time-sensitive and changes in the data, applicable codes, standards, and acceptable engineering practices may invalidate the findings of this workplan. Any use or reliance upon this workplan by third parties shall be at their sole risk. Cardinal Operating Company Cardinal Power Plant Bottom Ash Pond Complex

TABLE OF CONTENTS

Lega	I Noti	ce	i
Table	e of C	ontents	ii
Exec	utive	Summary	iii
1.0	Dev	elopment of Alternative Capacity	
	1.1	Background Information	
	1.2	General Strategy for Compliance with EPA Regulations	
	1.3	Alternative Disposal Solutions Considered	
	1.4	Conceptual Design of Reconfigured BAP Complex	
	1.5	Explanation & Justification of Time Requested	
2.0	Proj	ect Schedule: Visual Timeline	
3.0		ect Schedule: Narrative Discussion	
	3.1	Installation Activities & Projected Workflow	
	3.2	Engineering and Design	
	3.3	Procurement	
	3.4	Construction, Startup, & Implementation	
4.0	Proj	ect Schedule: Progress to Date	
5.0	Refe	erences	
6.0	Cert	ification of Compliance	
	6.1	Owners Certification of Compliance	

6.2 Compliance Documents

EXECUTIVE SUMMARY

The Bottom Ash Pond (BAP) Complex at the Cardinal Power Plant in Brilliant, Ohio consists of two surface impoundments, the Bottom Ash Pond and Recirculation Pond, which are managed as a single coal combustion residual (CCR) unit. This unit does not meet the liner design criteria promulgated by 40 CFR Part 257 Subpart D ("the EPA CCR Rule"). Therefore, the Cardinal Power Plant must cease placing the CCR and non-CCR waste streams currently sent to the BAP Complex as soon as technically feasible but no later than April 11, 2021, unless an alternative deadline is granted by the EPA in accordance with 40 CFR 257.103. After evaluating several on- and off-site alternative disposal solutions for the waste streams currently sent to the BAP Complex – both permanent and temporary – the Cardinal Operating Company has concluded that no alternative disposal capacity is available for certain waste streams currently being sent to the BAP Complex, and that it was technically infeasible to obtain alternative disposal capacity for these waste streams on- or off-site by April 11, 2021. Accordingly, pursuant to 40 CFR 257.103(f)(1)(iv)(A), the Cardinal Operating Company has prepared the following workplan detailing its development of alternative disposal capacity to replace the BAP Complex.

The Cardinal Power Plant currently sends the following CCR and non-CCR waste streams to the BAP Complex: bottom ash transport water (CCR), metal cleaning waste water (non-CCR), plant services waste water (non-CCR), cooling tower blowdown and basin overflow (non-CCR), sump and drain water (non-CCR), coal pile run-off overflow (non-CCR), and Jet Bubbling Reactor waste water (non-CCR). After evaluating several options for providing alternative disposal capacity to the BAP Complex for these waste streams, the Cardinal Operating Company elected to install a multiple technology system: retrofitting the Recirculation Pond to handle the CCR waste streams and repurposing the Bottom Ash Pond into a non-CCR waste water basin. In addition to providing compliance with the EPA CCR Rule, this option separates the CCR and non-CCR waste streams currently being commingled in the BAP Complex, which gives the station more flexibility in complying with the EPA's recently-revised effluent limitation guidelines for steam electric power generating stations ("ELG Rule"). As such, this alternative disposal capacity provides a holistic solution for complying with both the EPA CCR and ELG Rules.

The Cardinal Operating Company will begin the development of this multiple technology solution by stopping all flows to the Recirculation Pond, then excavating the CCR currently stored therein, and finally retrofitting it with an EPA CCR Rule-compliant composite liner system. After the composite liner system has been installed and the retrofit work has been certified, the retrofitted pond will begin receiving CCR waste streams. The retrofitted pond is expected to be operational by November 30, 2021.

Once the Recirculation Pond has been retrofitted, the Cardinal Operating Company will begin repurposing the Bottom Ash Pond into a non-CCR waste basin. This work will be completed in two phases in order to continue sending non-CCR waste streams to the pond so that the plant can remain in compliance with its

NPDES permit during construction. In the first phase, the southern portion of the pond will be clean-closed and re-lined with a geomembrane liner. Once this first phase is complete, the non-CCR waste streams will be directed to the repurposed portion of the pond. This alternative disposal capacity for the BAP Complex's non-CCR waste streams is expected to be available by June 9, 2022.

Based on the scheduled completion dates for the retrofitted CCR pond and repurposed non-CCR waste basin, the Cardinal Operating Company is requesting the EPA allow the BAP Complex to continue receiving the noted CCR waste streams until November 30, 2021, and the noted non-CCR waste streams until June 9, 2022. Further details on the BAP Complex, the waste streams managed therein, and the Cardinal Operating Company's development of alternative disposal capacity for these waste streams are provided throughout this workplan.

1.0 DEVELOPMENT OF ALTERNATIVE CAPACITY

This section presents the option selected by the Cardinal Operating Company to provide alternative disposal capacity to the Cardinal Power Plant's Bottom Ash Pond Complex for the coal combustion residual (CCR) and non-CCR waste streams managed therein. In addition, this section provides background information on the Cardinal Power Plant, the Bottom Ash Pond Complex and the waste streams managed within them, the adverse impact to plant operations if the Bottom Ash Pond Complex was shutdown, the process the Cardinal Operating Company undertook to select the alternative disposal capacity currently being developed, and a narrative of the alternative disposal capacity design. Finally, an explanation and justification for the time being requested to operate the Bottom Ash Pond Complex beyond April 11, 2021 are also provided in this section.

1.1 BACKGROUND INFORMATION

1.1.1 CARDINAL POWER PLANT

The Cardinal Operating Company operates the Cardinal Power Plant ("Cardinal"), which is a coal-fired steam electric power generating station located in Brilliant, Ohio, adjacent to the Ohio River. The station's address is 306 County Road 7E, Brilliant, Ohio 43913. The plant consists of three operating units – Units 1, 2, and 3 – and has a combined nameplate capacity of approximately 1,800 MW. Unit 1 is owned by AEP Generation Resources Inc., the competitive generation subsidiary of American Electric Power. Units 2 and 3 are owned by Buckeye Power, Inc., a generation and transmission cooperative that operates the Cardinal Operating Company. The plant operates as a base-load generation asset to meet the day-to-day electricity demands of the 25 electric cooperatives that own and govern Buckeye Power, Inc. as well as the local communities serviced by AEP Generation Resources Inc.

1.1.2 BOTTOM ASH POND COMPLEX

1.1.2.1 POND COMPLEX CHARACTERISTICS

Cardinal's Bottom Ash Pond (BAP) Complex consists of two surface impoundments, the BAP and the Recirculation Pond, which are managed as a single CCR unit. These ponds are adjacent to each other – the larger BAP is located north of the smaller Recirculation Pond – and are located south of Unit 3's power block and flue gas desulfurization (FGD) island. Both ponds are west of and adjacent to the Ohio River.

1.1.2.2 POND COMPLEX INFLOWS & OPERATIONS

The primary purpose of the BAP Complex is to store bottom ash produced by Cardinal during powergenerating operations. The bottom ash handling system at each of the station's three units sluices bottom ash transport water (BATW) via several pipes to the northwest corner of the BAP. Based on the Fact Sheet submitted with the Cardinal Operating Company's 2018 National Pollutant Discharge Elimination System (NPDES) permit application for the Cardinal station (Ref. 3), the plant sluices approximately 4.1 million gallons of BATW to the BAP Complex per day.

When bottom ash enters the BAP, the coarser ash particles tend to settle out of the transport water near the discharge point into the pond, while the finer ash particles tend to settle out further from the discharge point near the southern end of the pond. Waste water in the BAP ultimately flows into the Recirculation Pond through an overflow discharge structure located at the southeast side of the BAP. During normal plant operations, water in the Recirculation Pond is ultimately stored and recycled by the Recirculation Pumphouse and sent back to the station for use in the plant's fly ash-handling systems (*i.e.*, source water for sluicing fly ash to Fly Ash Reservoir (FAR) II). In extreme events (*e.g.*, large rainfall), excess water may be discharged to the adjacent Ohio River through Outfall 023, which is a drop outlet structure with a 36-inch-diameter pipe. This discharge is regulated by the station's active NPDES permit. A partition wall currently separates the portion of the Recirculating Pond that feeds into the Recirculating Pumphouse and the portion that discharges through Outfall 023.

In addition to BATW, the plant also conveys the following low-volume waste (LVW) streams to the BAP Complex: metal cleaning waste water, Unit 1 and 2 service water, Unit 3 cooling tower blowdown and basin overflow water, overflow water from the coal pile run-off pond, and storm water drainage from Unit 3. Per the aforementioned NPDES permit application, these streams have a collective average inflow into the BAP Complex of approximately 8.0 million gallons per day (MGD).

Table 1 summarizes the CCR and non-CCR waste streams sent to the BAP Complex. Per the aforementioned NPDES permit application, the maximum flows listed in the table are based on the 10-year, 24-hour storm event for the site.

Table 1 – Inflows into Cardinal Bottom Ash Pond Complex

Waste Stream	Description	Average Flow, MGD (Max. Flow, MGD)
CCR Waste Streams		4.14
Unit 1 & 2 Bottom Ash Transport Water	Sluice water containing bottom ash particles from the Unit 1 and 2 boilers	2.30
Unit 3 Bottom Ash Transport Water	Sluice water containing bottom ash particles from the Unit 3 boiler	1.84
Non-CCR Waste Streams		7.98 (17.55)
Metal Cleaning Waste Water	Waste water from the tank used to store waste water from cleaning the Unit 1, 2, and 3 boilers	0.0014
Unit 1 & 2 Plant Services Waste Water	Waste water from the process water used to operate equipment in Units 1 and 2 (<i>e.g.</i> , heat exchangers)	4.32
Unit 3 Cooling Tower Blowdown	Waste water used to remove minerals collected in the Unit 3 cooling tower basin	1.58
Unit 3 Cooling Tower Basin Overflow	Overflow water from the Unit 3 cooling tower basin	1.83
Unit 3 Sump and Drain Water	Storm water collected by sumps and drains in the Unit 3 power block	0.02 (1.60)
Coal Pile Run-Off Pond Overflow	 Waste water collected by the station's Coal Pile Run-Off Pond. Includes storm water from: Coal pile, Coal truck unloading area, Unit 1, 2, and 3 FGD areas (including gypsum pile, limestone pile, and marine area run-off), and Unit 1 and 2 power block sumps and drains. 	0.23 (6.44)
Jet Bubbling Reactor (JBR) Waste Water	Waste water from the JBR in the Unit 1, 2, and 3 FGD system and associated storage tanks. Includes waste water from: • JBR process water, • Reagent feed tank, • FGD reclaim water, and • Byproduct storage tank.	0.00 (1.78)

Source: Cardinal 2018 NPDES Permit Application Fact Sheet (Ref. 3)

1.1.2.3 APPLICABLE REGULATIONS

1.1.2.3.1 FEDERAL CCR RULE

The BAP Complex has been regulated by the EPA CCR Rule (40 CFR Part 257 Subpart D, Ref. 1) since the rule went into effect in October 2015. Per the 2016 Water Infrastructure Improvements for the Nation (WIIN) Act, both the BAP and the Recirculation Pond will continue to be subject to the requirements prescribed in the EPA CCR Rule until the EPA approves a CCR permit program developed and submitted by the Ohio EPA. Because the Ohio EPA has yet to submit a proposed CCR permit program to the EPA, Ohio is currently considered a Nonparticipating State per 40 CFR 257.53. Consequently, this workplan and the alternative closure deadline requested herein for the BAP and the Recirculation Pond are subject to the approval of the EPA.

1.1.2.3.2 FEDERAL ELG RULE

In addition to the preceding EPA CCR Rule, the operation of the BAP Complex – specifically discharges through NPDES-permitted Outfall 023 – is also subject to compliance with the EPA's effluent limitation guidelines for steam electric power plants ("ELG Rule"). The 2020 update to the ELG Rule (Ref. 8) sets new limits for discharging BATW and other waste streams generated by steam electric power plants to waters of the U.S. Pursuant to the new 40 CFR 423.13(k)(1)(i) and (k)(2)(i)(A), the ELG Rule establishes a zero-liquid discharge (ZLD) standard for Cardinal's BATW – including any LVW streams that come into contact with BATW – unless the BATW is used in an FGD scrubber or under the following conditions:

- To maintain the bottom ash system's water balance during:
 - o Significant precipitation events (10-year, 24-hour storm event or longer), and
 - Situations where excessive quantities of other waste streams regularly handled by the bottom ash system compromise the system's ability to handle recycled BATW;
- To maintain the bottom ash system's water chemistry, and
- To conduct maintenance when water volumes cannot be managed by redundancies, tanks, etc.

In any of the preceding situations, the plant would not be permitted to purge more than 10% of the bottom ash system's maximum volumetric capacity for BATW (calculated on a 30-day rolling average and excluding redundancies, maintenance systems, *etc.*).

Cardinal will be subject to the ZLD standard for BATW promulgated by the updated ELG Rule upon incorporation into the facility's NPDES permit by a date determined by the Ohio EPA. Pursuant to the station's NPDES permit, the Ohio EPA has approved a compliance end date of December 31, 2023. This complies with the new 40 CFR 423.13(k)(1)(i), which requires this NPDES permit modification to occur no later than December 31, 2025.

1.1.2.4 FUTURE HANDLING OF CCR & NON-CCR WASTE STREAMS

The BAP Complex does not meet the liner design criteria promulgated by 40 CFR 257.71(a) and is therefore considered to be an unlined CCR surface impoundment. Thus, per 40 CFR 257.101(a)(1) and (a)(3), Cardinal must cease placing the CCR and non-CCR waste streams listed in Table 1 into the BAP Complex as soon as technically feasible and no later than April 11, 2021, unless an alternative deadline is granted by the EPA.

As detailed herein, the Cardinal Operating Company is requesting that the EPA allow Cardinal to continue sending certain CCR and non-CCR waste streams to the BAP Complex after April 11, 2021 while it develops alternative capacity to replace the BAP Complex because:

- No existing alternative disposal capacity is available on- or off-site for these waste streams,
- It was technically infeasible to develop the alternative capacity selected by April 11, 2021 for these waste streams, and
- FAR II, which the station uses to dispose of its fly ash transport water (FATW), will not cease operating until June 2021, and the BAP Complex provides the source water for the station's fly ash sluicing systems.

1.1.3 ADVERSE IMPACT TO PLANT OPERATIONS WITHOUT THE BAP COMPLEX

In order to generate power at Cardinal, it is necessary to dispose of the bottom ash produced from the combustion of pulverized coal in the station's boilers. Without a suitable replacement for the BAP Complex, the Cardinal plant would be forced to stop power-generating operations. Given that the plant is a base-load generation asset for 25 electric cooperatives (see Section 1.1.1), a forced shutdown would leave the electric grid susceptible to unplanned and prolonged outages.

1.2 GENERAL STRATEGY FOR COMPLIANCE WITH EPA REGULATIONS

The Cardinal Operating Company has evaluated several different handling and/or disposal alternatives for Cardinal's CCR and non-CCR waste streams since 2016, shortly after the EPA's new CCR Rule and the 2015 amendment to its ELG Rule both became effective. Given the ZLD standards established for both FATW and BATW in the 2015 ELG Rule (Ref. 9), waste streams which included (and still include) non-CCR waste streams that are commingled with FATW and BATW, Cardinal evaluated alternatives that either eliminated these waste streams or allowed for them to be recirculated back into plant systems. In this evaluation of ELG Rule compliance options, Cardinal also sought solutions that would be compliant with the new EPA CCR Rule. In essence, the Cardinal Operating Company has been seeking holistic solutions in regard to complying with both the EPA CCR and ELG Rules for alternative handling and/or disposal of Cardinal's CCR and non-CCR waste streams.

1.3 ALTERNATIVE DISPOSAL SOLUTIONS CONSIDERED

Prior to the August 2018 *Utility Solid Waste Activities Group* (*USWAG*) decision by the U.S. Court of Appeals for the D.C. Circuit (Ref. 2), in which the Court ordered the provisions in the EPA CCR Rule allowing unlined ash ponds to continue operating be vacated and remanded, the Cardinal Operating Company started evaluating available alternatives for replacing the existing BAP Complex. In accordance with the Cardinal Operating Company's desire for a holistic solution, this evaluation assessed not only permanent disposal solutions for Cardinal's BATW but also the LVW streams managed by the pond complex. This assessment is summarized in Section 1.3.3.

Pursuant to the recently-revised alternative closure requirements for CCR surface impoundments in the EPA CCR Rule, the Cardinal Operation Company also evaluated whether existing capacity is available on- or offsite for each waste stream currently sent to the BAP Complex. For those streams where existing capacity is not available, the Cardinal Operating Company evaluated whether it was technically feasible to obtain alternative disposal capacity – either temporary or permanent – by April 11, 2021. The following subsections discuss the alternative disposal solutions considered for each waste stream managed in the BAP Complex and how these waste streams were ultimately dispositioned.

1.3.1 EXISTING ON-SITE DISPOSAL SOLUTIONS

1.3.1.1 BOTTOM ASH TRANSPORT WATER

Because BATW is a CCR waste stream, it must be disposed of in an active CCR unit. As documented on the Cardinal Operating Company's public CCR website (Ref. 4), Cardinal has three CCR units on-site: the BAP Complex, FAR II, and FAR I Landfill. FAR II is a CCR surface impoundment used by the station to store and treat its FATW, as well as leachate and contact storm water run-off from FAR I Landfill. However, like the BAP Complex, FAR II is not compliant with the liner design criteria promulgated by the EPA CCR Rule and is therefore subject to the closure-for-cause requirements promulgated by 40 CFR 257.101. Thus, FAR II would not be an acceptable alternative disposal facility for Cardinal's bottom ash even if the necessary mechanical equipment and piping were installed to divert BATW from the BAP Complex to FAR II.

Located adjacent to FAR II, the station's FAR I Landfill is an EPA CCR Rule-compliant disposal facility that is primarily used by the station to dispose of the gypsum byproduct from its FGD systems. This landfill has also been used to dispose of bottom ash that has been dredged from the BAP Complex and subsequently dewatered. While the landfill may receive bottom ash and has sufficient capacity to accommodate Cardinal's daily generation of bottom ash, the Ohio EPA prohibits industrial solid waste landfills like FAR I Landfill from receiving bulk or noncontainerized liquids wastes like Cardinal's BATW (Ref. 11). Thus, the station cannot utilize its landfill for directly disposing of its bottom ash while it has a wet bottom ash-handling system.

directly send its bottom ash to FAR I Landfill. Because Cardinal does not currently have either of these systems, the station does not presently have the means to directly dispose of its bottom ash in FAR I Landfill.

In summary, there is no alternative on-site disposal capacity to the BAP Complex available for Cardinal's wet-generated bottom ash because:

- The station's only other wet CCR disposal facility, FAR II, is not compliant with the EPA CCR Rule's liner design criteria and, like the BAP Complex, is subject to closure for cause, and
- Neither a dry bottom ash-handling system nor a bottom ash dewatering system are present at the station to allow for Cardinal to utilize its on-site CCR landfill, FAR I Landfill.

1.3.1.2 NON-CCR WASTE STREAMS

1.3.1.2.1 METAL CLEANING WASTE WATER

When Cardinal cleans a boiler during a scheduled unit outage, the resulting waste water is stored in the station's Metal Cleaning Waste Tank. When this tank is full, its contents are drained to the BAP Complex. Given the intermittent and infrequent nature of this flow, the Cardinal Operating Company has not scheduled another boiler clean until after alternative disposal capacity for the BAP Complex becomes available. Thus, metal cleaning waste water will no longer be sent to the BAP Complex.

1.3.1.2.2 OTHER NON-CCR WASTE STREAMS

Unlike the metal cleaning waste water, the remaining non-CCR waste streams sent to the BAP Complex are continuous flows and/or must be sent to the pond during significant storm events. The three continuous non-CCR waste streams sent to the BAP Complex – Unit 1 and 2 plant services waste water, Unit 3 cooling tower blowdown, and Unit 3 cooling tower basin overflow – are also significant flows that exceed or are similar to the flow rates for the Unit 1, 2, and 3 BATW. Cardinal primarily relies on the size of the BAP Complex to provide adequate time for sedimentation of the total suspended solids (TSS) present in these waste streams. This is necessary for the station to recirculate the water back into station operations or, if the station cannot handle the excess water from a significant storm event, to discharge it to the Ohio River via Outfall 023 in accordance with its NPDES permit.

The only other pond at the Cardinal site that is large enough to accept the plant services and cooling tower waste streams currently going into the BAP Complex (7.7 MGD total) is FAR II. However, as previously discussed, this pond is not an acceptable disposal alternative to the BAP Complex since it is also subject to the EPA CCR Rule's closure-for-cause requirements. Therefore, there is no alternative disposal capacity currently available at the Cardinal site for these three waste streams.

Although the Unit 3 sumps and drains, coal pile run-off pond, and JBR waste water flows are intermittently sent to the BAP Complex, it is necessary for these flows to be sent to the BAP Complex during significant

storm events. Because the station has a limited means of recirculating the excess water introduced to its overall water balance during a significant rain event, it must discharge the surplus or risk overtopping / flooding. In particular, the coal pile run-off ponds receive storm water collected in several different areas of the plant in addition to storm water run-off from the coal pile. These relatively small ponds (each less than one acre) would be at risk of overtopping during a significant storm event if the excess water was not otherwise removed. Finally, like all the other flows discussed thus far, FAR II is not an acceptable alternative for these three waste streams. Thus, there is no alternative capacity currently available at the Cardinal site for the excess storm water collected in the Unit 3 sumps and drains, the coal pile run-off ponds, and the JBR area.

1.3.2 EXISTING OFF-SITE DISPOSAL SOLUTIONS

Although the EPA itself has acknowledged that it is not feasible to transport wet-generated CCR to an off-site disposal facility (Ref. 5), the Cardinal Operating Company performed its due diligence and evaluated the feasibility of temporarily transporting the average daily volume of BATW, Unit 1 and 2 plant services waste water, Unit 3 cooling tower blowdown, Unit 3 cooling tower basin overflow, Unit 3 sump and drain water, and coal pile run-off pond overflow to an off-site disposal facility until a permanent disposal facility could be installed on-site. Given that the JBR waste water flow is typically only present during significant storm events, these flows were not included in this evaluation. As previously mentioned, landfills are generally not permitted to receive bulk or noncontainerized liquids, so only waste water treatment plants (WWTPs) could be considered as potential disposal facilities for the waste water flows considered in this evaluation.

Although not covered in this workplan, the Cardinal Operating Company is also requesting an alternate deadline for ceasing flows to FAR II. Consequently, the CCR and non-CCR waste streams sent to this pond will also need to be transported to an off-site treatment facility. As demonstrated in the corresponding workplan for FAR II, Cardinal does not currently have alternative means of disposing the flows presented in Table 2. As shown in the table, an average flow of approximately 9.8 MGD of CCR and non-CCR waste water would need to be sent to a temporary facility off-site in addition to the noted BAP Complex waste streams.

To be a viable option, a WWTP would need to receive the average daily volume of the preceding CCR and non-CCR waste streams from the BAP Complex and FAR II, in addition to the waste water volume the WWTP currently treats. Therefore, per Table 1 and Table 2, the WWTP (or combination of WWTPs) would need to be capable of receiving an average flow of 21.9 MGD.

Waste Stream	Description	Average Flow, MGD
CCR Waste Streams		8.93
Unit 1 & 2 Fly Ash Transport Water	Sluice water containing fly ash particles from the Unit 1 and 2 ESPs	5.76
Unit 3 Fly Ash Transport Water	Sluice water containing fly ash particles from the Unit 3 ESP	3.17
Non-CCR Waste Streams		0.88
FAR I Landfill Leachate	Leachate collected and removed from FAR I Landfill	0.09
FAR I Landfill Contact Storm Water	Contact storm water from FAR I Landfill	0.79

Source: Cardinal 2018 NPDES Permit Application Fact Sheet (Ref. 3)

Inquiries were placed with 11 WWTPs within 50 miles of the station to determine if any plants in the region were capable of handling the total or a significant portion of the 21.9 MGD of ash transport and non-CCR waste water from Cardinal. Of the four WWTPs that responded, two plants had a combined capacity of less than 10 MGD, and one indicated that the facility could not accept external waste water streams. A representative from the fourth WWTP stated that the plant had the rated capacity to accommodate the average volume of waste water produced at Cardinal but expressed concerns regarding the water chemistry.

Even if this specific WWTP's water chemistry concerns were alleviated, or if additional WWTPs responded stating that they had sufficient capacity, the Cardinal Operating Company would need to identify a means of transporting the waste water to one or more WWTPs. Given the station's existing ash-handling infrastructure, trucks with tank trailers would likely be the only transportation method that could be established for the station's ash transport and non-CCR waste streams prior to the April 11, 2021 deadline for ceasing all flows into Cardinal's ash ponds.

Based on an average continuous flow rate of 8,400 gpm, this scenario would require new tanks be installed at some interception point upstream of the BAP Complex to temporarily store the BATW and non-CCR waste streams currently going into the BAP Complex prior to being pumped into tank trucks. A similar system would be established near FAR I Landfill to collect its leachate and contact storm water run-off. Meanwhile, fly ash slurry temporarily stored in the tanks downstream of the station's Hydroveyors® would be directly pumped into the trucks' tank trailers. It should be noted that this scenario would require Cardinal to identify and obtain an alternate source of water for the fly ash-handling system in lieu of the water currently recycled from the BAP Complex. Ohio state law limits the overall gross vehicle weight to 80,000 pounds (Ref. 6). Considering the weight of the CCR solids in the waste water being transferred to a WWTP and assuming an empty tank trailer weight of 12,000 pounds, a 7,000-gallon tank trailer would be the maximum tank trailer that would be permitted to transport waste water to an off-site WWTP. Therefore, over 3,100 daily trips would be required to transport 21.9 MGD of ash transport and non-CCR waste water to a WWTP. Even if Cardinal implemented an alternate means of handling its non-CCR waste water, it would require more than 1,800 daily trips to transport the 13.1 MGD of BATW and FATW generated by the station.

Even if the station could support the number of tank trucks to keep up with its daily production rate of transport and non-CCR waste water, there would be significant logistics concerns in coordinating that many trips to and from the station's property. The only way trucks can access the Cardinal site is via Ohio State Route 7 (SR-7). Based on traffic data compiled by the Ohio Department of Transportation (Ref. 7), the average annual daily traffic (AADT) in 2019 for commercial trucks along SR-7 near Cardinal was 1,770 trucks. Therefore, the 3,100 trips required to transport Cardinal's daily volume of ash transport and non-CCR waste water to an off-site WWTP would almost triple the daily volume of truck traffic currently on SR-7. This would impose significant congestion issues on this four-lane road along the Ohio River, an increased potential for traffic accidents, and an increase in air pollution emissions. Thus, in addition to being harmful to human health and the environment, it is impractical to route 3,100-trips worth of trucks per day to an off-site WWTP for several months until alternative ash disposal facilities are installed on-site.

Based on the lack of regional WWTPs available to process or even handle Cardinal's daily volume of ash transport and non-CCR waste water, and based on the impracticality and risks of coordinating the number of truck trips required to handle this volume of waste water, the Cardinal Operating Company has reached the same conclusion as the EPA (Ref. 5) regarding the off-site transportation of wet-generated ash: it is not feasible.

1.3.3 NEW ON-SITE DISPOSAL SOLUTIONS

Based on the preceding evaluations, no alternative disposal capacity currently exists on- or off-site for Cardinal's BATW, Unit 1 and 2 plant services waste water, Unit 3 cooling tower blowdown, Unit 3 cooling tower basin overflow, Unit 3 sump and drain water, coal pile run-off pond overflow, and JBR waste water. Consequently, the Cardinal Operating Company has been actively developing alternative disposal capacity for these waste streams. This subsection presents the process the Cardinal Operating Company underwent to ultimately select the alternative disposal capacity to replace the existing BAP Complex.

1.3.3.1 EVALUATION OF ASH DISPOSAL METHODS

In the third quarter of 2018, Cardinal Operating Company started performing a detailed evaluation of different methods for disposing of Cardinal's fly ash in lieu of sluicing it to FAR II. A similar assessment was also

performed for the station's bottom ash-handling system, which included an evaluation of the following options:

- Install geotextile filter tubes at FAR I Landfill,
- Construct a new surface impoundment on undeveloped land,
- Construct a concrete settling tank at FAR I Landfill, and
- Retrofit the BAP Complex.

1.3.3.1.1 GEOTEXTILE FILTER TUBES

Geotextile filter tubes are containers with oval-shaped cross sections that are composed of engineered fabric that can filter out fine particles within water. Thus, BATW lines could be routed directly to a series of these tubes to filter bottom ash particles out of the transport water. As the bottom ash particles are consolidated within each tube, filtered sluice water would percolate out of each tube onto an impermeable pad with appropriate run-off control measures. Once a tube is full of bottom ash particles, BATW would be redirected to another tube while the full tube continues to dewater. After the filtered ash has been sufficiently dewatered, the full tube would be cut open and loaded onto trucks for final disposal in FAR I Landfill.

For Cardinal, a series of geotextile filter tubes could be installed within the existing FAR I Landfill area. The tubes could be installed in a series of self-contained bays that would facilitate sequential operation of the tubes: one bay would feature a tube actively receiving BATW, a second bay would feature a tube being dewatered, and a third bay would feature a tube being reclaimed for landfilling. Collected filtrate from dewatering could be gravity-drained to a collection sump that would ultimately convey water to a new recirculation water storage tank. To comply with the revised ELG Rule, a new recirculation water system would be installed to pump water back to all three units for re-use in the existing bottom ash-handling system.

While geotextile filter tubes have been used as a method for dewatering bottom ash ponds, there would be challenges in operating and dewatering these tubes during below-freezing weather conditions and excessive rain events. Ultimately, these operational challenges convinced the Cardinal Operating Company that geotextile filter tubes are a technically infeasible replacement for the BAP Complex, and this option was removed from consideration as an alternative disposal option.

1.3.3.1.2 NEW SURFACE IMPOUNDMENT

The Cardinal Operating Company also considered replacing the BAP Complex with a new surface impoundment. Two potential locations on the station's property were identified as suitable for a new ash pond provided new dams were constructed to obtain the necessary long-term storage capacity. Pursuant to the EPA CCR Rule, the new ash pond would be lined with a composite liner system consisting of a geomembrane underlain by a compacted clay liner with a permeability no greater than 1×10^{-7} cm/sec. A

groundwater monitoring program for the new ash pond would be implemented, including the installation of upstream and downstream monitoring wells, to sample and test groundwater in accordance with the EPA CCR Rule. Like the geotextile filter tube option, a recirculation system for BATW would be installed for this option.

Although ash ponds are a proven technology for ash disposal, constructing a new surface impoundment would require a significantly longer design, permitting, and construction effort than the other options considered. Except for the plant proper, Cardinal's property is predominately hilly terrain. So while the two locations identified as potential sites for a new ash pond are currently undeveloped, it would require extensive design and construction efforts to pump BATW and route the corresponding piping to these locations, to install an EPA CCR Rule-composite liner system, and to construct the earth dams required to form a reservoir. This option would also require sufficient time to adequately establish the background groundwater conditions in accordance with the EPA CCR Rule's groundwater monitoring requirements. Finally, a significant amount of return piping would need to be installed to comply with the revised EPA ELG Rule. Overall, it was estimated that this option would take just over 3 years to develop from engineering and design through construction and commissioning.

Given the prolonged schedule required to design, permit, and construct a new surface impoundment relative to the other options evaluated, this option was removed from consideration as an alternative disposal option to replace the BAP Complex.

1.3.3.1.3 CONCRETE SETTLING TANK

In lieu of a traditional ash pond, bottom ash could be settled out of transport water by using self-supporting, cast-in-place reinforced concrete tanks. This option would feature a series of primary tanks where most of the ash particles would settle. Water from the primary tanks would overflow into a surge tank for settling of the finer ash particles. Like the previous two options, BATW in the surge tank would ultimately be recirculated back to the station to comply with the revised ELG Rule. Cardinal would sluice BATW to one primary tank at a time, switching to an empty tank as a given tank reaches capacity. Equipment would then be used to manually segregate and manipulate the ash in the full tank to promote dewatering. After this initial dewatering, ash would be recovered and transferred to an adjacent concrete pad to completely dewater. Like the pad proposed for the geotextile filter tube option, this dewatering pad would feature appropriate run-off control measures; it would also be sloped such that water drains back to the primary tank. Once the ash is sufficiently dry, it would be loaded onto trucks and disposed of in FAR I Landfill.

While concrete settling tanks have been used to handle bottom ash, this technology, like geotextile filter tubes, poses operational risks in inclement weather. The operation of these tanks and subsequent dewatering of ash collected therein would not be technically feasible during below-freezing weather conditions and excessive rain events. Thus, the Cardinal Operating Company also remove this option from consideration as a replacement for the BAP Complex.

1.3.3.1.4 RETROFITTED BOTTOM ASH POND COMPLEX

Given the existing BAP Complex's compliance with all other parts of the EPA CCR Rule, both the BAP and Recirculation Pond are suitable for future bottom ash disposal provided that they are retrofitted with EPA CCR Rule-compliant liner systems. In this scenario, both ponds would be dewatered and then lined with a composite liner system consisting of a geomembrane underlain by a compacted clay liner with a permeability no greater than 1×10^{-7} cm/sec.

While this retrofit would obtain compliance with the EPA CCR Rule, the Cardinal Operating Company ultimately sought a holistic alternative disposal solution for all waste streams currently managed in the BAP Complex that achieved compliance with both the CCR and ELG Rules (see Section 1.2). Thus, the Cardinal Operating Company expanded the study of this option to evaluate different alternatives for retrofitting both ponds that evaluated factors including, but not limited to, impoundment size, handling of CCR and non-CCR waste streams, and modifications to existing station infrastructure (e.g., BATW and LVW discharge pipes).

In order to comply with the recently-revised ELG Rule, BATW recovered from the reconfigured BAP Complex would need to be recirculated in station operations or diverted to the station's FGD systems prior to being discharged to the Ohio River. Target water quality standards were established for the recirculation water to determine the maximum TSS concentration levels that could be recirculated with minimal impact to the existing pumps and piping in the Recirculation Pumphouse, which would preclude the need for new equipment and thus allow the ponds to be retrofitted quicker. In early 2019, bottom ash samples were collected from various locations within the BAP Complex and subsequently tested. Based on the size distribution and average density of these bottom ash samples, it was determined that the Recirculation Pond's existing footprint was suitable to function as the station's primary and only bottom ash settling pond. After receiving these test results, the Cardinal Operating Company began evaluating whether to segregate the CCR and non-CCR waste streams, developing conceptual design drawings and process flow diagrams, updating the station's water balance to reflect the operational changes, and estimating the capital costs to fund the project.

Given that the existing Recirculation Pond footprint could promote enough sedimentation of the station's bottom ash particles to support recirculation, Cardinal Operating Company evaluated whether to combine both CCR and non-CCR waste streams in the retrofitted ash ponds or to segregate these waste streams. The former would allow the ponds to be retrofitted with minimal impacts to the existing infrastructure and thus would likely be the faster path to overall compliance with the EPA CCR and ELG Rules. However, this option would also prohibit the station from discharging any of its LVW streams since they would be considered BATW pursuant to the ELG Rule. Conversely, segregating these streams would provide the station with the means of discharging its LVW streams as needed but would require additional time to design and construct the infrastructure necessary to segregate the non-CCR waste streams from the CCR waste streams.

Regardless, the Cardinal Operating Company considered both alternatives to be technically feasible options for replacing the BAP Complex.

1.3.3.2 OPTION SELECTED

Ultimately, the Cardinal Operating Company elected to comply with the EPA CCR and ELG Rules by reconfiguring the BAP Complex to separate CCR and non-CCR waste streams. Since the existing Recirculation Pond was determined to have sufficient size to settle out enough bottom ash particles to obtain the target recirculation water quality, this pond will handle only CCR waste streams (BATW) while the existing BAP will handle only non-CCR waste streams (LVW streams). The Recirculation Pond will therefore replace the existing BAP as Cardinal's primary bottom ash disposal facility. Consequently, the BAP Complex's Recirculation Pond will be retrofitted with an EPA CCR Rule-compliant liner system. Meanwhile, the BAP area within the Bottom Ash Pond Complex will be clean closed and then repurposed for use as an LVW storage pond.

In essence, the Cardinal Operating Company has opted to replace the BAP Complex with a multiple technology system that consists of a retrofitted Recirculation Pond and a repurposed BAP that functions as a non-CCR waste water basin.

1.3.3.3 JUSTIFICATION OF OPTION SELECTED

Of the new, permanent on-site disposal alternatives considered to replace the BAP Complex, the multiple technology system selected – retrofit the Recirculation Pond and construct a non-CCR waste water basin in the BAP footprint – is the alternative disposal capacity option that could be implemented the fastest and is technically feasible. As discussed in their respective summaries, geotextile filter tubes and concrete settling tanks would have operational risks during inclement weather, especially during the winter. And while a new ash pond could be constructed on undeveloped land on Cardinal's property, the hilly terrain and distance from the plant would require significant design, permitting, and construction schedules to implement the BATW piping to and from the impoundment, install the composite liner system, and to construct the dams necessary to form a reservoir. Conversely, the multiple technology system selected is taking advantage of the station's existing infrastructure (e.g., transport piping and Recirculation Pumphouse), which reduces design and construction time. Moreover, the construction will be staged to provide alternative disposal capacity for all waste streams currently managed by the BAP Complex as soon as technically feasible. This is discussed in greater detail in Section 3.0.

1.4 CONCEPTUAL DESIGN OF RECONFIGURED BAP COMPLEX

This section describes the conceptual designs for the retrofitted Recirculation Pond and the repurposed BAP. Given the planned operational changes to these ponds and for clarity, the existing BAP and Recirculation Pond areas will be hereafter referred to as the North/LVW Pond and South Pond, respectively.

1.4.1 RETROFITTED SOUTH POND

1.4.1.1 CCR REMOVAL

Cardinal will initiate the retrofit of the South Pond by dewatering the existing pond and subsequently removing any accumulated bottom ash and any contaminated soils from the pond in accordance with 40 CFR 257.102(k)(1)(i). Initial dewatering will be accomplished by lowering the water levels in both the North and South Ponds to a water level that allows continuous operation of the Recirculation Pumphouse. The removed water will be directed to the Ohio River through permitted NPDES Outfall 023 using temporary pumps located along the perimeter dike. In order to fully dewater the South Pond, the current flow from the North Pond will be diverted via a temporary supply pipe connected to the Recirculation Pumphouse; the pipe will also allow the station to continue recovering water from the BAP Complex during the South Pond retrofit work. After the temporary pipe is installed, the South Pond will be dewatered by pumping the water stored therein to the North Pond, which will have the capacity available for this water after the initial dewatering effort, or through the permitted NPDES outfall. Once the dewatering process is complete, all CCR material and CCR-impacted soils will be removed from the pond and processed as required for transportation to and final disposal in FAR I Landfill.

1.4.1.2 COMPOSITE LINER DESIGN

After the CCR and CCR-impacted soils in the South Pond have been removed, the existing partition wall currently dividing the pond will be removed along with the existing water treatment system and its associated equipment. Once the partition wall has been removed, the pond equalization pipe from the North Pond's discharge structure will be removed and sealed in-place two feet below the bottom of the new EPA CCR Rule-compliant liner system.

Conceptually, the South Pond's new composite liner system will consist of (from bottom to top):

- 2-foot-thick clay layer,
- 60-mil high-density polyethylene (HDPE) geomembrane,
- 8-oz/sy non-woven geotextile, and
- A protective layer.

The protective layer installed above the other liner components will vary across the South Pond due to the varying frequency of future dredging operations in each portion of the pond. The northernmost portion of the pond will be dredged every three to five years, while the southernmost portion of the pond will be regularly dredged. The middle portion of the pond is not expected to be dredged. Based on these dredging frequencies, the protective layers in each portion of the pond will be as follows:

- Along the northern most portion:
 - o 8-in.-thick gravel layer, and
 - o 18-in.-thick riprap layer.

- Along the southern most portion:
 - o 4-in.-thick gravel layer, and
 - o 8-in.-thick concrete layer.
- Along the middle of the pond and the new dredge staging and dewatering area:
 - o 8-in.-thick of gravel layer.

The lowest two layers of the composite liner system will comply with the design criteria for composite liners promulgated by the EPA CCR Rule. Pursuant to 40 CFR 257.70(b), a composite liner must be comprised of an upper geomembrane (at least 60-mil thick for HDPE geomembranes) and a lower component consisting of compacted soil that is at least 2-feet thick with a permeability no greater than 1×10^{-7} cm/sec. Accordingly, the lower clay layer will be compacted to ensure its hydraulic conductivity does not exceed this EPA design criterion. The Cardinal Operating Company is also evaluating the potential of substituting geosynthetic clay liner (GCL) for clay materials to achieve this low permeability but is currently planning on using clay as noted.

The purpose of the gravel, riprap, and concrete components in the upper protective layer system is to protect the geomembrane from being damaged by equipment removing CCR from the retrofitted South Pond in the future. Similarly, the geotextile component will protect the geomembrane from tears induced by the sharp, angular aggregate in the protective layer.

1.4.1.3 POND APPURTENANCES

In order to recover CCR stored in the retrofitted South Pond, a new dredge staging and bottom ash dewatering area will be constructed near the new BATW discharge point into the pond. As CCR is dredged from the South Pond, it will be temporarily stored on an area with an EPA CCR Rule-compliant liner to dewater before ultimately being transported to FAR I Landfill for final disposal. In addition, new perimeter berms will be constructed around the dewatering area to contain the water from the moist-to-wet CCR. Any run-off from the area will be directed back towards the retrofitted South Pond.

While the existing bottom ash handling pumps will continue to be used, the jet pumps under the units' bottom ash hoppers will be replaced to accommodate the increased pressure drop from the BATW pipe extension to the retrofitted South Pond. These new pumps will allow for the BATW system velocity to be maintained such that the bottom ash remains in suspension in the transport water as it is conveyed to the retrofitted South Pond. Treated BATW will continue to be recovered and recycled back into plant operations via the Recirculation Pumphouse, and any excess water or blowdown will be fed to the Unit 3 FGD system. The discharge of excess BATW through the Unit 3 FGD system is permitted by the ELG Rule.

1.4.2 REPURPOSED NORTH/LVW POND

After the South Pond has been retrofitted and is operational, the Cardinal Operating Company will begin repurposing the North Pond. Due to the small size of the retrofitted South Pond and the limited volume of

water that can be recovered by the station's FGD system (see Section 1.5.3), the North Pond will need to continue receiving LVW streams even after the South Pond has been retrofitted. In order to repurpose the North Pond while it continues to receive LVW streams from the plant, the pond will be repurposed in two stages: the southern portion first, then the northern portion.

1.4.2.1 CONSTRUCTION OF TEMPORARY LVW IMPOUNDMENT

Before the southern portion of the North Pond can be dewatered, the LVW streams going into the pond need to be isolated from the area. To accomplish this, a temporary impoundment will be constructed near the existing LVW discharge point in the northwest corner of the pond. This impoundment will be constructed by excavating out the bottom ash in the area to form a bowl, with the excavated material used to create a dike separating the area from the rest of the North Pond. Finally, a geomembrane liner will be installed over the bottom ash remaining on the pond floor to keep the LVW streams stored in the temporary impoundment separated from the underlying ash.

1.4.2.2 CCR REMOVAL IN SOUTHERN PORTION

After the temporary LVW impoundment is constructed, the Cardinal Operating Company will initiate closure of the southern portion of the North Pond by dewatering it and subsequently removing any accumulated bottom ash and any contaminated soils from the pond in accordance with 40 CFR 257.102(c). Like the South Pond, all CCR material and CCR-impacted soils removed from this area of the North Pond will be processed as required for transportation to and final disposal in FAR I Landfill. Once the area has been decontaminated, it will be certified as closed and will then be ready to be repurposed as a non-CCR waste water basin.

1.4.2.3 LINER DESIGN

Once the southern portion of the North Pond has been certified as clean-closed, the subgrade will be compacted and smooth-rolled until it is adequate to support the pond's new liner. Because the repurposed pond will not be receiving BATW (or any CCR in general), it will not require the same liner system as the South Pond. Instead, the North Pond's liner system will feature a 60-mil HDPE geomembrane in accordance with the Ohio EPA's liner design criteria. To complete the liner system, an 8-oz/sy non-woven geotextile will be placed above the geomembrane. After the liner system is installed, the southern portion of the North Pond will be available as alternative disposal capacity for the LVW streams currently going into the BAP Complex. Accordingly, Cardinal will then divert all LVW streams from the temporary impoundment to the re-lined southern portion of the North Pond.

1.4.2.4 CCR REMOVAL & RE-LINING OF NORTHERN PORTION

Once the LVW streams are re-directed to the repurposed portion of the North Pond, all the CCR and CCRimpacted material in the remainder of the North Pond will be removed and transported to FAR I Landfill. This area will then be clean-closed per 40 CFR 257.102(c) and subsequently lined with a 60-mil HDPE geomembrane liner in accordance with Ohio EPA requirements. Like the southern portion, an 8-oz/sy nonwoven geotextile will be placed above the geomembrane. After this area has been re-lined, the entire North Pond will be placed into service as the station's LVW Pond (*i.e.*, non-CCR waste basin).

1.4.3 IMPACTS TO STATION WATER BALANCE

Historically, Cardinal has recycled BATW stored in the BAP Complex for use in its wet fly ash-handling systems. Once these systems are converted to dry handling in June 2021, BATW will no longer need to be used for this purpose. Given the selected approach for developing alternative disposal capacity by segregating the station's BATW from its LVW streams, BATW will be recycled to the station in a closed loop system for use in the station's bottom ash-handling system. However, with the future segregation of the ponds within the BAP Complex, some BATW will need to be discharged from the closed-loop system to control the water inventory and chemistry. To accomplish this, a new blowdown line will be installed to transfer some BATW from the retrofitted South Pond to the Unit 3 FGD system. As previously noted, discharge of BATW through the station's FGD system is acceptable per the revised EPA ELG Rule. This flow is expected to provide the 1.84 MGD currently taken from the Unit 3 intake stream to operate the FGD system (Ref. 4).

1.5 EXPLANATION & JUSTIFICATION OF TIME REQUESTED

Per the visual timeline representation and narrative discussion of the project schedule presented in Sections 2.0 and 3.0, respectively, the Cardinal Operating Company is requesting to the EPA allow the South Pond and the North Pond to continue operating until November 30, 2021 and until June 9, 2022, respectively. During this period, the following CCR and non-CCR waste streams would be placed into the BAP Complex since they do not currently have alternative disposal options at Cardinal or offsite:

- Unit 1 and 2 BATW (until November 30, 2021),
- Unit 3 BATW (until November 30, 2021),
- Unit 1 and 2 plant services waste water (until June 9, 2022),
- Unit 3 cooling tower blowdown (until June 9, 2022),
- Unit 3 sump and drain water (until June 9, 2022),
- Coal pile run-off pond overflow (until June 9, 2022), and
- JBR waste water (until June 9, 2022).

As previously stated, metal cleaning waste water will not be placed into the BAP Complex until after the South Pond has been retrofitted.

The Cardinal Operating Company is requesting this additional time to continue operating the BAP Complex because of the need to continue operating the pond to supply water to its wet fly ash-handling systems until FAR II is replaced by a dry system, the time required to secure project funding from the electric cooperatives for which it serves, and the need to continue placing LVW streams into the northern portion of the BAP Complex until a portion of the repurposed LVW Pond is operational. These items are discussed in the following paragraphs. A detailed explanation and justification for the time required to repurpose the BAP Complex, starting with the engineering and design phase, is provided in the narrative of the project schedule in Section 3.0.

Finally, pursuant to the recently-revised alternative closure requirements in the EPA CCR Rule, the Cardinal Operating Company also evaluated whether temporary storage could be provided for the preceding CCR and non-CCR waste streams that will be sent to the BAP Complex until the South Pond is retrofitted and the North Pond is repurposed. This evaluation is summarized in a following paragraph.

1.5.1 WATER SOURCE FOR FLY ASH-HANDLING SYSTEM

Regardless of the option selected to replace the BAP Complex, the BAP Complex would need to remain operational to support Cardinal's fly ash-handling system until it is converted into a dry system. As previously stated, Cardinal recycles water from the Recirculation Pond to sluice its fly ash to FAR II. Without the BAP Complex operating, the station would not be able to sluice to FAR II. Pursuant to the Cardinal Operating Company's corresponding workplan for replacing FAR II, there is currently no alternative disposal capacity for the waste streams currently sent to FAR II. Thus, Cardinal must continue operating FAR II until the new dry fly ash-handling system is online. This system is currently being constructed at the site and is expected to be operational on June 7, 2021. Therefore, the BAP Complex would need to operate until at least June 7, 2021 regardless of the alternative disposal capacity selected to replace it.

1.5.2 PROJECT FUNDING & INITIATION

As part of the study of alternative disposal capacity options to replace the BAP Complex, Cardinal Operating Company developed capital cost estimates to assess the financial requirements for funding the project. These cost estimates were then used to obtain the necessary funding for the project. The alternative disposal capacity project for replacing the BAP Complex could not commence until the appropriate funds were approved and allocated.

In general, funding for environmental compliance projects is not approved until the corresponding environmental regulations are finalized. While this project addresses revisions to the EPA CCR Rule in response to the October 2018 mandate by the U.S. Court of Appeals for the D.C. Circuit that vacated and

remanded provisions allowing unlined CCR surface impoundments like the North and South Ponds to continue operating (Ref. 2), these updates were not finalized by the EPA until late-August 2020. Given the project approval process utilized by the Cardinal Operating Company, it was not possible to initiate procurement and construction of the reconfigured BAP Complex on the basis of forecasted changes to the EPA CCR Rule due to the October 2018 court mandate. However, the Cardinal Operating Company successfully demonstrated the importance of complying with the anticipated changes to the EPA CCR Rule and the limited time available for achieving compliance. Consequently, the Cardinal Operating Company was able to authorize and commence developing alternative disposal capacity for the BAP Complex sooner than typically allowed for environmental compliance projects.

1.5.3 CONTINUED OPERATION OF NORTH POND AFTER SOUTH POND RETROFIT

As shown in the visual timeline representation of the project schedule (Section 2.0) and as described in the corresponding narrative (Section 3.0), alternative disposal capacity will be available for Cardinal's BATW by November 30, 2021 once the South Pond has been retrofitted. However, this pond cannot be used to handle the LVW streams currently going into the North Pond due to its size and the amount of water the station can recover in excess of BATW.

As previously stated, the Cardinal Operating Company determined that the South Pond had adequate area and storage volume to provide the detention time required to remove enough TSS from the BATW for the water to be recirculated into station operations. However, this water quality standard would not comply with the station's existing NPDES permit. Therefore, the station will not be able to discharge the waste water stored in this pond to the Ohio River once it is operational, even before the Ohio EPA incorporates the revised ELG Rule standards for BATW into the station's NPDES permit.

In lieu of discharging directly to the Ohio River from the retrofitted South Pond, the station could send excess water through its FGD system and then discharge it following appropriate treatment. As previously stated in Section 1.4.3, the Cardinal Operating Company plans on recycling 1.84 MGD of BATW from the retrofitted South Pond to operate the Unit 3 FGD system. However, this is the maximum volume of water that can be handled by the FGD system. Consequently, additional water placed into the retrofitted South Pond beyond BATW could not be discharged through the FGD system.

Given that the station would not be able to discharge water from the retrofitted South Pond directly to the Ohio River due to high TSS concentrations or to the Unit 3 FGD system due to its operating limits, sending the subject LVW streams to the retrofitted South Pond in addition to the station's BATW would put the pond at risk of overtopping. This would be considered an uncontrolled released of BATW from the impoundment in violation of the station's NPDES permit. Consequently, LVW streams need to continue being discharged into the North Pond until it has been repurposed as a non-CCR waste water basin, even after the South Pond has been retrofitted with an EPA CCR Rule-compliant composite liner system.

1.5.4 TEMPORARY DISPOSAL OF WASTE STREAMS

The Cardinal Operating Company considered two temporary disposal solutions for the CCR and non-CCR waste streams that will continue to be sent to the BAP Complex until the retrofitted South Pond and repurposed North Pond are operational on November 30, 2021 and June 9, 2022, respectively: tanks and water treatment trailers.

1.5.4.1 STORAGE TANKS

Based on the Cardinal Operating Company's current forecast of obtaining permanent alternative disposal capacity to replace the BAP Complex, enough tanks would need to be procured and installed at the site to provide approximately one years' worth of storage for the BATW produced by the plant for approximately one year. Similarly, the station would need to install enough tanks to provide about 1.5 years' worth of storage for the non-CCR waste water produced by the plant. Given average daily inflows of 4.14 and 7.98 MGD of CCR and non-CCR waste water into the BAP Complex (see Table 1), these temporary tanks would need to provide almost 5.9 billion gallons-worth of storage. It is not technically feasible to install the number of tanks required to provide this storage capacity until the BAP Complex is reconfigured. Less storage capacity would be required if the tank contents could be regularly discharged or recirculated, but the tanks would need to be large enough to promote sedimentation of the TSS in the waste streams. The number and size of these tanks could be controlled if the waste could be transported off-site, but the logistics required for off-site transport, even if off-site disposal capacity was available, also make this temporary solution technically infeasible (see Section 1.3.2).

1.5.4.2 WASTE WATER TREATMENT TRAILERS

While it is technically infeasible to use tanks to temporarily store and/or treat the large CCR and non-CCR flows currently going into the BAP Complex, waste water treatment trailers from a vendor that specializes in such technology may be capable of treating the BATW and non-CCR waste streams currently being sent to the BAP Complex. These trailers can remove TSS from and neutralize the pH in waste streams, among other treatment capabilities. The amount of waste water a trailer can treat is dependent on the water chemistry, but 1 MGD is generally achievable.

Given an average daily inflow of 12.1 MGD, it would take about 12 waste water treatment trailers to handle and treat the CCR and non-CCR waste streams currently going into the BAP Complex. While it may be feasible to find space on the plant site for 12 trailers, the implementation of this temporary system would require time to perform the engineering and design of piping to and from the trailers, modifications to Cardinal's NPDES permit, and installation of the system itself. Moreover, it should be recognized that there is only a limited number of these waste water treatment trailers available. Assuming Cardinal is able to procure 12 waste water treatment trailers, they could not be installed near the BAP Complex given the limited open space available and the need to provide unimpeded access to the site to the contractor in charge of reconfiguring the BAP Complex. Assuming the station can allocate enough space near Unit 3 for 12 waste water treatment trailers (about 1,500 feet away from the current discharge point into the BAP Complex), it is expected that at least three months would be required to perform the necessary engineering and design work to divert the subject waste streams to the waste water treatment trailers and then route effluent from the trailers to an NPDES-permitted outfall. More design time would likely be necessary if any or all of the waste water treatment trailers had to be sited near FAR I Landfill due to space restrictions at the plant. Because the handling and treatment of these waste streams is being changed, the Cardinal Operating Company would need to modify its existing NPDES permit with the Ohio EPA, it would be expected to take approximately six months to get this permit modification finalized. It would likely take another two months to install and commission this temporary system, assuming a contractor has already been procured by the time the modified NPDES permit is issued by the Ohio EPA.

Based on the preceding analysis, it is anticipated that the fastest feasible timeframe for which this temporary system could be designed, permitted, and installed is approximately 10 months. Therefore, if Cardinal were to proceed with implementing this temporary option for the waste streams currently going into the BAP Complex, it is anticipated that this system would be operational by September of 2021.

Although temporary waste water treatment tanks may provide a faster compliance timeline for the subject CCR and non-CCR waste streams by about two months and nine months, respectively (the retrofitted South Pond and the repurposed North Pond will be operational by November 30, 2021 and by June 9, 2022, respectively), it does not align with the Cardinal Operating Company's goal of developing a holistic solution that complies with both the EPA CCR and ELG Rules. Implementation of this temporary solution would only provide a temporary means for compliance with the EPA CCR and ELG Rules and would involve mobilization of additional construction traffic and resources to establish a temporary solution when a permanent one will be available a few months later. In general, the Cardinal Operating Company does not consider treating this volume of non-CCR waste streams in this manner an acceptable long-term means of compliance with the ELG Rule.

The alternative disposal capacity selected by the Cardinal Operating Company will ultimately bring Cardinal's BAP Complex into full compliance with both the EPA CCR and ELG Rules, and the reconfigured BAP Complex will allow Cardinal to permanently separate the CCR and non-CCR waste streams therein. As the EPA states in its preamble to the recent revisions to its CCR Rule (Ref. 10, p. 53536), "[T]here are many technical reasons that a facility might select one approach over another that have nothing to do with cost or convenience. For example...if a facility is trying to comply with multiple EPA regulations or moving away from the commingling of CCR and non-CCR waste streams, adopting a multiple technology approach may

ultimately result in faster compliance overall, even if individual components could theoretically be adopted sooner."

Based on the preceding analysis, the Cardinal Operating Company does not consider temporary waste water treatment trailers to be in line with its goal of developing a holistic solution that brings the BAP Complex in compliance with both the EPA and ELG Rules or the intentions of the EPA when developing the revised alternative closure provisions for its CCR Rule. However, to preclude the interaction of LVW streams with bottom ash stored in the North Pond once the retrofitted South Pond starts receiving BATW, the Cardinal Operating Company plans to limit the area in which LVW will be placed in the non-compliant North Pond. Moreover, this limited area will be lined with a temporary geomembrane liner to minimize contact between LVW water and the bottom ash in this area.

2.0 PROJECT SCHEDULE: VISUAL TIMELINE

This section presents a visual timeline representation of the Cardinal Operating Company's schedule for retrofitting the South Pond in the BAP Complex and subsequently repurposing the North Pond as a non-CCR waste basin. Pursuant to 40 CFR 257.103(f)(iv)(1)(A)(2), the following visual timeline representation of the project schedule shows:

- How each phase and the steps within that phase interact with or are dependent on each other and the other phases,
- All of the steps and phases that can be completed concurrently,
- The total time needed to retrofit the South Pond and to repurpose the North Pond as a non-CCR waste basin.

As shown in its visual timeline representation, the project schedule is divided into the following phases:

- Engineering & Design;
- Procurement (Contractor Selection);
- Procurement (Equipment Fabrication & Delivery); and
- Construction, Startup, & Implementation.

See Section 3.0 for the corresponding narrative discussion of the project schedule.

	ottom Ash Detailed Design	-			Monthly Report							1-CRD-BA0				_				-20 17:16
Activity ID	Activity Name	Rem Duration	Activity % Start	Finish	3 Sep Oct Nov Dec	Jan Feb M	lar Apr Ma	202 iy Jun	-	Sep Oc	Nov Dec	Jan Feb I	Mar Apr May	2021 Jun Ju	Aug Se	p Oct	Nov Dec	Jan Feb Ma	2022 ar Apr May Jun	Jul Aug
D-BA0 Card	dinal Level 3 Bottom Ash Detailed Design	498	21-Sep-19 A	29-Aug-22									P							
RD-BA0.67	Milestones	319	20-Apr-20 A	29-Aug-22																
MS100	Engineering Start	0	100% 20-Apr-20 A				8													
MS110	Start Construction	0	0% 27-May-21																	
MS115	CCR Compliance Documents - Final Certification	0	0%	30-Nov-21*													- \$- 1			
MS120	Modification Complete	0	0%	29-Aug-22*																
CRD-BA0.1 O	Outage Schedule	388	21-Sep-19 A	23-Oct-21																
CRD-BA0.1.24		219	21-Sep-19 A	23-Oct-21																
OUTU1.001	2019 Fall Outage 0	0	100% 21-Sep-19 A	29-Sep-19 A																
OUTU1.002	2020 Spring Outage 40	0	100% 07-May-20 A	-					┈╫┊┾╶╻	-										
OUTU1.003 OUTU1.004	2020 Fall Outage 10 2021 Spring Outage 9	0	100% 31-Aug-20 A 0% 19-Mar-21	09-Sep-20 A 27-Mar-21								<u>i i i</u>	►□◄							
OUTU1.004	2021 Fall Outage 23	23	0% 19-Mar-21	23-Oct-21									٩		ר <u>י</u> ריד	► <				
CRD-BA0.1.25		376	19-Oct-19 A	11-Oct-21																
OUTU2.001	2019 Fall Outage 0	0	100% 19-Oct-19 A	18-Nov-19A	┝╼══															
OUTU2.002	2020 Spring Outage 0	0	100% 04-Apr-20 A	13-Apr-20 A					····	****										
OUTU2.003	2020 Fall Outage 9	4	0% 26-Sep-20 A	04-Oct-20	1					: •										
OUTU2.004	2021 Spring Outage 59	59	0% 27-Mar-21	24-May-21]															
OUTU2.005	2021 Fall Outage 10	10	0% 02-Oct-21	11-Oct-21												►∎◄				
	Unit No 3	360	05-Oct-19 A	04-Oct-21																
OUTU3.001	2019 Fall Outage	0	100% 05-Oct-19 A	14-Oct-19 A	•															
OUTU3.002	2020 Spring Outage	0	100% 18-Apr-20 A	27-Apr-20 A																
OUTU3.003	2020 Fall Outage	24 10	0% 10-Oct-20* 0% 01-May-21*	02-Nov-20 10-May-21									·► <mark>∎</mark> ◄							
OUTU3.004 OUTU3.005	2021 Spring Outage 2021 Fall Outage	10	0% 01-May-21 0% 25-Sep-21*	04-Oct-21																
	Engineering & Design	412	27-Apr-20 A	29-Apr-22																
CRD-BA0.69.1		399	27-Apr-20 A	29-Apr-22																
	1.24 Design Basis/Criteria	0	27-Apr-20 A																	
	Design Basis/Criteria - Prepare & Review	0	100% 27-Apr-20 A	13-May-20 A			┊╞╋╞┓													
GEN1000000.20	Design Basis/Criteria - S&L Prepare & Submit Package to Cardinal	0	100% 14-May-20 A	20-May-20 A			┈┈╵╵╴													
	5 Design Basis/Criteria - Cardinal review	0	100% 21-May-20 A	-																
	Design Basis/Criteria - Issue for Use	0	100% 01-Jun-20 A	-																
	1.25 General Arrangements General Arrangements - Prepare & Review	<u>59</u> 0	11-May-20 A 100% 11-May-20 A																	
	6 General Arrangements - Peer Review	0	100% 03-Jun-20 A	03-Jun-20 A																
	General Arrangements - S&L Prepare & Submit Package to Cardinal	0	100% 04-Jun-20 A	16-Jun-20 A																
	5 General Arrangements - Cardinal review	0	100% 17-Jun-20 A																	
GEN200000.30	General Arrangements - Issue for Use	0	100% 03-Aug-20 A	14-Aug-20 A					∥⊧∎											
GEN2000000.60) General Arrangements - Final Issue	59	0% 01-Sep-20 A	28-Dec-20					- •		<u> </u>	■≠┘┊│┊								
	1.26 Update Project Cost Estimate	3	17-Aug-20 A																	
	Update Project Cost Estimate - Prepare & Review	0	100% 17-Aug-20 A																	
	Update Project Cost Estimate - S&L Prepare & Submit Package to Cardinal	0	100% 15-Sep-20 A							┆ <mark>╺┝</mark> ┫┥ ╞┥ <mark>╝</mark> ┥										
	5 Update Project Cost Estimate - Cardinal review	0	100% 22-Sep-20 A																	
	Update Project Cost Estimate - Issue for Use 1.2 CCR Semi-Annual Progress Report #1	3 46	0% 29-Sep-20 A 26-Feb-21	05-Oct-20 30-Apr-21																
-	CCR Semi-Annual Progress Report #1 CCR Semi-Annual Progress Report #1 - Prepare & Review	16	0% 26-Feb-21*	19-Mar-21					┄╌╂╂┠┊╊┠╌┠╌											
	CCR Semi-Annual Progress Report #1 - S&L Prepare & Submit Package to Cardinal	10	0% 22-Mar-21	02-Apr-21	1								┝╼╗╡							
	5 CCR Semi-Annual Progress Report #1 - Cardinal review	10	0% 05-Apr-21	16-Apr-21	1								┕╼┓╸							
GEN4000000.30	CCR Semi-Annual Progress Report #1 - Issue for Use	10	0% 19-Apr-21	30-Apr-21	11 1 1								╘╾═╡⋖	{ {	, 11					
Terrare and the second s	1.3 CCR Semi-Annual Progress Report #2	43	31-Aug-21	29-Oct-21												-				
	CCR Semi-Annual Progress Report #2 - Prepare & Review	13	0% 31-Aug-21*	17-Sep-21																
	CCR Semi-Annual Progress Report #2 - S&L Prepare & Submit Package to Cardinal	10	0% 20-Sep-21	01-Oct-21											TI II					
ļ	CCR Semi-Annual Progress Report #2 - Cardinal review CCR Semi-Annual Progress Report #2 - Issue for Use	10 10	0% 04-Oct-21 0% 18-Oct-21	15-Oct-21 29-Oct-21												╘╾═				
	1.4 CCR Semi-Annual Progress Report #3	45		29-Oct-21 29-Apr-22																
		40	2017 60-22	25 Apr-22			: [];	1						i 	: : !!	ļi.		: : : :		
Remainin	ng Level of Effort 🔶 🔶 Milestone						Page 1 c	of 8										1	6	
Actual W	/ork				Engineering, F	Procureme	nt & Cor	nstruc	ction Se	chedule	by WB	S								
Remainin	ng Work										-						Sa	rgent &	Lundy	
	lemaining Work																			
◆ Baseline	-																			
														I						

Activity ID	tom Ash Detailed Design	Rem	Activity % Start	Finish		2020						
<u></u>		Duration	Complete		9 Sep Oct Nov Dec Jan Fe	eb Mar Apr May Jun Jul Aug	Sep	Oct	Nov Dec	Jan F	eb Mar	A
	CCR Semi-Annual Progress Report #3 - Prepare & Review	15	0% 28-Feb-2									1
GEN600000.20	CCR Semi-Annual Progress Report #3 - S&L Prepare & Submit Package to Cardinal	10	0% 21-Mar-2	•								1
GEN600000.25	CCR Semi-Annual Progress Report #3 - Cardinal review	10	0% 04-Apr-22	•								1
GEN600000.30	Semi-Annual Progress Report #3 - Issue for Use	10	0% 18-Apr-22	· · ·								
	1 Design Review	1	03-Sep-2									ļ
DR25	25% Design Review	0	100% 03-Sep-2	· ·			7					ļ.
DR60	60% Design Review	1	0% 24-Nov-2									1
CRD-BA0.69.2 (304	15-Jun-20									1
	1 Civil General Notes & Details	<u>118</u> 40	19-Oct-20									1
CIVIL01000.10	Civil General Notes & Details - Prepare & Review		0% 19-Oct-20									
CIVIL01000.30	Civil General Notes & Details - Bid Issue	10	0% 16-Dec-2							• 		
CIVIL01000.60	Civil General Notes & Details - Construction Issue	20	0% 11-Mar-2									-
	2 Temporary Erosion Control	130	01-Oct-20									-
CIVIL01005.10	Temporary Erosion Control - Prepare & Review	60	0% 01-Oct-20							<u>.</u>		į.
CIVIL01005.30	Temporary Erosion Control - Bid Issue	10	0% 30-Dec-2									<u>.</u>
CIVIL01005.60	Temporary Erosion Control - Construction Issue	20	0% 11-Mar-2								F	-
	3 Pond Lining Drawings	130	22-Sep-2									1
CIVIL02000.10	Pond Lining drawings - Prepare & Review	33	0% 22-Sep-2									i
CIVIL02000.30	Pond Lining drawings - Bid Issue	10	0% 16-Dec-2									<u>.</u>
CIVIL02000.60	Pond Lining drawings - Construction Issue	20	0% 11-Mar-2	1 07-Apr-21								5
	4 Civil Sitework Demo Drawings	118	19-Oct-20									-
CIVIL02005.10	Civil Sitework Demo Drawings - Prepare & Review	40	0% 19-Oct-20									į.
CIVIL02005.30	Civil Sitework Demo Drawings - Bid Issue	10	0% 16-Dec-2	0 31-Dec-20						•••••••		
CIVIL02005.60	Civil Sitework Demo Drawings - Construction Issue	20	0% 11-Mar-2	1 07-Apr-21								5
	5 Roads and Paving	118	19-Oct-20						<u> </u>			ļ
CIVIL03000.10	Roads and Paving - Prepare & Review	40	0% 19-Oct-20	0 15-Dec-20								į.
CIVIL03000.30	Roads and Paving - Bid Issue	10	0% 16-Dec-2	0 31-Dec-20						.		÷
CIVIL03000.60	Roads and Paving - Construction Issue	20	0% 11-Mar-2	1 07-Apr-21								5
	10 PTI for Pond Retrofit Permitting	152	21-Aug-2									-
CIVIL06005.10	PTI for Pond Retrofit Permitting - Prepare & Review	17	0% 21-Aug-2									ļ
CIVIL06005.20	PTI for Pond Retrofit Permitting - S&L Prepare & Submit Package to Cardinal	5	0% 26-Oct-20	0 30-Oct-20								Ì
CIVIL06005.25	PTI for Pond Retrofit Permitting - Submittal to Ohio EPA	1	0% 01-Dec-2	0* 01-Dec-20					••••			
CIVIL06005.30	PTI for Pond Retrofit Permitting - Expected Approval	0	0%	01-May-21*								-
CRD-BA0.69.2.	11 ODNR Dam Modification Permit Support	152	07-Aug-2	0 A 01-May-21								1
CIVIL07000.10	ODNR Dam Modification Permit Support - Prepare & Review	17	0% 07-Aug-2	0 A 23-Oct-20								
CIVIL07000.20	ODNR Dam Modification Permit Support - S&L Prepare & Submit Package to Cardinal	5	0% 26-Oct-20	0 30-Oct-20					4			
CIVIL07000.25	ODNR Dam Modification Permit Support - Submittal to ODNR	1	0% 01-Dec-2	0* 01-Dec-20					•			
CIVIL07000.30	ODNR Dam Modification Permit Support - Expected Approval	0	0%	01-May-21*								-
CRD-BA0.69.2.	19 CCR Work Plan Study	41	15-Jun-20	0 A 30-Nov-20								ļ.
CIVIL18000.10	CCR Work Plan Study - Prepare & Review	11	0% 15-Jun-20	0 A 15-Oct-20					-			
CIVIL18000.20	CCR Work Plan Study - S&L Prepare & Submit Package to Cardinal	10	0% 16-Oct-20	0 29-Oct-20				۴	◀			
CIVIL18000.25	CCR Work Plan Study - Cardinal review	10	0% 30-Oct-20	0 12-Nov-20				4-0	-			1
CIVIL18000.30	CCR Work Plan Study - Issue for Use	10	0% 13-Nov-2	0 30-Nov-20					▶			
CRD-BA0.69.2.	20 NPDES Modifications Permitting	152	01-Sep-2	0 A 01-May-21								1
CIVIL19000.10	NPDES Modification Permitting - Prepare & Review	11	0% 01-Sep-2									1
CIVIL19000.20	NPDES Modification Permitting - S&L Prepare & Submit Package to Cardinal	10	0% 16-Oct-20			······································		┡	-			
CIVIL19000.25	NPDES Modification Permitting - Submittal to Ohio EPA	1	0% 01-Dec-2						-			Ì
CIVIL19000.30	NPDES Modification Permitting - Expected Approval	0	0%	01-May-21*	-							
	21 Construction SWPPP Permitting	65	01-Feb-2	-								1
CIVIL20000.10	Construction SWPPP Permitting - Prepare & Review	6	0% 01-Feb-2									1
	Construction SWPPP Permitting - S&L Prepare & Submit Package to Cardinal	5	0% 09-Feb-2			····························	·+++++++++++++++++++++++++++++++++++++			-		
CIVIL20000.20	Construction SWPPP Permitting - Submittal to Ohio EPA	1	0% 00 r 00 2								-	1
CIVIL20000.20	Sonor dotton Own FT FT ormitting - Submitted to Onio LLA	0			-							<u>+</u>
CIVIL20000.25	Construction SWPPP Permitting - Expected Approval	. 0	0%	01-May-21*								-
CIVIL20000.25 CIVIL20000.30	Construction SWPPP Permitting - Expected Approval		07.4		<u></u> I _ I _ I _ I _ I _ I _ I _ I _							
CIVIL20000.25 CIVIL20000.30 CRD-BA0.69.2.	22 CCR Complaince Documentation: Loc Restrictions, Dsg & Operating Criteria,	294	07-Aug-2			·····································					يليون الم	-
CIVIL20000.25 CIVIL20000.30			07-Aug-2 0% 07-Aug-2 0% 20-Sep-2	0 A 17-Sep-21								

Actual Work

- Remaining Work

 - Critical Remaining Work

Baseline Milestone

►

Page 2 of 8 Engineering, Procurement & Construction Schedule by WBS

201	74						_								t-20	17	:16		
202 In	Jul	Aug	S	ер	Oct	Nov	D	ес	Jan	Feb	Mar	Apr	20 May	22 Jun	Jul	Au	ug l	Sep	Oct
										-		•							
											Ļ	∎-							
												└╼─	<						
					1														
					1														
			+																
					1														
·			- C																
1																:			
											7								
							-			0	1								
							9	d	ge		2	LU	ndy	y					
										1									
	1																		

al Level 3 Bottom Ash Detailed Design Activity ID Activity Name	Rem	Activity % Start	Finish		2020
	Duration	Complete		J Sep Oct Nov Dec Jan Feb Mar Apr May Jur	Jul Aug Sep Oct Nov Dec Jan Feb Mar /
CIVIL21000.25 CCR Compliance Documentation - Cardinal review	20	0% 18-Oct-21	12-Nov-21		
CIVIL21000.30 CCR Compliance Documentation - Issue for Use	10	0% 15-Nov-21	30-Nov-21		
CRD-BA0.69.2.65 Vndr Dwgs - Topographic & Bathymetric survey VTOPO00005.70 Topographic & Bathymetric survey - Mobilize	0	20-Jul-20 A 100% 20-Jul-20 A	21-Sep-20 A 24-Jul-20 A		
VTOPO00005.75 Topographic & Bathymetric survey - Perform Mapping	0	100% 20-Jul-20 A	07-Aug-20 A	<u> </u>	╶┊┼╽ <mark>╔╪╧╗╤</mark> ╢╴┊┼╎┼╶┝╁╶┍┝╺╌╿╴╴╸╴╸╸╸╴╴╴╴╴╴╴╴╴╴╴
VTOPO00005.75 Topographic & Bathymetric survey - Periorin Mapping VTOPO00005.85 Topographic & Bathymetric survey - Review Report	0	100% 27-Jui-20 A	28-Aug-20 A		
VTOPO00005.80 Topographic & Bathymetric survey - Neview Report VTOPO00005.80 Topographic & Bathymetric survey - Submit Report	0	100% 17-Aug-20 A	28-Aug-20 A 31-Aug-20 A		
	0	-	-		
VTOPO00005.90 Topographic & Bathymetric survey - Final Report	-	100% 31-Aug-20 A	21-Sep-20 A		
CRD-BA0.69.20 Structural	130 118	29-Jul-20 A 19-Oct-20	07-Apr-21 07-Apr-21		·┊┤┨┨╴╣╴╌┫┙┊┨╌┨╸┝┨╴┑┥╺┨╴╴┊╴┨╶╴┊╴╸╸╸╸╸╸
CRD-BA0.69.20.56 Concrete General Notes & Details STR0100000.10 Concrete General Notes & Details - Prepare & Review	40	0% 19-Oct-20	15-Dec-20		
STR010000.30 Concrete General Notes & Details - Bid Issue	10	0% 16-Dec-20	31-Dec-20		
STR010000.60 Concrete General Notes & Details - Construction Issue	20	0% 10 Dec 20	07-Apr-21		
CRD-BA0.69.20.57 Modify Outfall 023 Structure	20	19-Oct-20	07-Apr-21		
STR020000.10 Modify Outfall 023 Structure - Prepare & Review	40	0% 19-Oct-20	15-Dec-20	┫╴┊╶╶╌╴┊╶╌╴┊╶╴╴╴┊╶╴╴╴┊╶╴╴╴┊╶╴╴╴┊╶╴╴╴┊	·┊┼╂╴╬╶╫┊┼┼╶╊ <mark>╼┢╧╋╧╧</mark> ╶┊╌┠╶┊╴╴╸ <mark>┠</mark> ┊╴
STR020000.30 Modify Outfall 023 Structure - Bid Issue	10	0% 16-Dec-20	31-Dec-20		
STR020000.60 Modify Outfall 023 Structure - Construction Issue	20	0% 10-Dec-20	07-Apr-21		
CRD-BA0.69.20.58 Pipe Road Crossing Trenches	130	21-Sep-20 A	07-Apr-21		
STR030000.10 Pipe Road Crossing Trenches - Prepare & Review	52	30% 21-Sep-20 A	15-Dec-20	¶: : : : : : : ! ! ! ! ! ! ! ! ! ! ! ! !	┊║║║║╘ <mark>┥<mark>┥┧╶┿╤╄╼╧╼</mark>╕┊┃┊┊╴┊╴<mark>╿</mark>┊</mark>
STR030000.30 Pipe Road Crossing Trenches - Bid Issue	10	0% 16-Dec-20	31-Dec-20	<u> </u>	·┊┼╢╴╬╶╟┊╌╎╌╫╶┼┊╴╢╴╴ <mark>╘╧╧╧╡</mark> ╶┊┊╴╴╸┥╴╴ <mark>┼</mark>
STR030000.60 Pipe Road Crossing Trenches - Construction Issue	20	0% 10-Dec-20	07-Apr-21		
CRD-BA0.69.20.59 Foundations - Misc. Pads and Pipe Supports	73	01-Sep-20 A	07-Apr-21		
STR040000.10 Foundations - Misc. Pads and Pipe Supports - Prepare & Review	0	100% 01-Sep-20 A	29-Sep-20 A		
STR040000.30 Foundations - Misc. Pads and Pipe Supports - Bid Issue	5	0% 23-Dec-20	31-Dec-20		
STR040000.60 Foundations - Misc. Pads and Pipe Supports - Dia Issue	20	0% 23-Dec-20	07-Apr-21	┨╴╡╌╌╌╴╡╌╌╌╴╡╌╌╌╴╡╌╌╌╴╡╌╌╌╴╡╌╌╴╴╡╴┨┨╴╡╌╌╌╸	╶┊┤╴╢╴╬╶╴╢╴╬╴╴┥╺╞┨╶╴┊╶╴╴╴╴╴╴╴╴╴╴╴╴╴╴╴╴╴
CRD-BA0.69.20.60 Pumphouse Bulikheads	130	01-Sep-20 A	07-Apr-21		
STR0500000.10 Pumphouse Bulkheads - Prepare & Review	130	0% 01-Sep-20 A	27-Oct-20*	¶	
STR050000.30 Pumphouse Bullkheads - Bid Issue	10	0% 16-Dec-20	31-Dec-20		
STR050000.60 Pumphouse Bulkheads - Construction Issue	20	0% 10 Dec 20	07-Apr-21		
CRD-BA0.69.20.61 Structural Steel - Pipe supports and Auxiliary steel	130	01-Sep-20 A	07-Apr-21	┫-┪┥┥┥┥┥┥-	╺┊┼╏╢╴╬╌╴╟╴┊╌╎╴┊┟╶╴┝┊╴╽╴╴┊╴╴╴╴┊╴┠╶╶┊┊╴╴╴╴╡╸╴╴╴ <mark>╴</mark> ┦╴
STR0600000.10 Structural Steel - Pipe supports and Auxiliary steel - Prepare & Review	29	0% 01-Sep-20 A	10-Nov-20*		
STR0600000.30 Structural Steel - Pipe supports and Auxiliary steel - Bid Issue	10	0% 16-Dec-20	31-Dec-20		
STR0600000.60 Structural Steel - Pipe supports and Auxiliary steel - Construction Issue	20	0% 11-Mar-21	07-Apr-21		
CRD-BA0.69.20.52 Civil/Structural Walkdowns	35	29-Jul-20 A	18-Nov-20		
STR0700000.00 Civil/Structural Walkdowns - Summary	35	0% 29-Jul-20 A	18-Nov-20		╴┊┤╴ <mark>╢╋╴╬┥╌╢╸┆╌╴┥╌╎┥╶╎┥╴╌┥╌</mark> ┨╴╴┥╴╴╴╴┥╴┨╶┊┊╴╴╴╡╴╴╴ <mark>┨</mark> ┊╴
CRD-BA0.69.3 Mechanical	130	04-May-20 A	07-Apr-21		
CRD-BA0.69.3.31 Mechanical General Notes & Details	130	21-Aug-20 A			
MECH010000.10 Mechanical General Notes & Details - Prepare & Review	12	0% 21-Aug-20 A	16-Oct-20]	┊╎║┊╟ <mark>╤╤╤╪╪</mark> ╪╬╌╎╌╌┊╌╴╴┊╴┃┊┊┊┊╴┃
MECH010000.30 Mechanical General Notes & Details - Bid Issue	10	0% 16-Dec-20	31-Dec-20	1	
MECH010000.60 Mechanical General Notes & Details - Construction Issue	20	0% 11-Mar-21	07-Apr-21		
CRD-BA0.69.3.32 Demo drawings - BATW piping	118	19-Oct-20	07-Apr-21		
MECH010005.10 Demo drawings - BATW piping - Prepare & Review	40	0% 19-Oct-20	15-Dec-20		┊╎║┊║┊╎╟╧╇╬┾╤╤╌┊╷┨┊┊┊┊╏┊
MECH010005.30 Demo drawings - BATW piping - Bid Issue	10	0% 16-Dec-20	31-Dec-20	1	
MECH010005.60 Demo drawings - BATW piping - Construction Issue	20	0% 11-Mar-21	07-Apr-21	1	
CRD-BA0.69.3.34 Demo drawings - LVW piping	118	19-Oct-20	07-Apr-21		······································
MECH020005.10 Demo drawings - LVW piping - Prepare & Review	40	0% 19-Oct-20	15-Dec-20		
MECH020005.30 Demo drawings - LVW piping - Bid Issue	10	0% 16-Dec-20	31-Dec-20	1	
MECH020005.60 Demo drawings - LVW piping - Construction Issue	20	0% 11-Mar-21	07-Apr-21	1	::::::::::::::::::::::::::::::::::::::
CRD-BA0.69.3.4 Demo drawings - Metal Cleaning Waste Tank Facility	118	19-Oct-20	07-Apr-21		
MECH021005.10 Demo drawings - Metal Cleaning Waste Tank Facility - Prepare & Review	40	0% 19-Oct-20	15-Dec-20		
MECH021005.30 Demo drawings - Metal Cleaning Waste Tank Facility - Bid Issue	10	0% 16-Dec-20	31-Dec-20		
MECH021005.60 Demo drawings - Metal Cleaning Waste Tank Facility - Construction Issue	20	0% 11-Mar-21	07-Apr-21	1	· ;]]]] ·] ·]]]]] · · ·]] ·
CRD-BA0.69.3.5 Demo drawings - Chemical Treatment System	130	17-Aug-20 A	07-Apr-21		
MECH022005.10 Demo drawings - Chemical Treatment Systemy - Prepare & Review	8	0% 17-Aug-20 A	12-Oct-20		
MECH022005.30 Demo drawings - Chemical Treatment System - Bid Issue	10	0% 16-Dec-20	31-Dec-20		
MECH022005.60 Demo drawings - Chemical Treatment System - Construction Issue	20	0% 11-Mar-21	07-Apr-21	1	
CRD-BA0.69.3.36 P&ID - Symbol Sheet	40	04-May-20 A	07-Apr-21		
Remaining Level of Effort				Page 3 of 8	
Actual Work				Engineering, Procurement & Constru	ction Schedule by WBS
Remaining Work					
Critical Remaining Work					

202	21												20		:t-20	17	:16	;		
	Jul	Aug	Se	ep	Oct	Nov	D	ec	Jan	Feb	Mar	Apr	May		Jul	Au	g	S	ер	Oct
																	1			
_			_								1		_				_			
							s	a	rge	ent		Lu	ndy	y						
)	1									


Activity ID	Activity Name	Rem	Activity % Start	Finish	2020	0	0000
		Duration	Complete				021 2022 Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug
MECH040000.10	P&ID - Symbol Sheet - Prepare & Review	0	100% 04-May-20 A	31-Jul-20 A			
MECH040000.16	P&ID - Symbol Sheet - Peer Review	0	100% 03-Aug-20 A	04-Aug-20 A			
MECH040000.20	P&ID - Symbol Sheet - S&L Prepare & Submit Package to Cardinal	0	100% 05-Aug-20 A	11-Aug-20 A			
MECH040000.25	P&ID - Symbol Sheet - Cardinal review	0	100% 12-Aug-20 A	25-Aug-20 A			
MECH040000.30	P&ID - Symbol Sheet - Design Issue	0	100% 26-Aug-20 A	09-Sep-20 A		╘╫╈╤╕╃╵╷╌╷╎╬╌┝╶╌┊╌┫╌╬┥╌╌╴╴╸╸	
MECH040000.60	P&ID - Symbol Sheet - Construction Issue	40	0% 11-Feb-21	07-Apr-21			
	37 P&ID - Blowdown to FGD P&ID - Blowdown to FGD - Prepare & Review	40	04-May-20 A	-		<u></u> ··· <mark>·</mark> ·····	
		0	-	31-Jul-20 A			
	P&ID - Blowdown to FGD - Peer Review	0	100% 03-Aug-20 A	-			
	P&ID - Blowdown to FGD - S&L Prepare & Submit Package to Cardinal	0	100% 05-Aug-20 A	-			
	P&ID - Blowdown to FGD - Design Issue	0	100% 03-Aug-20 A	-			
	P&ID - Blowdown to FGD - Cardinal review	0	100% 14-Aug-20 A	•			······································
	P&ID - Blowdown to FGD - Construction Issue	40		07-Apr-21			
	38 P&ID - Existing system tie-ins (Recirc System) P&ID - Existing system tie-ins (Recirc System) - Prepare & Review	40 0	04-May-20 A 100% 04-May-20 A				
	P&ID - Existing system tie-ins (Recirc System) - Peer Review	0	100% 03-Aug-20 A				
	P&ID - Existing system tie-ins (Recirc System) - S&L Prepare & Submit Package to C	0	100% 05-Aug-20 A				
	P&ID - Existing system tie-ins (Recirc System) - Sac Trepare & Submit Fackage to C	0	100% 03-Aug-20 A	<u> </u>	┨╒╌╌╴╡╌╌╴╡╌╌╴╡╌╴╴╡╴╴╴╡╴╴╴╡╴╴╴╡╴┠┨╡╌╴╴╴╡╿┨	│ <mark>──────</mark> ──┤╷╷╷╷╷╷╷╷	
	P&ID - Existing system tie-ins (Recirc System) - Design Issue	0	100% 14-Aug-20 A 100% 28-Aug-20 A	-			
	P&ID - Existing system tie-ins (Recirc System) - Construction Issue	40	0% 11-Feb-21	07-Apr-21		│┊║┊ <mark>┞┼┼╢║┼┊┊┼╢┊_┝┲╧┲╧╧┥</mark> ┊│	
	39 P&ID - Existing system tie-ins (BATW U1-2)	40	04-May-20 A				
	P&ID - Existing system tie-ins (BATW U1-2) - Prepare & Review	0	100% 04-May-20 A	-	┨┊┊┊┊┊┊┊┊┊┊┊╎┝ <mark>╤</mark> ━━━━┿┿		
MECH070000.16	P&ID - Existing system tie-ins (BATW U1-2) - Peer Review	0	100% 03-Aug-20 A	04-Aug-20 A			······································
MECH070000.20	P&ID - Existing system tie-ins (BATW U1-2) - S&L Prepare & Submit Package to Care	0	100% 05-Aug-20 A	13-Aug-20 A			
MECH070000.25	P&ID - Existing system tie-ins (BATW U1-2) - Cardinal review	0	100% 14-Aug-20 A	27-Aug-20 A			
	P&ID - Existing system tie-ins (BATW U1-2) - Design Issue	0	100% 28-Aug-20 A	11-Sep-20 A			
	P&ID - Existing system tie-ins (BATW U1-2) - Construction Issue	40	0% 11-Feb-21	07-Apr-21			
	40 P&ID - Existing system tie-ins (BATW U3)	40	04-May-20 A	07-Apr-21			
	P&ID - Existing system tie-ins (BATW U3) - Prepare & Review	0	100% 04-May-20 A		┨┊┊┊┊┊┊┊┊┊┊┊┊┊┊┊┊┊		
MECH080000.16	P&ID - Existing system tie-ins (BATW U3) - Peer Review	0	100% 03-Aug-20 A	04-Aug-20 A		╞╗╾╢╴┃┃┃┃┃┃	
MECH080000.20	P&ID - Existing system tie-ins (BATW U3) - S&L Prepare & Submit Package to Cardir	0	100% 05-Aug-20 A	13-Aug-20 A			
MECH080000.25	P&ID - Existing system tie-ins (BATW U3) - Cardinal review	0	100% 14-Aug-20 A	27-Aug-20 A			
MECH080000.30	P&ID - Existing system tie-ins (BATW U3) - Design Issue	0	100% 28-Aug-20 A	11-Sep-20 A			
MECH080000.60	P&ID - Existing system tie-ins (BATW U3) - Construction Issue	40	0% 11-Feb-21	07-Apr-21			
	41 P&ID - Existing system tie-ins (LVW)	40	04-May-20 A	07-Apr-21			
	P&ID - Existing system tie-ins (LVW) - Prepare & Review	0		31-Jul-20 A		<mark>₽<mark>−</mark>╢┊┃┃┃ ║┇┃ ┊╴┊┃┊┊ ┊ <mark>┃</mark> ┃┊┃┊</mark>	
MECH090000.16	P&ID - Existing system tie-ins (LVW) - Peer Review	0	100% 03-Aug-20 A	04-Aug-20 A			
	P&ID - Existing system tie-ins (LVW) - S&L Prepare & Submit Package to Cardinal	0	100% 05-Aug-20 A	13-Aug-20 A			
	P&ID - Existing system tie-ins (LVW) - Cardinal review	0	100% 14-Aug-20 A	27-Aug-20 A			
	P&ID - Existing system tie-ins (LVW) - Design Issue	0	100% 28-Aug-20 A	11-Sep-20 A			
MECH090000.60	P&ID - Existing system tie-ins (LVW) - Construction Issue	40	0% 11-Feb-21	07-Apr-21			
	1 P&ID - Unit 1 & 2 - Service Water System Tie-Ins	40	04-May-20 A				······································
	Unit 1 & 2 - Service Water System Tie-Ins - Prepare & Review	0	100% 04-May-20 A			╊ _{┲┓} ╢┊╽╽╽╷║┊╎┊┊┊╽┊┊┊┆ <mark>╷</mark>	
	Unit 1 & 2 - Service Water System Tie-Ins - Peer Review	0	100% 03-Aug-20 A				
	Unit 1 & 2 - Service Water System Tie-Ins - S&L Prepare & Submit Package to Cardin	0	100% 05-Aug-20 A	•			
	Unit 1 & 2 - Service Water System Tie-Ins - Cardinal review	0	100% 14-Aug-20 A	-			
	Unit 1 & 2 - Service Water System Tie-Ins - Design Issue	0	100% 28-Aug-20 A		┨┊╍╍┊╍╍┊╍╍┊╍╸┊╍┊╸╸┊╸┊╸┊	╽┊╌╴╢╴ ┊╴┫╽╴┨╴╴╢╠╶╽╴╶┊╴╸┊┫╺┊╶┊╸╸	······································
	Unit 1 & 2 - Service Water System Tie-Ins - Construction Issue	40	0% 11-Feb-21	07-Apr-21			
	P&ID - Ash Hopper Piping P&ID - Ash Hopper Piping - Prepare & Review	40 0	04-May-20 A 100% 04-May-20 A		¶∶∶∶∶∶∶∶∶∶∣└ _┿ <u>────</u>		
	P&ID - Ash Hopper Piping - Peer Review	0	100% 03-Aug-20 A			╄╦┛╢┊╽╽╏╷║╝╎┊╴┊╽┊┊┊┇ <mark>╷</mark> ┊╷	
	P&ID - Ash Hopper Piping - S&L Prepare & Submit Package to Cardinal	0	100% 05-Aug-20 A	-			
	P&ID - Ash Hopper Piping - Cardinal review	0		27-Aug-20 A		┝╘ <mark>╾╔╗╤</mark> ┨┝╌┨╌╌╢╠╌┨╌╌┊╌┨╴┊┊╌╌╴ <mark>┨</mark> ┊╌╴ <mark>┨</mark> ╶╌╴┨	
	P&ID - Ash Hopper Piping - Design Issue	0	100% 03-Aug-20 A	09-Sep-20 A		╞╼╤╪╤╉┩╽║║╽┆╴┊╴╽╽┊╴┊╴╽┊╽┊╵	
	P&ID - Ash Hopper Piping - Construction Issue	40	0% 11-Feb-21	07-Apr-21			
				•			
Remaining	Level of Effort Milestone				Page 4 of 8		
Actual Wor	rk				Engineering, Procurement & Construction	on Schedule by WBS	
Remaining	Work						Sargent & Lundy
e	maining Work						
Baseline M	-						

	ottom Ash Detailed Design		1		Monthly Report	Layout				Project	ID.I F 14-									t-20 17:16	16
Activity ID	Activity Name	Rem Duration	Activity % Start	Finish	J Sep Oct Nov Dec	Jan Feb	Mar Apr	2020 May Jun Ju		Sep Oct	Nov Dec	Jan Feb N	lar Apr M	2021 lay Jun J	 Sep Oct Nov	v Dec	Jan Feb	Mar Apr	2022 r May Jun	Jul Aug	ιT
	3.43 LVW Overflow to Outfall 023 - Pipe Composite	130	07-Aug-20 A	-										<u> </u>							-
	5 LVW Overflow to Outfall 023 - Pipe Composite - Initial Layout	0	100% 07-Aug-20 A	30-Sep-20 A											 						
	LVW Overflow to Outfall 023 - Pipe Composite - Prepare & Review	10	0% 01-Oct-20	14-Oct-20																	
	LVW Overflow to Outfall 023 - Pipe Composite - Bid Issue	10 40	0% 16-Dec-20 0% 11-Feb-21	31-Dec-20 07-Apr-21								-									
	LVW Overflow to Outfall 023 - Pipe Composite - Construction Issue Unit 1 BATW Lines to South pond - Iso/Composite (2 lines)	40 130	0% 11-Feb-21	•																, 1	
-	5 Unit 1 BATW Lines to South pond - Iso/Composite (2 lines) - Initial Layout	0	100% 07-Aug-20 A	30-Sep-20 A																	
MECH120000.10	0 Unit 1 BATW Lines to South pond - Iso/Composite (2 lines) - Prepare & Review	10	0% 01-Oct-20	14-Oct-20						┝╾╞═╡╇╿											1
MECH120000.30	0 Unit 1 BATW Lines to South pond - Iso/Composite (2 lines) - Bid Issue	10	0% 16-Dec-20	31-Dec-20							L=	-								, ,	
MECH120000.60	0 Unit 1 BATW Lines to South pond - Iso/Composite (2 lines) - Construction Issue	40	0% 11-Feb-21	07-Apr-21																	
	3.45 Unit 2 BATW Lines to South pond - Iso/Composite (2 lines)	130	07-Aug-20 A	-																	
	5 Unit 2 BATW Lines to South pond - Iso/Composite (2 lines) - Initial Layout	0	100% 07-Aug-20 A	30-Sep-20 A											 						
	0 Unit 2 BATW Lines to South pond - Iso/Composite (2 lines) - Prepare & Review	10	0% 01-Oct-20	14-Oct-20																	
	0 Unit 2 BATW Lines to South pond - Iso/Composite (2 lines) - Bid Issue	10	0% 16-Dec-20	31-Dec-20																,	
	Unit 2 BATW Lines to South pond - Iso/Composite (2 lines) - Construction Issue 3.46 Unit 3 BATW Lines to South pond - Iso/Composite (2 lines)	40 130	0% 11-Feb-21	07-Apr-21																,	
1	Unit 3 BATW Lines to South pond - Iso/Composite (2 lines) Unit 3 BATW Lines to South pond - Iso/Composite (2 lines) - Initial Layout	0	07-Aug-20 A 100% 07-Aug-20 A	30-Sep-20 A					+												
	0 Unit 3 BATW Lines to South pond - Iso/Composite (2 lines) - Prepare & Review	10	0% 01-Oct-20	14-Oct-20					╟┼╌┼╶┼╴						 					 	
	0 Unit 3 BATW Lines to South pond - Iso/Composite (2 lines) - Bid Issue	10	0% 16-Dec-20	31-Dec-20	11 1 1 1						-	-									
MECH140000.60	0 Unit 3 BATW Lines to South pond - Iso/Composite (2 lines) - Construction Issue	40	0% 11-Feb-21	07-Apr-21	1							►	╺╪╕┥┊┊								
	3.47 Reroute LVW discharge pipes	130	07-Aug-20 A	-																	
	5 Reroute LVW discharge pipes - Initial Layout	0	100% 07-Aug-20 A	30-Sep-20 A											 -						¦
	0 Reroute LVW discharge pipes - Prepare & Review	10	0% 01-Oct-20	14-Oct-20																	
	0 Reroute LVW discharge pipes - Bid Issue	10	0% 16-Dec-20	31-Dec-20																	
	0 Reroute LVW discharge pipes - Construction Issue	40	0% 11-Feb-21	07-Apr-21																	
	3.48 Blowdown to FGD - Iso Blowdown to FGD - Iso - Initial Layout	130 0	07-Aug-20 A 100% 07-Aug-20 A	07-Apr-21 30-Sep-20 A					╢┿═══												
	0 Blowdown to FGD - Iso - Prepare & Review	10	0% 01-Oct-20	14-Oct-20						┢					 						
	0 Blowdown to FGD - Iso - Bid Issue	10	0% 16-Dec-20	31-Dec-20							L	•									
MECH160000.60	0 Blowdown to FGD - Iso - Construction Issue	40	0% 11-Feb-21	07-Apr-21								-									
CRD-BA0.69.	3.42 Temporary Piping Layout from North Pond to Recirc. Pumphouse	130	07-Aug-20 A	07-Apr-21																	
MECH100000.05	5 Temporary Piping Layout from North Pond to Recirc. Pumphouse - Initial Layout	0	100% 07-Aug-20 A	25-Sep-20 A					-		<u>_</u>										
MECH100000.06	6 Temporary Piping Layout from North Pond to Recirc. Pumphouse - Initial Analysis	2	0% 28-Sep-20 A	02-Oct-20						" 										,	
	0 Temporary Piping Layout from North Pond to Recirc. Pumphouse - Model Review	5	0% 05-Oct-20	09-Oct-20																	
	0 Temporary Piping Layout from North Pond to Recirc. Pumphouse - Bid Issue	20	0% 02-Dec-20	31-Dec-20								-									
J	0 Temporary Piping Layout from North Pond to Recirc. Pumphouse - Final Analysis	10	0% 11-Mar-21	24-Mar-21																	
	Temporary Piping Layout from North Pond to Recirc. Pumphouse - Construction Issue		0% 11-Feb-21	07-Apr-21											 						
	3.2 Unit 1 & 2 - Service Water System Tie-Ins - Iso/Composite Unit 1 & 2 - Service Water System Tie-Ins - Iso/Composite (2 lines) - Initial Layout	130 0	100% 07-Aug-20 A	07-Apr-21 25-Sep-20 A					+											,	
ļ	6 Unit 1 & 2 - Service Water System Tie-Ins - Iso/Composite (2 lines) - Initial Analysis	0	100% 28-Sep-20 A																		
	0 Unit 1 & 2 - Service Water System Tie-Ins - Iso/Composite (2 lines) - Model Review	5	0% 01-Oct-20	07-Oct-20							-										
MECH141000.30	0 Unit 1 & 2 - Service Water System Tie-Ins - Iso/Composite (2 lines) - Bid Issue	20	0% 02-Dec-20	31-Dec-20								-									
MECH141000.50	0 Unit 1 & 2 - Service Water System Tie-Ins - Iso/Composite (2 lines) - Final Analysis	10	0% 11-Mar-21	24-Mar-21								M									
MECH141000.60	0 Unit 1 & 2 - Service Water System Tie-Ins - Iso/Composite (2 lines) - Construction Is:	40	0% 11-Feb-21	07-Apr-21									╺╘╧┥┊								
	3.8 Ash Hopper Piping - Iso/Composite	130	07-Aug-20 A	-						Щ!!!!!											
	5 Ash Hopper Piping - Iso/Composite - Initial Layout	0	100% 07-Aug-20 A								+										
	6 Ash Hopper Piping - Iso/Composite - Initial Analysis	7	0% 28-Sep-20 A		l	·		·····	┃.↓						 					,	
	Ash Hopper Piping - Iso/Composite - Model Review	5	0% 12-Oct-20	16-Oct-20						╽║ ╔ ╝╫┊		•									
	Ash Hopper Piping - Iso/Composite - Bid Issue Ash Hopper Piping - Iso/Composite - Bid Issue	20 10	0% 02-Dec-20	31-Dec-20								L									
l	Ash Hopper Piping - Iso/Composite - Final Analysis Ash Hopper Piping - Iso/Composite - Construction Issue	40	0% 11-Mar-21 0% 11-Feb-21	24-Mar-21 07-Apr-21																	
	3.49 Supports - Ash Piping	40	20-Oct-20	07-Apr-21									┲╹								
7 mm	0 Supports - Ash Piping - Prepare & Review	20	0% 20-Oct-20	16-Nov-20							1				 -						
	0 Supports - Ash Piping - Bid Issue	10	0% 16-Dec-20	31-Dec-20	1							-									
MECH190000.60	0 Supports - Ash Piping - Construction Issue	40	0% 11-Feb-21	07-Apr-21	1								╺╋╛┥┊│								
CRD-BA0.69.	3.3 Supports - Unit 1 & 2 - Service Water System Tie-Ins	117	20-Oct-20	07-Apr-21							<u> </u>										
Remainin	ng Level of Effort 🔶 🔶 Milestone						Page	5 of 8										1			
					Engineering D	rooure			on Cal	adula		•					1				
Actual W					Engineering, P	ocurem	ent & C	JIISTUCT	un sch	euule l	Jy WBS	,				_	0		Tener.		
Remainin	5															Sar	gent	SL	undy		
Critical R	Remaining Work																1.59	1			
	Milestone																	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~			

tom Ash Detailed Design	Rem	Activity % Start	Finish	Monthly Report Layout	Project ID:FPT4-CRD-BA0	28-Oct-20 17:16
	Duration	Complete		g Sep Oct Nov Dec Jan Feb Mar Apr	r May Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug	
Supports - Unit 1 & 2 - Service Water System Tie-Ins - Prepare & Review	20	0% 20-Oct-20	16-Nov-20			
			· ·			
	40	0% 11-Feb-21	07-Apr-21			
7 Supports - Ash Hopper Piping	117	20-Oct-20	07-Apr-21			
Supports - Ash Hopper Piping - Prepare & Review	20	0% 20-Oct-20	16-Nov-20			
Supports - Ash Hopper Piping - Bid Issue	10	0% 16-Dec-20	31-Dec-20			
Supports - Ash Hopper Piping - Construction Issue	40	0% 11-Feb-21	07-Apr-21			
	34					
· · · · · · · · · · · · · · · · · · ·		· ·				
List - Pipelines - Prepare & Review	24	0% 23-Sep-20 A				
List - Pipelines - Issue for Use	10	0% 04-Nov-20	17-Nov-20	<u> </u>		
35 List - Valves	34	23-Sep-20 A	17-Nov-20			
List - Valves - Prepare & Review	24	· ·				
List - Valves - Issue for Use	10	0% 04-Nov-20	17-Nov-20			
52 Mechanical Walkdowns	35				╶┊╌╌┊╌╌┊╎ <mark>╢_┙</mark> ╧╍╍┊╸ <mark>╽┨╶╢</mark> ┊╍╗╴┊╴╴┊┨╶┊╴╴┥╸┨┊╴┨┊╶┨┊╴╴	┊╢╫ <mark>╠╌╌┊╌╶┊╢</mark> ╶┊
Wiring Drawings - Prepare & Review	40	0% 14-Jan-21	10-Mar-21			
Wiring Drawings - Construction Issue	20	0% 11-Mar-21	07-Apr-21			
21 Cable Tabulations	130	01-Oct-20	07-Apr-21			
Cable Tabulations - Prepare & Review	20	0% 01-Oct-20	28-Oct-20			
		0% 16-Dec-20	31-Dec-20			
-					╶┊╌╌╴┊╌╴┊╷╢╴┊╴╴┊╴┨╶╏╴ <mark>┊</mark>	
-						
-						
Electrical Wakdowns - Summary	77	0% 29-Jul-20 A	22-Jan-21			
&C	92	29-Jul-20 A	12-Feb-21			
27 Control Description- Logics	66					
I/O Database/List	30	20% 02-Oct-20 A	11-Nov-20			
I/O Database/List - S&L Prepare & Submit Package to Cardinal	10	0% 12-Nov-20	25-Nov-20			
			11-Dec-20	1		
I/O Database/List - Cardinal review	10	0% 30-Nov-20				
I/O Database/List - Cardinal review I/O Database/List - Issue for Use	10 12	0% 30-Nov-20 0% 14-Dec-20	31-Dec-20			
I/O Database/List - Issue for Use 29 Instrument List and Details	12 52	0% 14-Dec-20 15-Oct-20	31-Dec-20			
I/O Database/List - Issue for Use 29 Instrument List and Details Instrument List and Details - Prepare & Review	12 52 40	0% 14-Dec-20 15-Oct-20 0% 15-Oct-20	31-Dec-20 11-Dec-20			
I/O Database/List - Issue for Use 29 Instrument List and Details Instrument List and Details - Prepare & Review Instrument List and Details - Issue for Use	12 52 40 12	0% 14-Dec-20 15-Oct-20 15-Oct-20 0% 14-Dec-20 0% 14-Dec-20	31-Dec-20 11-Dec-20 31-Dec-20			
I/O Database/List - Issue for Use 29 Instrument List and Details Instrument List and Details - Prepare & Review Instrument List and Details - Issue for Use 30 I&C Walkdowns	12 52 40 12 35	0% 14-Dec-20 15-Oct-20 15-Oct-20 0% 15-Oct-20 0% 14-Dec-20 29-Jul-20 A 29-Jul-20 A	31-Dec-20 11-Dec-20 31-Dec-20 18-Nov-20			
I/O Database/List - Issue for Use 29 Instrument List and Details Instrument List and Details - Prepare & Review Instrument List and Details - Issue for Use 30 I&C Walkdowns I&C Walkdowns - Summary	12 52 40 12 35 35	0% 14-Dec-20 15-Oct-20 0% 15-Oct-20 14-Dec-20 0% 14-Dec-20 29-Jul-20 A 29-Jul-20 A	31-Dec-20 11-Dec-20 31-Dec-20 18-Nov-20 18-Nov-20			
I/O Database/List - Issue for Use 29 Instrument List and Details Instrument List and Details - Prepare & Review Instrument List and Details - Issue for Use 30 I&C Walkdowns	12 52 40 12 35	0% 14-Dec-20 15-Oct-20 15-Oct-20 0% 15-Oct-20 0% 14-Dec-20 29-Jul-20 A 29-Jul-20 A	31-Dec-20 11-Dec-20 31-Dec-20 18-Nov-20			
I/O Database/List - Issue for Use Instrument List and Details Instrument List and Details - Prepare & Review Instrument List and Details - Issue for Use IkC Walkdowns I&C Walkdowns - Summary ARP Pressure Increase Instrument Evaluation ARP Pressure Increase Instrument Evaluation	12 52 40 12 35 35 10	0% 14-Dec-20 15-Oct-20 0% 15-Oct-20 15-Oct-20 0% 14-Dec-20 29-Jul-20 A 29-Jul-20 A 0% 29-Jul-20 A 01-Oct-20 01-Oct-20	31-Dec-20 11-Dec-20 31-Dec-20 18-Nov-20 14-Oct-20 14-Oct-20			
I/O Database/List - Issue for Use 29 Instrument List and Details Instrument List and Details - Prepare & Review Instrument List and Details - Issue for Use 30 I&C Walkdowns I&C Walkdowns - Summary 31 ARP Pressure Increase Instrument Evaluation	12 52 40 12 35 35 10 10	0% 14-Dec-20 15-Oct-20 0% 15-Oct-20 14-Dec-20 0% 14-Dec-20 29-Jul-20 A 0% 0% 29-Jul-20 A 0% 10-Oct-20 0% 01-Oct-20 0% 01-Oct-20	31-Dec-20 11-Dec-20 31-Dec-20 18-Nov-20 14-Oct-20 14-Oct-20			
	Supports - Ash Hopper Piping - Prepare & Review Supports - Ash Hopper Piping - Bid Issue Supports - Ash Hopper Piping - Construction Issue 1 Control Valve Data Sheets Control Valve Data Sheets - Prepare & Review Control Valve Data Sheets - Issue for Use 3 List - Pipelines List - Pipelines - Prepare & Review List - Pipelines - Issue for Use 5 List - Valves List - Valves List - Valves 5 List - Valves List - Valves - Prepare & Review List - Valves - Prepare & Review List - Valves - Summary 6 Control Valve Data Issue 7 Control Installation Drawings 7 Control Installation Drawings Cable Tabulations - Construction Issue 8 Lectrical Installation Drawings Electrical Installation Drawings - Prepare & Review Electrical Installation Drawings - Construction Issue 3 List-ist Valves - Summary 4 Control Description- Logics Control Description- Logics - Sach Prepare & Review Control Description- Logics - Sach Prepare & Submit Package to Cardinal Control Description- Logics - Sach Prepare & Submit Package to Cardinal Control Description- Logics - Sach Prepare & Submit Package to Cardinal Control Description- Logics - Sach Prepare & Submit Package to Cardinal Control Description- Logics - Sach Prepare & Submit Package to Cardinal Control Descri	Supports - Unit 1 & 2 - Service Water System Tie-Ins - Construction Issue400 Supports - Blowdown to FGD127Supports - Blowdown to FGD - Prepare & Review30Supports - Blowdown to FGD - Construction Issue40Supports - Blowdown to FGD - Construction Issue40Supports - Ash Hopper Piping117Supports - Ash Hopper Piping - Prepare & Review20Supports - Ash Hopper Piping - Construction Issue40Control Valve Data Sheets40Control Valve Data Sheets - Prepare & Review24Control Valve Data Sheets - Issue for Use10S List - Pipelines34List - Pipelines - Prepare & Review24List - Pipelines - Prepare & Review24List - Pipelines - Prepare & Review24List - Valves - Prepare & Review26Viring Drawings - Prepare & Review20O Wiring Drawings - Prepare & Review20Cable Tabulations - Prepare & Review20 <td>Supports Unit 1 & 2 - Service Water System Tie-Ins - Construction Issue 40 0% 11 - Feb-21 0 Supports - Blowdown to FGD 060-Ct-20 Supports - Blowdown to FGD - Frepare & Review 30 0% 06-Ct-20 Supports - Blowdown to FGD - Construction Issue 10 0% 16-Dec-20 Supports - Ash Hopper Piping 117 20-Oct-20 Supports - Ash Hopper Piping - Bid Issue 100 0% 16-Dec-20 Supports - Ash Hopper Piping - Construction Issue 40 0% 11-Feb-21 Control Valve Data Sheets - Issue for Use 34 23-Sep-20 A Control Valve Data Sheets - Issue for Use 34 23-Sep-20 A Control Valve Data Sheets - Issue for Use 10 0% 44-Nov-20 3 List - Pipelines 34 23-Sep-20 A 24 0% 23-Sep-20 A List - Pipelines - Issue for Use 10 0% 44-Nov-20 34 23-Sep-20 A List - Pipelines - Issue for Use 10 0% 24-Nov-20 32-Sep-20 A List - Valves - Issue for Use 10 0% 32-Sep-20 A</td> <td>Supports - Unit 1 & 2 - Service Water System Tie-Ins - Construction Issue 440 490 11-Feb-21 07-Apr-21 0 Supports - Blowdown to FGD - Prepare & Review 300 400 605 16-Dec-200 31-Dec-20 Supports - Blowdown to FGD - Construction Issue 400 401 405 16-Dec-20 31-Dec-20 Supports - Blowdown to FGD - Construction Issue 400 405 11-Dec-21 67-Apr-21 Supports - Ash Hopper Piping - Prepare & Review 20 405 16-Dec-20 31-Dec-20 Supports - Ash Hopper Piping - Construction Issue 401 405 16-Dec-20 31-Dec-20 Supports - Ash Hopper Piping - Construction Issue 404 405 23-Sep-20A 17-Avr-20 Control Valve Data Sheets - Prepare & Review 24 405 23-Sep-20A 17-Avr-20 List - Pipelines - Susue for Use 34 23-Sep-20A 17-Avr-20 List - Pipelines - Prepare & Review 24 405 23-Sep-20A 17-Avr-20 List - Valves - Susue for Use 34 23-Sep-20A 17-Avr-20 List - Valves - Susue for Use 34</td> <td>Supports: Unit 18 2. Service Water System Tie Ins - Construction Issue 40 0%, 11 Fab 21 07.4 p 21 0 Apports: Blowdown to FGD - Pepting & Review 30 0.6 (0.6 C2.2) 07.4 p 21 07.4 p 21 Supports: Blowdown to FGD - Pepting & Review 30 0.6 (0.6 C2.2) 07.4 p 21 07.4 p 21 Supports: Blowdown to FGD - Pepting & Review 20 0.6 (0.6 C2.2) 07.4 p 21 07.4 p 21 Supports: AbitMopper Pepting - Regare & Review 20 0.6 (0.6 C2.2) 07.4 p 21 07.4 p 21 Supports: AbitMopper Pepting - Regare & Review 20 0.6 (0.6 C2.2) 07.4 p 21 07.4 p 21 Supports: AbitMopper Pepting - Regare & Review 24 0.6 (0.7 Mov 20) 17.N ove 20 07.N ove 20 Control Mave Data Benets 10 0.6 (0.4 Nove 20) 17.N ove 20 07.N ove 20 2 List - Peptines - Review 24 0.6 (0.4 Nove 20) 07.N ove 20 07.N ove 20 2 List - Notess 30 23.8 spc 20.4 07.8 Nove 20 07.8 Nove 20 2 List - Peptines - Review 24 0.6 (0.4 Nove 20) 07.8 Nove 20 07.8 Nove 20 2 List - Notess 10 0.6 (0.4 Nove 20) 07.8 Nove 20 07</td> <td>Support Control <t< td=""></t<></td>	Supports Unit 1 & 2 - Service Water System Tie-Ins - Construction Issue 40 0% 11 - Feb-21 0 Supports - Blowdown to FGD 060-Ct-20 Supports - Blowdown to FGD - Frepare & Review 30 0% 06-Ct-20 Supports - Blowdown to FGD - Construction Issue 10 0% 16-Dec-20 Supports - Ash Hopper Piping 117 20-Oct-20 Supports - Ash Hopper Piping - Bid Issue 100 0% 16-Dec-20 Supports - Ash Hopper Piping - Construction Issue 40 0% 11-Feb-21 Control Valve Data Sheets - Issue for Use 34 23-Sep-20 A Control Valve Data Sheets - Issue for Use 34 23-Sep-20 A Control Valve Data Sheets - Issue for Use 10 0% 44-Nov-20 3 List - Pipelines 34 23-Sep-20 A 24 0% 23-Sep-20 A List - Pipelines - Issue for Use 10 0% 44-Nov-20 34 23-Sep-20 A List - Pipelines - Issue for Use 10 0% 24-Nov-20 32-Sep-20 A List - Valves - Issue for Use 10 0% 32-Sep-20 A	Supports - Unit 1 & 2 - Service Water System Tie-Ins - Construction Issue 440 490 11-Feb-21 07-Apr-21 0 Supports - Blowdown to FGD - Prepare & Review 300 400 605 16-Dec-200 31-Dec-20 Supports - Blowdown to FGD - Construction Issue 400 401 405 16-Dec-20 31-Dec-20 Supports - Blowdown to FGD - Construction Issue 400 405 11-Dec-21 67-Apr-21 Supports - Ash Hopper Piping - Prepare & Review 20 405 16-Dec-20 31-Dec-20 Supports - Ash Hopper Piping - Construction Issue 401 405 16-Dec-20 31-Dec-20 Supports - Ash Hopper Piping - Construction Issue 404 405 23-Sep-20A 17-Avr-20 Control Valve Data Sheets - Prepare & Review 24 405 23-Sep-20A 17-Avr-20 List - Pipelines - Susue for Use 34 23-Sep-20A 17-Avr-20 List - Pipelines - Prepare & Review 24 405 23-Sep-20A 17-Avr-20 List - Valves - Susue for Use 34 23-Sep-20A 17-Avr-20 List - Valves - Susue for Use 34	Supports: Unit 18 2. Service Water System Tie Ins - Construction Issue 40 0%, 11 Fab 21 07.4 p 21 0 Apports: Blowdown to FGD - Pepting & Review 30 0.6 (0.6 C2.2) 07.4 p 21 07.4 p 21 Supports: Blowdown to FGD - Pepting & Review 30 0.6 (0.6 C2.2) 07.4 p 21 07.4 p 21 Supports: Blowdown to FGD - Pepting & Review 20 0.6 (0.6 C2.2) 07.4 p 21 07.4 p 21 Supports: AbitMopper Pepting - Regare & Review 20 0.6 (0.6 C2.2) 07.4 p 21 07.4 p 21 Supports: AbitMopper Pepting - Regare & Review 20 0.6 (0.6 C2.2) 07.4 p 21 07.4 p 21 Supports: AbitMopper Pepting - Regare & Review 24 0.6 (0.7 Mov 20) 17.N ove 20 07.N ove 20 Control Mave Data Benets 10 0.6 (0.4 Nove 20) 17.N ove 20 07.N ove 20 2 List - Peptines - Review 24 0.6 (0.4 Nove 20) 07.N ove 20 07.N ove 20 2 List - Notess 30 23.8 spc 20.4 07.8 Nove 20 07.8 Nove 20 2 List - Peptines - Review 24 0.6 (0.4 Nove 20) 07.8 Nove 20 07.8 Nove 20 2 List - Notess 10 0.6 (0.4 Nove 20) 07.8 Nove 20 07	Support Control Control <t< td=""></t<>

		ttom Ash Detailed Design			1	Monthly Report Layout	Project ID:FPT4-CRD-BA0	28-Oct-20 17:1
	Activity ID	Activity Name	Rem Duration	Activity % Start	Finish	2020 g Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug	2021 Sep Oct Nov Dec Jan Feb Mar Apr May Jun J	ul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug
	PGWC000000.20	0 Spec - General Work Specification - S&L Prepare & Submit Package to Cardinal	5	0% 02-Dec-20	08-Dec-20			
	PGWC000000.25	5 Spec - General Work Specification - Cardinal review	10	0% 09-Dec-20	22-Dec-20			
	PGWC000000.30	0 Spec - General Work Specification - Bid Issue	5	0% 23-Dec-20	31-Dec-20*			
	PGWC000000.40	0 Spec - General Work Specification - Bid Period	30	0% 04-Jan-21	12-Feb-21			
	PGWC000000.50	0 Spec - General Work Specification - Tech Bid Eval / Recommendation	28	0% 15-Feb-21	24-Mar-21			
		2 Spec - General Work Specification - Commercial Evaluation	10	0% 11-Mar-21	24-Mar-21			
		5 Spec - General Work Specification - Conform Spec for Contract	5	0% 25-Mar-21	31-Mar-21			
		0 Spec - General Work Specification - Award	5	0% 01-Apr-21	07-Apr-21*		1	
-		4 Vndr Dwgs- General Work Specification	333	08-Apr-21	29-Jul-22	╻-┆┊┊┊┊┊┊- ┊- ┊-	·····	····
_		5 General Work Specification - Mobilize	35	0% 08-Apr-21	26-May-21			
-		9 General Work Specification - Procure / Fab / Deliver Materiaks	80 333	0% 12-May-21	02-Sep-21 29-Jul-22			
		General Work Specification - Interface Spec - Construction Quality Assurance	63	0% 08-Apr-21	29-Jui-22 31-Mar-21			
Г		Spec - Construction Quality Assurance - Prepare & Review	10	0% 04-Jan-21	15-Jan-21		La La <u>La construcción de la con</u>	
		Spec - Construction Quality Assurance - S&L Prepare & Submit Package to Cardinal	5	0% 18-Jan-21	22-Jan-21			
		Spec - Construction Quality Assurance - Cardinal review	5	0% 25-Jan-21	29-Jan-21			
		Spec - Construction Quality Assurance - Bid Issue	3	0% 01-Feb-21	03-Feb-21			
		Spec - Construction Quality Assurance - Bid Period	15	0% 04-Feb-21	24-Feb-21			
	PCQA000000.50		15	0% 25-Feb-21	17-Mar-21		┝╼╔═┥┫	
	PCQA000000.52	Spec - Construction Quality Assurance - Commercial Evaluation	5	0% 11-Mar-21	17-Mar-21			
	PCQA000000.55	Spec - Construction Quality Assurance - Conform Spec for Contract	5	0% 18-Mar-21	24-Mar-21			
	PCQA000000.60	Spec - Construction Quality Assurance - Award	5	0% 25-Mar-21	31-Mar-21			
	CRD-BA0.70.63	Vndr Dwgs- Construction Quality As surance	335	01-Apr-21	26-Jul-22			
	VCQA000000.90	Construction Quality Assurance - Contractor Interface	335	0% 01-Apr-21	26-Jul-22			
_		5 Spec - Topographic & Bathymetric Survey	0	27-Apr-20 A	17-Jul-20 A			
) Spec - Topographic & Bathymetric Survey - Prepare & Review	0	100% 27-Apr-20 A	01-May-20 A			
		Spec - Topographic & Bathymetric Survey - S&L Prepare & Submit Package to Cardir	0	100% 04-May-20 A	08-May-20 A			
		Spec - Topographic & Bathymetric Survey - Cardinal review	0	100% 11-May-20 A	15-May-20 A			
		Spec - Topographic & Bathymetric Survey - Bid Issue	0	100% 18-May-20 A	20-May-20 A		·····	
		Spec - Topographic & Bathymetric Survey - Bid Period	0	100% 21-May-20 A	30-Jun-20 A 08-Jul-20 A			
		Spec - Topographic & Bathymetric Survey - Tech Bid Eval / Recommendation Spec - Topographic & Bathymetric Survey - Commercial Evaluation	0	100% 01-Jul-20 A 100% 01-Jul-20 A	08-Jul-20 A			
-		5 Spec - Topographic & Bathymetric Survey - Conform Spec for Contract	0	100% 01-3ul-20 A	10-Jul-20 A			
		Spec - Topographic & Bathymetric Survey - Award	0	100% 09-3ul-20 A	17-Jul-20 A			
C		Procurement (Equipment Fabrication & Delivery)	138	08-Apr-21	18-Oct-21			
	CRD-BA0.71 P		106	08-Apr-21	02-Sep-21			
Г		Clay Procurment - Ordering	20	0% 08-Apr-21	05-May-21			
		Clay Procurment - Delivery	86	0% 06-May-21	02-Sep-21			
		Gravel and Riprap	106	08-Apr-21	02-Sep-21			
Г	PFDR000000.90	Gravel & Riprap Procurement - Ordering	20	0% 08-Apr-21	05-May-21			
	PFDR000000.99	Gravel & Riprap Procurement - Delivery	86	0% 06-May-21	02-Sep-21			
	CRD-BA0.71.3	Geomembrane	106	08-Apr-21	02-Sep-21			
		Geomembrane Procurement - Ordering	20	0% 08-Apr-21	05-May-21			
		Geomembrane Procurement - Fabrication	66	0% 06-May-21	05-Aug-21			
		Geomembrane Procurement - Delivery	20	0% 06-Aug-21	02-Sep-21			
-	CRD-BA0.71.4		106	08-Apr-21	02-Sep-21			
_		Geotextile Procurement - Ordering	20	0% 08-Apr-21	05-May-21			
		Geotextile Procurement - Fabrication	66	0% 06-May-21	05-Aug-21 02-Sep-21			╔ _{╋╋╋} ┥╢╠╴┊╴┊╎┊╴┊╴┊╴┊╴┊╴┊╴╽
_	CRD-BA0.71.5	Geotextile Procurement - Delivery	20 138	0% 06-Aug-21	18-Oct-21	· · · · · · · · · · · · · · · · · · ·	<u> </u>	
		Concrete Procurement - Ordering	138	0% 08-Apr-21	11-Oct-21			
		Concrete Procurement - Delivery	5	0% 12-Oct-21	18-Oct-21			
		Pipes and Valves	70	08-Apr-21	14-Jul-21			
Г		Pipes & Valves Procurement - Ordering	10	0% 08-Apr-21	21-Apr-21			
F		Pipes & Valves Procurement - Fabrication	40	0% 22-Apr-21	16-Jun-21	<u> </u>		
	Remaining Actual Wo Remaining	g Level of Effort ◆ ◆ Milestone ork g Work	40	0% 22-Apr-21	16-Jun-21	Page 7 of 8 Engineering, Procurement & Construction Sc		Sargent & Lundy
	-	emaining Work						

CRD-BA0.71.7 Put PFDP000000.90 F PFDP000000.95 F PFDP000000.99 F RD-BA0.66 Mat X01000000.00 E X01000000.00 F X02000001.00 F X03000002.00 It X04000003.00 S X05000004.00 N X06000005.00 F X08000005.00 F CONSTR0100.00 It RD-BA0.CON It RD-BA0.CON C	Pumps Procurement - Ordering Pumps Procurement - Fabrication Pumps Procurement - Delivery Inagement and Administration External Status Meetings - Summary Project Status Meetings (Conference Calls) - Summary Internal Team Meetings - Summary Schedule Development and Maintenance - Summary Monthly Progress reports - Summary Project Adminstration Support & Document Control - Summary Project Management (Lining) - Summary Home office support of construction - Summary	Duration 20 70 10 40 20 470 326 326 326 326 326 326 448 458 458 458	Commetee 0% 17-Jun-21 0% 08-Apr-21 0% 08-Apr-21 0% 22-Apr-21 0% 17-Jun-21 0% 03-Aug-20 A 0% 03-Aug-20 A	14-Jul-21 14-Jul-21 21-Apr-21 16-Jun-21 14-Jul-21 09-Aug-22 18-Jan-22 18-Jan-22 18-Jan-22 18-Jan-22 18-Jan-22 18-Jan-22 18-Jan-22 18-Jan-22	Sep Oct N	ov Dec	Jan Feb	Mar A	or May	Jun	Jul Ai	ıg Seț	p Oct	Nov	Dec Ja	an Feb	Mar
CRD-BA0.71.7 Put PFDP000000.90 F PFDP000000.95 F PFDP000000.99 F RD-BA0.66 Mat X01000000.00 E X01000000.00 F X01000000.00 F X03000002.00 It X04000003.00 S X05000004.00 K X07000006.00 F X08000005.00 F CONSTR0100.00 It RD-BA0.CON It RD-BA0.CON It	Imps Pumps Procurement - Ordering Pumps Procurement - Fabrication Pumps Procurement - Delivery Inagement and Administration External Status Meetings - Summary Project Status Meetings (Conference Calls) - Summary Internal Team Meetings - Summary Schedule Development and Maintenance - Summary Monthly Progress reports - Summary Project Adminstration Support & Document Control - Summary Project Management (Lining) - Summary Project Management (Closure) - Summary Home office support of construction - Summary	70 10 40 20 470 326 326 326 326 326 448 458 458	08-Apr-21 0% 08-Apr-21 0% 22-Apr-21 0% 17-Jun-21 0% 03-Aug-20 A 0% 03-Aug-20 A	14-Jul-21 21-Apr-21 16-Jun-21 14-Jul-21 09-Aug-22 18-Jan-22 18-Jan-22 18-Jan-22													
PFDP000000.90 F PFDP000000.95 F PFDP000000.99 F RD-BA0.66 Mar X01000000.00 E X02000001.00 F X03000002.00 In X04000003.00 S X05000004.00 N X06000005.00 F X08000005.00 F CONSTR0100.00 In RD-BA0.CON In RD-BA0.CON In	Pumps Procurement - Ordering Pumps Procurement - Fabrication Pumps Procurement - Delivery Inagement and Administration External Status Meetings - Summary Project Status Meetings (Conference Calls) - Summary Internal Team Meetings - Summary Schedule Development and Maintenance - Summary Monthly Progress reports - Summary Project Adminstration Support & Document Control - Summary Project Management (Lining) - Summary Home office support of construction - Summary	10 40 20 470 326 326 326 326 448 458 458	0% 08-Apr-21 0% 22-Apr-21 0% 17-Jun-21 0% 03-Aug-20 A	21-Apr-21 16-Jun-21 14-Jul-21 09-Aug-22 18-Jan-22 18-Jan-22 18-Jan-22													
PFDP000000.95 F PFDP000000.99 F RD-BA0.66 Mat X01000000.00 F X02000001.00 F X03000002.00 In X04000003.00 S X05000004.00 N X06000005.00 F X08000005.00 F CONSTR0100.00 In RD-BA0.CON In RD-BA0.CON In	Pumps Procurement - Fabrication Pumps Procurement - Delivery Inagement and Administration External Status Meetings - Summary Project Status Meetings - Summary Internal Team Meetings - Summary Schedule Development and Maintenance - Summary Monthly Progress reports - Summary Project Adminstration Support & Document Control - Summary Project Management (Lining) - Summary Home office support of construction - Summary	20 470 326 326 326 326 326 448 458	0% 22-Apr-21 0% 17-Jun-21 03-Aug-20 A 03-Aug-20 A 0% 03-Aug-20 A	16-Jun-21 14-Jul-21 09-Aug-22 18-Jan-22 18-Jan-22 18-Jan-22													3 I.
RD-BA0.66 Mail X01000000.00 E X02000001.00 F X03000002.00 II X04000003.00 S X05000004.00 N X06000005.00 F X07000006.00 F X0800005.00 F CONSTR0100.00 II RD-BA0.CON C A13770.1330 1	Inagement and Administration External Status Meetings - Summary Project Status Meetings (Conference Calls) - Summary Internal Team Meetings - Summary Schedule Development and Maintenance - Summary Monthly Progress reports - Summary Project Administration Support & Document Control - Summary Project Management (Lining) - Summary Project Management (Closure) - Summary Home office support of construction - Summary	470 326 326 326 326 326 448 458 458	17-Jun-21 03-Aug-20 A 0% 03-Aug-20 A	09-Aug-22 18-Jan-22 18-Jan-22 18-Jan-22 18-Jan-22													
X01000000.00 F X02000001.00 F X03000002.00 In X04000003.00 S X05000004.00 N X06000005.00 F X07000006.00 F X08000005.00 F CONSTR0200.00 In RD-BAO.CON C A13770.1330 1	External Status Meetings - Summary Project Status Meetings (Conference Calls) - Summary Internal Team Meetings - Summary Schedule Development and Maintenance - Summary Monthly Progress reports - Summary Project Adminstration Support & Document Control - Summary Project Management (Lining) - Summary Project Management (Closure) - Summary Home office support of construction - Summary	326 326 326 326 326 448 458 458	0% 03-Aug-20 A	18-Jan-22 18-Jan-22 18-Jan-22				i i		1							
X01000000.00 F X02000001.00 F X03000002.00 In X04000003.00 S X05000004.00 N X06000005.00 F X07000006.00 F X08000005.00 F	External Status Meetings - Summary Project Status Meetings (Conference Calls) - Summary Internal Team Meetings - Summary Schedule Development and Maintenance - Summary Monthly Progress reports - Summary Project Adminstration Support & Document Control - Summary Project Management (Lining) - Summary Project Management (Closure) - Summary Home office support of construction - Summary	326 326 326 448 458 458	0% 03-Aug-20 A	18-Jan-22 18-Jan-22													
X02000001.00 F X03000002.00 In X04000003.00 S X05000004.00 N X06000005.00 F X07000006.00 F X08000005.00 F X08000000.00 F X0800000.00 F X0800000.00 F X0800000.00 F X08000000.00 F X08000000.00 F X08000000000 F <t< td=""><td>Project Status Meetings (Conference Calls) - Summary Internal Team Meetings - Summary Schedule Development and Maintenance - Summary Monthly Progress reports - Summary Project Adminstration Support & Document Control - Summary Project Management (Lining) - Summary Project Management (Closure) - Summary Home office support of construction - Summary</td><td>326 326 326 448 458 458</td><td>0% 03-Aug-20 A 0% 03-Aug-20 A 0% 03-Aug-20 A 0% 03-Aug-20 A 0% 03-Aug-20 A</td><td>18-Jan-22 18-Jan-22</td><td></td><td>1</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></t<>	Project Status Meetings (Conference Calls) - Summary Internal Team Meetings - Summary Schedule Development and Maintenance - Summary Monthly Progress reports - Summary Project Adminstration Support & Document Control - Summary Project Management (Lining) - Summary Project Management (Closure) - Summary Home office support of construction - Summary	326 326 326 448 458 458	0% 03-Aug-20 A	18-Jan-22 18-Jan-22		1											
X03000002.00 In X04000003.00 S X05000004.00 N X06000005.00 F X07000006.00 F X08000005.00 F X08000005.00 F X08000005.00 F CONSTR0100.00 F RD-BA0.CON C A13770.1330 1	Internal Team Meetings - Summary Schedule Development and Maintenance - Summary Monthly Progress reports - Summary Project Adminstration Support & Document Control - Summary Project Management (Lining) - Summary Project Management (Closure) - Summary Home office support of construction - Summary	326 448 458 458	0% 03-Aug-20 A 0% 03-Aug-20 A		i i i												
X05000004.00 N X06000005.00 F X07000006.00 F X08000005.00 F CONSTR0100.00 F CONSTR0100.00 F RD-BA0.CON C A13770.1330 1	Monthly Progress reports - Summary Project Adminstration Support & Document Control - Summary Project Management (Lining) - Summary Project Management (Closure) - Summary Home office support of construction - Summary	448 458 458	0% 03-Aug-20 A	10 1 00										: :			
X06000005.00 F X07000006.00 F X08000005.00 F CONSTR0100.00 F CONSTR0100.00 F RD-BA0.CON C A13770.1330 1	Project Adminstration Support & Document Control - Summary Project Management (Lining) - Summary Project Management (Closure) - Summary Home office support of construction - Summary	458 458	0% 03-Aug-20 A	18-Jan-22							-				·····;···		
X07000006.00 F X08000005.00 F CONSTR0100.00 F CONSTR0200.00 Ir RD-BA0.CON C A13770.1330 1	Project Management (Lining) - Summary Project Management (Closure) - Summary Home office support of construction - Summary	458	00/ 00 1 00 1	08-Jul-22													-
X08000005.00 F CONSTR0100.00 F CONSTR0200.00 In RD-BA0.CON C A13770.1330 1	Project Management (Closure) - Summary Home office support of construction - Summary		0% 03-Aug-20 A	22-Jul-22										+ +			;
CONSTR0100.00 H CONSTR0200.00 H RD-BA0.CON C A13770.1330 1	Home office support of construction - Summary	450	0% 03-Aug-20 A	22-Jul-22								;		+ +			;
CONSTR0200.00 In RD-BA0.CON (A13770.1330 1		458	0% 03-Aug-20 A	22-Jul-22								;		+ +			;
RD-BA0.CON C A13770.1330 1		330	0% 08-Apr-21	26-Jul-22													L
A13770.1330 1	Incorporation of as-builts - Summary	40	0% 14-Jun-22	09-Aug-22													-
A13770.1330 1	Construction, Startup, and Implementation	328	27-May-21	29-Aug-22													-
A12770 1240 1	1A. Drawdown Waterlevel Within Ponds	17	0% 27-May-21	21-Jun-21													1
A13770.1340 1	1B. Install New Supply Pipe Through Dividing Berm	20	0% 22-Jun-21	20-Jul-21												1	
	1C. Install Temporary Supply Pipe from Dividing Dike to Recirculation Pumphouse	20	0% 22-Jun-21	20-Jul-21													
	1D. Install New Temporary Bulkheads In Recirculation Pumphouse	20	0% 22-Jun-21	20-Jul-21													-
	1E. Cease Flows to South Pond	1	0% 21-Jul-21	21-Jul-21													-
	2A. Dewater South Pond	5	0% 22-Jul-21	28-Jul-21													-
	2C. Remove Existing Water Treatment System and Associated Equipment	20	0% 29-Jul-21	25-Aug-21													
	6B. Demolish or Relocate Metal Cleaning Waste Tank	53	0% 22-Jun-21	03-Sep-21													
	2D. Remove CCR Material from within South Pond	40	0% 29-Jul-21	23-Sep-21													-
	2E. Certify All CCR Has Been Removed From South Pond	0	0% 24-Sep-21	24-Sep-21	-							-					-
	2B. Remove Existing Sheet Pile Wall	20	0% 27-Aug-21	27-Sep-21								-				-	-
	3A. Install EPA CCR Rule-Compliant Liner System in South Pond	40	0% 24-Sep-21	18-Nov-21													-
	3C. Extend BATW Pipes to South Pond	40	0% 24-Sep-21	18-Nov-21													
	3B. Install New Dewatering and Staging Area	30	0% 18-Oct-21*	30-Nov-21													-
	4A. Direct BATW to South Pond	1	0% 30-Nov-21	30-Nov-21													-
	4C. Allow South Pond to Refill to NWL	10	0% 01-Dec-21	14-Dec-21													-
	4B. Remove the Temporary Supply Pipe and Temporary Bulkheads	14	0% 01-Dec-21	20-Dec-21													-
	5A. Install Temporary LVW Impoundment In North Pond	14	0% 01-Dec-21	20-Dec-21													
	5B. Isolate LVW Flows to the Temporary LVW Impoundment	1	0% 21-Dec-21	21-Dec-21	-												-
	6A. Dewater South Portion of North Pond	14	0% 22-Dec-21	13-Jan-22													-
A13770.1540 6	6C. Remove CCR Material from South Portion of North Pond	200	0% 22-Jun-21	06-Apr-22	_												1
A13770.1550 6	6D. Certify Clean Closure of South Portion of North Pond	1	0% 07-Apr-22	07-Apr-22													1
A13770.1440 7	7A. Reconfigure Outfall 023 and Install New Drain Pipe	20	0% 08-Apr-22	05-May-22										1			
A13770.1570 7	7C. Reconfigure LVW Piping to North Pond	20	0% 08-Apr-22	05-May-22	_												
A13770.1520 7	7B. Install OHIO EPANPDES Compliant Liner in South Portion of North Pond	44	0% 08-Apr-22	08-Jun-22													1
A13770.1580 7	7D. Direct LVW Flows to South Portion of North Pond	1	0% 09-Jun-22	09-Jun-22													1
A13770.1590 8	8A. Dewater North Portion of North Pond	5	0% 10-Jun-22	16-Jun-22													-
A13770.1600 8	8B. Remove CCR Material from North Portion of North Pond	15	0% 17-Jun-22	08-Jul-22													
A13770.1610 8	8C. Certify Clean Closure of the North Portion of North Pond	1	0% 11-Jul-22	11-Jul-22													-
A13770.1620 9	9A. Install Ohio EPANPDES Compliant Liner in North Portion of North Pond	20	0% 12-Jul-22	08-Aug-22													-
A13770.1560 9	9C. Relabel Ponds	1	0% 09-Aug-22	09-Aug-22													-
A13770.1630 9	9B. Allow North Pond to Refill to NWL	14	0% 09-Aug-22	26-Aug-22													1
A13770.1300 F	Ready for Operations	0	0%	29-Aug-22													
CRD-BA0.CON.OU	JT Outage Tie-Ins	22	25-Sep-21	16-Oct-21													1
BAOUT.U3 L	Unit 3 Bottom Ash Outage Tie-In	5	0% 25-Sep-21	29-Sep-21													-
BAOUT.U1 L	Unit 1 Bottom Ash Outage Tie-In	5	0% 01-Oct-21	05-Oct-21													1
BAOUT.U2 L	Unit 2 Bottom Ash Outage Tie-In	5	0% 12-Oct-21	16-Oct-21													
Remaining LActual Work	Level of Effort Milestone				Engineer	ing, P	rocuren		ge 8 of 8 • Cons i		ion s	Sche	dule	by V	/BS		
Remaining V	Nork				2	-								-			
Critical Remaining																	



3.0 PROJECT SCHEDULE: NARRATIVE DISCUSSION

This section presents a narrative of the project steps and sequencing necessary to develop the alternative disposal capacity selected to replace the existing BAP Complex. This narrative follows and supplements the visual timeline representation of the project schedule provided in provided in Section 2.0.

Section 3.1 presents the steps Cardinal will take to retrofit the South Pond and repurpose the North Pond and the general sequence in which these steps will occur. This workflow is based on the steps necessary to execute the project and is considered to be the fastest feasible timeline in which the South Pond can be retrofitted with an EPA CCR Rule-compliant composite liner system and the North Pond can be repurposed as a non-CCR waste water basin. The subsequent sections discuss the steps that occur within each phase of the project (as shown in the visual timeline representation), including the tasks that occur during each of those steps.

See Section 4.0 for a narrative discussion of the progress the Cardinal Operating Company has made to date in developing this alternative disposal capacity for the BAP Complex.

3.1 INSTALLATION ACTIVITIES & PROJECTED WORKFLOW

As currently designed, the BAP Complex will be reconfigured by executing the following sequence of activities:

- Designing and permitting the retrofitted South Pond and repurposed North Pond;
- Procuring a general work contractor to perform the work;
- Retrofitting the South Pond:
 - Installing a temporary pipe system to supply the Recirculation Pumphouse from the North Pond during the South Pond retrofit work;
 - o Dewatering the pond and excavating the CCR and CCR-impacted soils (if any) therein;
 - Performing leveling and grading;
 - o Constructing a new dredge staging and CCR dewatering area;
 - o Removing several existing pond features, including:
 - Transfer pumps, chemical treatment systems, and associated equipment,
 - A portion of the pond equalization pipe from North Pond discharge structure (sealing the pipe thereafter), and
 - The partition wall in the South Pond;
 - Installing the composite liner system:
 - Compacting and rolling smooth the exposed subgrade,
 - Placing and compacting a 2-foot-thick clay layer,
 - Installing a 60-mil HDPE geomembrane liner,
 - Placing a non-woven geotextile, and

- Installing a protective layer of gravel, riprap, and/or concrete (varies within the South Pond);
- Extending the existing BATW pipes to the retrofitted South Pond; and
- o Certifying and commissioning the retrofitted South Pond;
- Repurposing the southern portion of the North Pond:
 - o Constructing a temporary impoundment in the northern portion of the pond,
 - o Isolating LVW streams to the temporary impoundment,
 - o Dewatering and excavating the CCR and CCR-impacted soils (if any) in the area,
 - o Certifying the area as clean-closed,
 - Installing a new liner system:
 - Compacting and rolling smooth the exposed subgrade,
 - Installing a 60-mil HDPE geomembrane liner, and
 - Placing a non-woven geotextile; and
 - Diverting LVW streams to the repurposed portion of the North Pond.

3.2 ENGINEERING & DESIGN

Before construction can begin on the BAP Complex, detailed engineering and design work must be completed which includes preparing the design drawings and specifications required to execute the work. The engineering and design work began in April 2020 and is scheduled to be completed in April 2022. The timeline for the engineering and design work was based on experience from similar pond retrofit projects and on engineering judgement. The anticipated engineering work for this project is broken out into the following categories: General, Civil, Structural, Mechanical, Electrical, and Instrumentation and Controls (I&C).

3.2.1.1 GENERAL

The General engineering and design work encompasses tasks that do not fall under one specific discipline. This phase involves tasks that are required by the other disciplines prior to detailed design and is projected to span from April 2020 through December 2020. The work will include:

- Preparing a project design basis and criteria,
- Preparing general arrangement drawings of the project site,
- Updating the project cost estimate based on the more detailed engineering and design performed in this phase, and
- Conducting design reviews.

In addition to the preceding tasks, the Cardinal Operating Company will prepare the semi-annual progress reports on the development of this alternative disposal capacity for the BAP Complex in accordance with 40 CFR 257.103(f)(1)(x). Pursuant to 40 CFR 257.103(f)(1)(xi), these reports will be prepared by April 30 and October 31 of each year for the duration of the project. Based on having alternative disposal capacity

available by the end of April 2022 for all of the CCR and non-CCR waste streams currently being managed in the BAP Complex, the Cardinal Operating Company anticipates submitting three of these progress reports to the EPA.

3.2.1.2 CIVIL

The Civil engineering and design work began in July 2020 and is scheduled to be substantially completed by April 2021. This phase involves tasks like preparing drawings, various permitting support documents, and the required EPA CCR Rule compliance demonstrations:

- Drawings:
 - Civil general notes and details,
 - o Temporary erosion control,
 - Pond lining,
 - Civil sitework demolition, and
 - o Roads and paving.
- Permitting Documents:
 - o Ohio EPA Storm Water Pollution Prevention Plan (SWPPP) for construction,
 - o Ohio EPA permitting documents support, and
 - Ohio DNR dam modifications permitting support.
- EPA CCR Rule Compliance Demonstrations:
 - o Location Restrictions (40 CFR 257.60 through 64),
 - o Design Criteria (40 CFR 257.72 and 74),
 - o Operating Criteria (40 CFR 257.80, 82, and 83),
 - o Groundwater Monitoring (40 CFR 257.90 through 93), and
 - o Closure and Post Closure Care (40 CFR 257.102 and 104).

In addition to the preceding tasks, the Civil engineering and design work included the procurement of a topographic and bathymetric survey of the BAP Complex to provide the necessary site inputs for design calculations and design drawings, including:

- Depth of bottom ash in the BAP Complex;
- Existing dike alignments, slopes, and elevations; and
- Locations of existing structures, equipment, and piping.

The process of procuring a topographic and bathymetric survey procurement began in April 2020, and the contract was awarded to a surveyor in late July 2020. This process included preparing a technical specification for the work, issuing a bid package, and performing technical and commercial evaluations in order to confirm the bidders evaluated every aspect of the specification. The surveying work began in July

2020 and was completed in September 2020. The total approximate area that was surveyed was over 60 acres.

3.2.1.3 STRUCTURAL

The Structural engineering and design work began in September 2020 and is scheduled to be completed in April 2021. Within this subcategory, the following drawings and support documents will be prepared:

- Concrete general notes and details,
- Modifications to the existing Outfall 023 structure,
- Pipe road crossing trenches,
- Foundations for miscellaneous structural pads and pipe supports,
- Pumphouse bulkheads, and
- Structural steel for pipe supports and auxiliary steel.

To support the preceding tasks, site walkdowns will be performed to gather necessary structural engineering and design inputs for the project.

3.2.1.4 MECHANICAL

The Mechanical engineering and design work began in May 2020 and is scheduled to be completed in April 2021. Within this subcategory, drawings and piping and instrumentation diagrams (P&IDs) will be prepared, including:

- Mechanical general notes and details;
- Demolition drawings for:
 - o BATW piping,
 - o LVW piping,
 - o Metal cleaning waste tank facility, and
 - o Chemical treatment system;
- P&IDs, isometric and composite drawings, and/or pipe supports for:
 - o Blowdown to the Unit 3 FGD,
 - o Existing system tie-ins for the recirculation system,
 - Existing system tie-ins for BATW from Units 1 and 2,
 - Existing system tie-ins for BATW from Unit 3,
 - o Existing system tie-ins for LVW,
 - Temporary piping from the North Pond to the Recirculation Pumphouse
 - Unit 1 and 2 service water system tie-ins, and
 - o Ash hopper piping;
- Control valve data sheets; and
- Lists for pipelines and valves.

To support the preceding tasks, site walkdowns will be performed to gather necessary mechanical engineering and design inputs for the project.

3.2.1.5 ELECTRICAL

The Electrical engineering and design work began in July 2020 and is scheduled to be completed in April 2021. Within this subcategory, drawings and calculations will be prepared, including:

- o Wiring drawings,
- o Cable tabulations, and
- o Electrical installation drawings.
- o Electrical walkdown summary.

To support the preceding tasks, site walkdowns will be performed to gather necessary electrical engineering and design inputs for the project.

3.2.1.6 INSTRUMENTATION & CONTROLS (I&C)

The I&C engineering and design work began in July 2020 and is scheduled to be completed in February 2021. Within this subcategory, drawings and calculations will be prepared, including:

- o Logic control descriptions,
- o I/O Database list, and
- o Instrument list and details.

To support the preceding tasks, site walkdowns will be performed to gather necessary I&C engineering and design inputs for the project.

3.3 PROCUREMENT

3.3.1 CONTRACTOR SELECTION

3.3.1.1 GENERAL WORK CONTRACTOR

The Cardinal Operating Company intends to hire one General Work Contractor to retrofit the South Pond and install the ancillary pond features. The General Work Contractor selection process is scheduled to begin in November 2020. The technical specification will take approximately two months to prepare and review, which will be performed concurrently with the corresponding engineering design drawings to be included with the specification in the bid package. This bid package is expected to be released to qualified contractors in early January 2021, and the subsequent bid period is expected to last approximately six weeks in order to give the bidders adequate time to assess, understand, price, and develop a plan for executing the scope of work.

Once all bids are obtained by mid-February 2021, the Cardinal Operating Company will assess the bids on a technical and commercial basis. The bid evaluation phase is expected to take six weeks in order to provide adequate time to thoroughly review each proposal, which may include asking bidders questions, ensuring each bid addresses all aspects of the scope of work, addressing any exceptions taken by the bidders in the technical and/or commercial terms, and ultimately selecting the winning bidder for the general work contract. Immediately after this bid evaluation phase, Cardinal will conform the commercial terms and technical specification with the winning bidder and subsequently award the contract. This last phase is expected to take about three weeks, which would have the general work contract awarded in early April 2021.

3.3.1.2 CONSTRUCTION QUALITY ASSURANCE

The Cardinal Operating Company also intends to hire a Construction Quality Assurance (CQA) Contractor to inspect the General Work Contractor's work to ensure it meets the performance standards specified in the construction contract. The CQA Contractor selection process will commence after the bid package for the General Work Contractor is released in early January 2021 and will go through a similar procurement process. A technical specification will be prepared detailing the work required of the CQA, which is expected to take approximately one month to prepare and review. The CQA bid package will then be issued to qualified CQA contractors; this is expected to occur in early February 2021. Given the nature of this work, the bid period and subsequent evaluation phase are only expected to take three weeks each. Thus, the Cardinal Operating Company expects to have bids for the CQA work reviewed for technical and commercial conformance by mid-March 2021. Like the general work contract, it is expected that the specification will be conformed with and awarded to the selected CQA Contractor within two weeks of completing the bid evaluation. Thus, the CQA Contractor for the project is expected to be hired around the end of March 2021, which is around the same time the Cardinal Operating Company anticipates awarding the general work contract.

3.3.2 EQUIPMENT FABRICATION & DELIVERY

Immediately after executing the general work contract in early April 2021, the manufactured materials required for the project (*e.g.*, HDPE geomembrane, piping) will be ordered. Some of these materials are expected to be long lead-time components, so ordering them in early spring of 2021 reduces the risk of supply delay by the time these materials are installed in the fall of 2021. In particular, the HDPE geomembrane for the South Pond's composite liner system is expected to have a long lead time to procure given the anticipated surge in CCR pond work.

The following subsections discuss how the Cardinal Operating Company anticipates the various materials required to execute this project will be procured.

3.3.2.1 CLAY, GRAVEL, & RIPRAP

Once the General Work Contractor has been awarded the construction contract, the contractor will work with the Cardinal Operating Company to find and select borrow sites for the clay, gravel, and riprap materials for the project. In particular, contractor will need to evaluate whether a clay borrow site has suitable material to meet the low hydraulic conductivity specified for the South Pond's composite liner system and whether it can be delivered to the project site on time.

It is expected that the borrow sites for clay, gravel, and riprap will be selected within a month after the construction contract is awarded. It is anticipated that the clay borrow site will be located within 20 miles of Cardinal, whereas the gravel and riprap are expected to come from borrow sites located between 30 and 60 miles away from the plant. A four-month delivery duration was scheduled for all three materials to provide an adequate window of time to ensure the materials are at the project site before the composite liner installation work begins in September of 2021.

3.3.2.2 GEOMEMBRANE & GEOTEXTILE

Concurrent with identifying borrow sites for the soil materials, the General Work Contractor will order the geosynthetic materials required for the project. Once the panels are ordered, the vendor will begin the fabrication process. From prior projects, experience with geomembrane/geotextile vendors, and the anticipated demand for geosynthetic materials for EPA CCR Rule compliance work, the fabrication time is expected to be approximately 70 days. Potential vendors that supply geomembrane and/or geotextile are between 100 and 350 miles away from the station. Accordingly, a 20-day delivery duration was scheduled to provide an adequate window of time to ensure the materials are at the project site before the composite liner installation work begins in September of 2021.

3.3.2.3 CONCRETE

Immediately after being awarded the contract to reconfigure the BAP Complex (beginning of April 2021), the General Work Contractor will begin contacting ready-mix concrete suppliers to furnish and deliver the concrete being installed over a portion of the composite liner system in the South Pond. Several potential ready-mix concrete suppliers are located within a 20-mile radius of the Cardinal site, including Brilliant and Steubenville, Ohio. Therefore, it is expected that the concrete for the retrofitted pond will be prepared at one of these plants and delivered to the site via ready-mix trucks. Given the proximity of these plants, ready-mix trucks should have adequate time to deliver and discharge the concrete in accordance with ASTM C94, "Standard Specification for Ready-Mixed Concrete," which requires concrete be discharged within 90 minutes after hydration commences.

3.3.2.4 PUMPS, PIPES, & VALVES

The final materials required for the project are the new pumps, pipes, and valves required for modifications to the existing CCR and non-CCR pipelines and upstream equipment. Like the other materials, these items will also be ordered once the General Work Contractor is awarded the project. These materials are expected to be delivered by mid-July 2021 since the installation of the new pumps is one of the earliest tasks on the construction schedule. Thus, the General Work Contractor is expected to have these materials ordered within two weeks after starting the project.

From prior projects and experience with pump, HDPE pipe, and valve vendors, the fabrication time was scheduled for 40 days. Potential vendors that supply these items are located between 30 and 110 miles from the plant site. Accordingly, a 20-day delivery duration was scheduled to provide an adequate window of time to ensure the equipment arrives at to the Cardinal station in time for it to be installed.

3.4 CONSTRUCTION, STARTUP, & IMPLEMENTATION

After being awarded the contract in early April 2021, the General Work Contractor will start mobilizing to the site. As previously mentioned, the BAP Complex must continue operating until the station's new dry fly ash-handling system is operational and FAR II is no longer needed. Per the Cardinal Operating Company's corresponding workplan for replacing FAR II, the dry fly ash-handling system is expected to be operational by June 7, 2021. Thus, the General Work Contractor for this project is expected to be fully mobilized to the site by late May, early June 2021. Upon mobilizing to the site, construction is anticipated to follow a multiphase approach to allow Cardinal to continue operating without major outages while the Bottom Ash Pond Complex is reconfigured.

The following construction schedule assumes that the General Work Contractor and its subcontractors (if any) will normally work five days per week at 10 hours per day.

3.4.1 PHASE 1: INITIATE DEWATERING & RE-ROUTE NORTH POND OUTFLOW

Before the water and ash in the South Pond can be removed, the pond needs to be isolated from the operations of the BAP Complex. This will be accomplished by installing a temporary supply pipe between the Recirculation Pumphouse and the North Pond. This work is scheduled to commence at the end of June 2021.

In order to install the temporary supply pipe in a dry condition, the water levels in the North and South Ponds will be lowered. This drawdown process is expected to start in May of 2021 after the contractor has partially mobilized to the site. The water level will be lowered by about seven feet in each pond, which will allow the Recirculation Pumphouse to continue supplying water to Cardinals' fly ash-handling system while the South Pond is being retrofitted. Approximately 390 million gallons of water in the South Pond and 1,100 million

gallons of water in the North Pond are expected to be removed during the drawdown process. The removed water will be directed to the Ohio River through NPDES-permitted Outfall 023 using temporary pumps located along the perimeter dike. The effluent limitations of Cardinal's NPDES permit will be maintained during the discharge of BATW as required to perform the necessary improvement. Compliance will be monitored in strict accordance with the applicable permits.

Once the water levels in both ponds are drawn down, the temporary supply pipe will then be installed through the dividing berm by excavating, installing and backfilling the pipe on the north side of the dike. Once the northern portion of the pipe is installed, the North Pond will be refilled to its working water elevation. The contractor will then repeat the same process on the south side of the dike. The temporary supply pipe will ultimately run through the existing dike where it will then connect to the Recirculation Pumphouse. This pipe will be approximately 300 feet from the existing outlet structure in the North Pond to the connection to the Recirculation Pumphouse. At its connection to the pumphouse, the temporary pipe will feature a manifold attached to temporary bulkheads that will be installed at the entrance of each pump bay to prevent water remaining in the South Pond from entering the pumphouse.

Once the North and South Ponds are segregated and a new flow path is established for the North Pond, all waste water streams will cease entering the South Pond, which can then be fully dewatered. Based on the work required, it is currently anticipated that approximately two months will be necessary to complete this task. Therefore, it is expected that the General Work Contractor can begin dewatering and removing CCR material from the South Pond by the end of July 2021.

3.4.2 PHASE 2: CLEAN OUT SOUTH POND

After all waste water is diverted away from the South Pond, the General Work Contractor will continue dewatering the pond until all free water remaining from Phase 1 is removed. It is estimated that approximately six feet of free water, the equivalent of 270 million gallons, will need to be removed at this time. This water will be removed in the similar manner as the pond drawdown work in Phase 1 but may be sent to the North Pond in lieu of Outfall 023 if space is available.

Once the water in the South Pond is removed, the General Work Contractor will remove the pond's water treatment system and the existing sheet pile wall currently separating the South Pond into two areas. At this point the contractor can begin removing CCR material and any CCR-impacted soils from the pond. Based on the recently-completed bathymetric survey and historical design drawings, it is anticipated that approximately 44,000 cubic yards of CCR will be removed during this phase. All removed CCR and CCR-impacted soils will be transported to FAR I Landfill for final disposal. Appropriate fugitive dust control measures (*e.g.*, water spray) will be implemented to minimize airborne CCR particulates while the CCR is being handled.

Based on the amount of water and CCR to be removed, it is anticipated that the General Work Contractor will need approximately two months to complete this phase. Therefore, it is expected that the South Pond will be free of CCR and CCR-impacted soils by the end of September 2021.

3.4.3 PHASE 3: RETROFIT SOUTH POND

Once the CCR material and CCR-impacted soils are removed from the South Pond, the composite liner system can be installed. The General Work Contractor will first compact and roll smooth the pond floor as necessary to ensure the subgrade is firm, clean, and smooth. After the CQA Contractor verifies the condition of the subgrade, the General Work Contractor will proceed with installing the clay component of the composite liner system. The clay will be placed in lifts, with each lift compacted to provide a hydraulic conductivity not exceeding 1×10^{-7} cm/sec in accordance with 40 CFR 257.70(b). Concurrent with the contractor placing and compacting the clay layer, the CQA Contractor will verify the lifts are indeed compacted to the specified performance criteria (*i.e.*, density, moisture content, and lift thickness).

Subsequent to placing and compacting the clay component of the composite liner system, panels of HDPE geomembrane will be deployed over the clay. Adjacent panels will be overlapped and thermally welded together. Like the clay component, the CQA Contractor will inspect the deployment of the geomembrane panels and the welds connecting them for conformance with the project specifications. Once the HDPE geomembrane liner is in place, the General Work Contractor will then begin placing the non-woven geotextile. The geotextile will be placed in panels and subsequently overlapped and sewn together at the seams.

The protective layer will be the final component of the composite system liner that is installed. As discussed in Section 1.4.1, this protective layer will vary across the South Pond due to different dredging frequencies expected in these areas during the pond's operating life. The various thicknesses of riprap, gravel, and concrete will be placed once the geotextile has been installed. The gravel and riprap layers will require some light compaction, while the concrete layer will be placed once the gravel and riprap have been positioned.

As the composite liner system is being installed, the new dredge staging and CCR dewatering area will be constructed near the new BATW discharge point into the South Pond. This area will be built over the new composite liner system with an 8-in.-thick protective layer of gravel. Compacted bottom ash excavated from the North Pond will be used to raise this area approximately three feet above the retrofitted pond's normal operating water level. Finally, the existing BATW discharge pipes will be extended south along the western berm of the BAP Complex to the South Pond.

This phase is currently scheduled to begin in the end of September 2021. The composite liner system is expected to require 26,000 cubic yards of clay; 33,000 square yards of geomembrane and geotextile; and over 6,000 cubic yards of aggregate (gravel and/or riprap) and concrete. Based on the work required, it is

currently anticipated that approximately two months will be necessary to complete this task. Therefore, it is expected that the composite liner system will be fully installed in the South Pond by mid-November 2021.

3.4.4 PHASE 4: COMMISSION & CERTIFY RETROFITTED SOUTH POND

After the new composite liner system has been installed in the South Pond and once the BATW lines have been extended thereto, the retrofitted pond will be certified in accordance with 40 CFR 257.102(k)(4). At this point, Cardinal will have alternative bottom ash disposal capacity available and will immediately begin sluicing BATW to the South Pond to store and treat the station's bottom ash. Thus, per the project schedule, it is expected that Cardinal will have alternative disposal capacity for the CCR waste streams currently sent to the existing BAP Complex by November 30, 2021.

Once the retrofitted South Pond is operational, the four recirculation pumps in the pond will be taken out of service. Meanwhile the four recirculation pumps for the North Pond will remain in service in order to continue segregating the LVW streams in the North Pond from the BATW in the South Pond. Once the South Pond's recirculation pumps are shutdown, the temporary bulkheads installed during Phase 1 will be removed in order to allow water to begin entering the South Pond. At this point, the temporary supply pipe from the North Pond to the Recirculation Pumphouse will be removed.

In order to remove the temporary supply pipe, the valve at the north end of the pipe will be closed and the pipe will be drained of excess water from the branch pipe valves at the Recirculation Pumphouse. At this point, the temporary bulkheads can be removed from the four northernmost openings. The temporary supply pipe will then be removed. up until the upstream side of the dividing dike. The rest of the pipe will remain within the dike to mitigate the risk of otherwise compromising the South Pond's new composite liner system; accordingly, the pipe will be sealed and filled with grout. Supports for the temporary supply pipe will also remain in place with sleeves integrated into the composite liner system.

This phase is expected to take approximately three weeks to complete once the retrofitted South Pond is operational. Therefore, it is expected that the temporary supply pipe and bulkheads will be removed by the late December 2021.

3.4.5 PHASE 5: INSTALL TEMPORARY IMPOUNDMENT IN NORTH POND

Once the retrofitted South Pond is operational, the General Work Contractor will begin repurposing the North Pond into a non-CCR waste water basin. As previously stated, this conversion will be accomplished by repurposing the southern portion of the pond first, followed by the northern portion. In order to start dewatering the CCR in the southern end of the pond, the LVW streams entering the North Pond will need to be isolated from the area.

In order to prevent LVW streams from entering the southern portion of the North Pond, a temporary impoundment will be installed in the pond's northwest corner to contain the waste during construction. The temporary impoundment will be formed by excavating bottom ash stored in the area to form a bowl shape with side slopes of 3H:1V or shallower. The excavated material will then be used to contract a dike between the temporary LVW impoundment and the rest of the North Pond. Once the dike is constructed, approximately 3,300 square yards of geomembrane will be temporarily placed on top of impoundment floor and will be held in place with washed gravel for ballast (as needed). Finally, the LVW streams will then be directed to the temporary impoundment and thus isolated from the rest of the North Pond.

Based on the amount of work needed to install the temporary LVW impoundment, it is anticipated that the General Work Contractor will need approximately three weeks to complete this phase. However, this phase can and is expected to be performed concurrently with Phase 4. Therefore, it is expected that the temporary LVW impoundment will be installed by late December 2021.

3.4.6 PHASE 6: CLEAN CLOSE SOUTHERN PORTION OF NORTH POND

Once the LVW streams have been isolated to the temporary impoundment, the contractor can begin the process of clean closing the southern portion of the new LVW Pond. However, given that approximately 310,000 cubic yards of CCR are expected to be removed from this area of the pond, it is anticipated that the General Work Contractor will start removing material from this pond after the water level is drawn down in the pond during Phase 1. The station regularly dredges material from the North Pond from an elevated area within the pond limits, where the excavated ash is dewatered and then transported to FAR I Landfill for disposal. It is expected that the contractor will follow a similar process to remove material from the North Pond even while it continues operating during the South Pond retrofit work (Phases 1 through 3).

Following the diversion of LVW streams to the temporary impoundment, the CCR remaining in the North Pond from the initial excavation work during Phases 1 and 3 will be dewatered using temporary pumps located along the perimeter dikes. This water will be discharged to the Ohio River through Outfall 023 in strict accordance with Cardinal's NPDES permit.

Once the water in the area has been removed, the General Work Contractor can begin removing CCR material and any CCR-impacted soils (if any) from the southern portion of the North Pond. At this point, the equipment in the aforementioned elevated dredging area will also be removed, including a 70-foot diameter, 40-foot tall metal cleaning waste tank and over 30 tons of auxiliary piping. All removed CCR and CCR-impacted soils will be transported to FAR I Landfill for final disposal. Appropriate fugitive dust control measures (*e.g.*, water spray) will be implemented to minimize airborne CCR particulates while the CCR is being handled. Finally, once all CCR and CCR-impacted soils have been removed, the southern portion of the North Pond will be certified as clean-closed in accordance with 40 CFR 257.102(f)(3).

Based on the amount of water, CCR, and equipment to be removed, it is anticipated that the General Work Contractor will need about three months to complete this phase after the LVW impoundment is installed. Therefore, it is expected that the southern portion of the North Pond will be clean-closed by early April 2022.

3.4.7 PHASE 7: INSTALL LINER SYSTEM IN SOUTHERN PORTION OF NORTH POND

As soon as the southern portion of the North Pond is certified as clean-closed, Outfall 023 will be relocated and a new drainpipe will be installed to discharge LVW streams from the repurposed North Pond. About 160 linear feet of piping will be installed from the existing outfall structure through the eastern dike to create the reconfigured Outfall 023.

While Outfall 023 is being reconfigured, an Ohio EPA NPDES-compliant liner will be installed in the cleanclosed, southern portion of the North Pond. This liner will consist of, from bottom to top, a 60-mil geomembrane and a non-woven geotextile. Approximately 110,000 square yards of each geosynthetic material is expected to be needed to line this area. As the liner is being installed, the LVW gravity piping will be temporarily extended to the southern portion of the North Pond, while the pressurized piping will be permanently rerouted to this area.

Once the LVW piping is reconfigured and the new liner is installed, the LVW streams will be directed to the southern portion of the North Pond, marking the completion of alternative disposal capacity for the LVW streams. Based on the amount of work required to install the liner system in the southern portion of the North Pond, it is anticipated that the General Work Contractor will need approximately two months to complete this phase. Thus, per the project schedule, it is expected that Cardinal will have alternative disposal capacity for the non-CCR waste streams currently being sent to the existing BAP Complex by June 9, 2022.

3.4.8 PHASES 8 & 9: COMPLETE LINER INSTALLATION IN NORTH POND

Once the LVW lines are diverted away from the temporary impoundment, the northern portion of the North Pond will be dewatered. All of the CCR material and CCR-impacted soils (if any) will be removed from this area and from underneath the temporary impoundment. Upon removing the CCR and CCR-impacted soils, the northern portion of the North Pond will be certified as clean closed per 40 CFR 257.102(f)(3). Afterwards, any necessary leveling and grading work can occur as specified in the construction drawings. Once the grading work is complete, an Ohio EPA NPDES-compliant liner system can be installed. Immediately thereafter, the entire North Pond will have been repurposed, can refill to its normal operating water level, and can begin operating exclusively as an LVW pond.

This phase of the project will begin after the southern portion of the North Pond starts receiving LVW streams on June 9, 2022. Given the amount of material to be removed and the area to be lined, it is expected that the entire LVW pond will be operational by the end of August 2022.

4.0 PROJECT SCHEDULE: PROGRESS TO DATE

This section presents a narrative of the progress the Cardinal Operating Company has made in retrofitting the South Pond and repurposing the North Pond for the BAP Complex's CCR and non-CCR waste streams, respectively. The project was authorized in April 2020, and the engineering and design work commenced shortly thereafter.

To date, the Cardinal Operating Company has finished preparing the project design basis, general arrangement drawings, and an updated cost estimate. In addition to these general engineering and design tasks, many of the discipline-specific activities are underway. Most of the P&IDs for the project have been prepared and issued for design, including the diagrams for the new FGD blowdown line, tie-ins to existing plant systems (bottom ash, recirculation, LVW, and service water). Finally, A 25% design review meeting was held to discuss the engineering and design work accomplished thus far in early September, and a follow-up meeting is scheduled for the end of November 2020 when the design work is expected to be about 60% complete. In addition, the Cardinal Operating Company is currently in the process of finalizing Ohio permitting requirements for the Engineering and Surface Water Controls, NPDES, and Dam modifications. These permit applications are expected to be submitted to the appropriate agencies prior to the end of 2020.

Finally, the Cardinal Operating Company has obtained a topographic and bathymetric survey of the BAP Complex area to provide the necessary design inputs for the engineering and design work to reconfigure the area. The initial survey was received at the end of August 2020 and was finalized a few weeks thereafter in late September 2020.

5.0 REFERENCES

- 1. 40 CFR Part 257 Subpart D, "Standards for the Disposal of Coal Combustion Residuals in Landfills and Surface Impoundments."
- 2. United States Court of Appeals, District of Columbia Circuit, *Utility Solid Waste Activities Group et al. v. Environmental Protection Agency*, No. 15-1219, 08/21/2018.
- Ohio Environmental Protection Agency, "Fact Sheet Regarding an NPDES Permit To Discharge to Waters of the State of Ohio for Cardinal Operating Company," Public Notice No. 18-05-061, Ohio EPA Permit No. 0IB00009*WD, Application No. OH0012581, 05/21/2018.
- 4. Buckeye Power, "CCR Rule Compliance Data and Information," <u>https://ohioec.org/buckeye-power/ccr-</u> rule-compliance-data-information/, Accessed 10/20/2020.
- Environmental Protection Agency, "Hazardous and Solid Waste Management System: Disposal of Coal Combustion Residuals from Electric Utilities, Part VI (Development of Final Rule – Technical Requirements)," 80 Fed. Reg. 74, p. 21423, 04/17/2015.
- 55 Ohio Revised Code 5577, "Load Limits on Highways," <u>https://codes.ohio.gov/orc/5577</u>, Accessed 10/20/2020.
- Ohio Department of Transportation, "Transportation Data Management System, Location ID 541, LRS ID SJEFSR00007**C," <u>http://www.ms2soft.com/tcds/?loc=Odot&mod=tcds&local_id=541</u>, Accessed 10/20/2020.
- Environmental Protection Agency, "Steam Electric Reconsideration Rule," 85 Fed. Reg. 198, pp. 64650– 64723, 10/13/2020.
- 9. Environmental Protection Agency, "Effluent Limitations Guidelines and Standards for the Steam Electric Power Generating Point Source Category," 80 Fed. Reg. 212, pp. 67838– 67903, 11/03/2015.
- Environmental Protection Agency, "Hazardous and Solid Waste Management System: Disposal of Coal Combustion Residuals From Electric Utilities; A Holistic Approach to Closure Part A: Deadline to Initiate Closure," 85 Fed. Reg. 168, pp. 53516–53566, 08/28/2020.
- 11. Ohio Administrative Code, 3745-29-19, "Operational Criteria for an Industrial Solid Waste Landfill Facility," Effective 09/23/2014.



6677 Busch Blvd, Columbus, OH 43229 614.846.5757

6.0 Certification of Compliance

To demonstrate that the criteria in 40 CFR § 257.103(f)(1)(iii) has been met, the following information is provided pursuant to 40 CFR § 257.103(f)(1)(iv)(B) to demonstrate that the Bottom Ash Pond is in compliance with the CCR Rule.

6.1 Owners Certification of Compliance

In accordance with 40 CFR § 257.103(f)(1)(iv)(B)(1), I hereby certify that, based on my inquiry of those persons who are immediately responsible for compliance with environmental regulations at Cardinal Power Plant, the Bottom Ash Pond is in compliance with all requirements contained in 40 CFR § 257 Subpart D.

TC M. alban NK (S PRJ

Thomas M. Alban Vice President October 30, 2020

6.2 Compliance Documents

In accordance with 40 CFR § 257.103(f)(1)(iv)(B)(2) through (B)(8), the following documents are provided below:

§257.103(f)(1)(iv)(B)(2)(i)-(iii) – Maps of groundwater monitoring wells relative to CCR Unit, well construction and drilling logs, and seasonal groundwater flow maps.

\$257.103(f)(1)(iv)(B)(3) – Groundwater monitoring results through first 2020 Semi-Annual monitoring period. In addition, the most recent Annual Groundwater Report (January 2020) is also provided for reference.

§257.103(f)(1)(iv)(B)(4) – Description of site geology and stratigraphic cross sections. Text is provided from the Groundwater Monitoring Network Report in accordance with §257.91.

§257.103(f)(1)(iv)(B)(5) – Corrective Measures Assessment – Not applicable, the Bottom Ash Pond is currently in Assessment Monitoring and does not exceed Groundwater Protection

Standards.

\$257.103(f)(1)(iv)(B)(6) – Remedy Selection Report – Not applicable, as described above, the Bottom Ash Pond is currently in Assessment Monitoring and no remedy selection report is required.

§257.103(f)(1)(iv)(B)(7) – Structural Stability Assessment pursuant to §257.73(d) was completed in October 2016. The next Stability Assessment will be completed prior to October 2021.

\$257.103(f)(1)(iv)(B)(8) – Safety Factor Assessment pursuant to \$257.73(e) was completed in October 2016. The next Safety Factor Assessment will be completed prior to October 2021.

40 CFR 257.101 (f)(1)(iv)(B)(2)(i)

Maps of Groundwater monitoring well locations in relation to CCR Unit



Monitoring Well Network

- Compliance Sampling Location
 Background Sampling Location

Bottom Ash Pond

Notes - Monitoring well coordinates provided by **Buckeye Power**. - Site features based on information available in Groundwater Monitoring Network Evaluation - Cardinal Site - Bottom Ash Pond (Geosyntec, 2016) provided by **Buckeye Power.**





	Site Layout om Ash Complex	
Buckeye Pow	ver Cardinal Generating Plar Brilliant, Ohio	nt
Geosy		Figure
con	sultants	2
Columbus, Ohio	2018/01/25	2

40 CFR 257.101 (f)(1)(iv)(B)(2)(ii)

Well construction diagrams and drilling logs for all groundwater monitoring wells

EXPLANATION OF SYMBOLS AND TERMS USED ON BORING LOGS FOR SAMPLING AND DESCRIPTION OF SOIL

SAMPLING DATA



- Blocked-in "SAMPLES" column indicates sample was attempted and recovered within this depth interval.

- Sample was attempted within this interval but not recovered.
- 2/5/9 The number of blows required for each 6-inch increment of penetration of a "Standard" 2-inch O.D. split-barrel sampler, driven a distance of 18 inches by a 140-pound hammer freely falling 30 inches. Addition of one of the following symbols indicates the use of a split-barrel other than the 2" O.D. sampler:

2S -3S -

- 2¹/₂"O.D. split-barrel sampler

- 3" O.D. split-barrel sampler

- P Shelby tube sampler, 3" O.D., hydraulically pushed.
- R Refusal of sampler in very-hard or dense soil, or on a resistant surface.
- 50-2" Number of blows (50) to drive a split-barrel sampler a certain number of inches (2), other than the normal 6-inch increment.
- S/D Split-barrel sampler (S) advanced by weight of drill rods (D),
- S/H Split-barrel sampler (S) advanced by combined weight of rods and drive hammer (H).

SOIL DESCRIPTIONS

All soils have been classified basically in accordance with the Unified Soil Classification System, but this system has been augmented by the use of special adjectives to designate the approximate percentages of minor components as follows:

<u>Adjective</u>	Percent by Weight
trace	1 to 10
little	11 to 20
some	21 to 35
"and"	36 to 50

The following terms are used to describe density and consistency of soils:

<u>Term (Granular Soils)</u>	Blows per foot
Very-loose	Less than 5
Loose	5 to 10
Medium-dense	11 to 30
Dense	31 to 50
Very-dense	Over 50
Term (Cohesive Soils)	<u>Qu (tsf)</u>
Very-soft	Less than 0.25
Soft	0.25 to 0.5
Medium-stiff	0.5 to 1.0
Stiff	1.0 to 2.0
Very-stiff	2.0 to 4.0
Hard	Over 4.0

Page 1 of 2 BOTTOM ASH POND MONITORING WELL INSTALLATION CARDINAL PLANT, BRILLIANT, OH



		-		820,30				9.8	DAT			5 - 12/	
		METH	Ю				D. Hollow-stem Auger		COMP	LETION	DEPTH	5	2.0'
SAM	PLER				2" 0		plit-barrel Sampler			CONCION	ENGY IN	IDEV	
ELEV.	DEPTH, FEET	SAMPLE NUMBER	SAMPLE	SAMPLE EFFORT	N 60	SAMPLE REC-%	DESCRIPTION			CONSIST AL MOIS LIMIT	TURE CO	NTENT	TEST RESULTS
	- 0 -						AGGREGATE - 34 INCHES		10	20		40	
		1		47 _{/34/26}	75	100							
667.0		2		⁴ / _{21/30}	64	100	FILL: Hard brown silty clay, some fine to coarse sand, some fine to coarse gravel, cobbles, moist.						H=3.0
665.3	- 5 -	3		$\frac{15}{6}$	18	27	FILL: Medium-dense gray fine to coarse grave, little to some fine to coarse sand, trace silt to						
662.8		4		$\frac{40}{7}$ 7	59	67	some silty clay, cobbles, dry.						
		5		$\frac{4}{8}$ 5	11	87	FILL: Stiff to very-stiff brown silty clay, some to "and" fine to coarse sand, some fine to coarse gravel, contains fine to coarse sand seams and						H=2.5
	- 10-	6		$\frac{11}{6}$ 4	19	100	sandstone fragments, damp.						H=3.0
658.3		7		⁸ /5	16	100	FILL: Medium-dense fine to coarse gravel, some						H=2.5-3.5
		8		$\frac{18}{3}$ 7	19	67	to "and" fine to coarse sand, some clayey silt, damp becoming moist.						
	- 15-	9		$\frac{3}{5}$ 6	11 13	100 53	- 3" pocket of sand at 14.5'.						11-1-25
653.8		10 - 11		³ /3/7 ⁴ /3/	8	67	Stiff gray clayey silt, "and" fine to coarse sand, little to some fine gravel, moist.						H=1.25 H=1.25
652.3		12		3'3'3	8	53	Loose brown fine to coarse sand, "and" silty clay, some fine to coarse gravel, moist.						H=1.0
650.6	- 20-	13		7/8/5	16	93	Loose to medium-dense brown fine to coarse gravel, some to "and" fine to coarse sand, some						H=4.5
		14		4 ₆	14	80	silty clay, damp to moist.						
		15		5 ⁸ /8/4	15	67							
	- 25-	16		⁶ / _{3/2}	6	80							
643.8		17 ¥		⁴ / _{4/5}	11	73	Hard brown mottled with gray and dark-gray silty clay, little fine to coarse sand, trace fine to coarse gravel (shale fragments), slightly organic, damp.						H=3.0-4.0
641.0	-	18		² / ₂ /	4	100	Stiff dark-brown clayey silt, little to some fine to medium sand, slightly organic, damp.						H=1.25-2.2
WATI	└ 30- ER LE	VEL ·	Ţ	31.	.0	Ţ	27.5 SYMBOLS USED TO INDICATE TEST F	RESULTS		Drill Rod	Energy	Ratio :	0.75
	TER N			Inside 12/7	HSA		Z/.5 G - Gradation See H - Penetro Inside Well Q - Uncon Comp Separate W - Unit Dr 12/15/15 C - Consol. Curves D - Relativ	y Wt ()	(tsf) pcf)	Last Ca	libration		8/2/2013

LOG OF BORING NO. MW-BAP-1 Page 2 of 2 BOTTOM ASH POND MONITORING WELL INSTALLATION

Page	e 2 of	f 2		BOT	TON	A ASI	LOG OF BORING NO. MW-BAP-1 H POND MONITORING WELL INSTALLATIO ARDINAL PLANT, BRILLIANT, OH	ON				58	ME
LOCA								59.8	DAT		12/4/15		
DRILL			IO	D: _). Hollow-stem Auger		COMPL	ETION	DEPTH:	5	52.0'
SAMP					2" (plit-barrel Sampler						
ELEV.	0 FEET	SAMPLE NUMBER	SAMPLE	SAMPLE EFFORT	N 60	SAMPLE REC-%	DESCRIPTION	×			ENCY IN TURE CO X LIQUID		TEST RESULT
638.8	50	7							10	20	30 4	0	
		⊻_ 19	;	SH SH SI	1 1 1	100	Very-soft to medium-stiff brown, gray and dark-gray organic clayey silt, little fine sand, contains silt seams and lenses, contains seams of fine to coarse sand, wet.						H=0.0-0.25
	- 35-	20	;	SH SH SI	0 H	100	,						H=0.0-0.75
		21	;	SH SH SI	0	100							H=0.0-0.75
(20.7		22A		SH	0	100							
630.7 628.8	-40-	22B 22C		Sң	1	100	Very-loose gray fine to coarse sand, interbedded with silty clay seams, wet.						H=1.0-1.5
		23		¹ / ₂ /	6	60	Loose brown fine to coarse sand, trace fine gravel, trace silt, wet.						-
626.8							Dense brown fine to coarse gravel, some to "and" fine to coarse sand, trace silt.						-
-	45-												-
		24		13 _{/17/2}	3 50	47							G
		25		19 /14,	40	67							_
618.8	50-			1	8								-
617.3		26	2	⁹ /7 _/	8 19	47	Medium-dense brown fine to coarse sand, trace fine gravel, trace clay.						-
	55						Encountered water at 31.0'.Encountered cobbles at 4.4 and 18.2'.						-
	- 55-						 Borehole converted to monitoring well upon completions. See separate well completion diagram. Boring locations and elevation surveyed by 						
	- 60-						AEP. - Datum: Ohio State Plane South. - NAD 27/NAVD 29 (Plant Grid).						-
WATER WATE	R LEV ER NO	LL.	Ţ	Insid	1.0 e HSA 7/15		SYMBOLS USED TO INDICATE TEST F G - Gradation See Inside Well - Uncon Comp 12/15/15 T- Triax Comp	ry Wt	(tsf) (pcf)	Last Ca	l Energy llibration ll Rig Nu	Date :	8/2/2013

LOG OF BORING NO. MW-BAP-2 Page 1 of 2 BOTTOM ASH POND MONITORING WELL INSTALLATION

Pag	ge 1 o	f 2	I	BOT	ГОМ	I ASF	LOG OF BORING NO. MW-BAP-2 I POND MONITORING WELL INSTALLATIC ARDINAL PLANT, BRILLIANT, OH	DN				86	ME
LOC	ATION	I: N	. 81	19,792	2, E.	2,513	3,707 ELEVATION: 66	9.9	DATE	E:	12/2/15	- 12	/4/15
DRIL	LING	METH	IOD):	4-1/4	4" I.C	0. Hollow-stem Auger	C0	OMPLI	ETION I	DEPTH:	4	5.0'
SAM	PLER	(S):					plit-barrel Sampler						
ELEV.	DEPTH, FEET	SAMPLE NUMBER	SAMPLE	EFFORT	N_{60}	SAMPLE REC-%	DESCRIPTION				ENCY INI TURE CON X LIQUID	ITENT	TEST RESULTS
	- 0 -	• 2					AGGREGATE - 23 INCHES	<u> </u>	::2	0 3	<u>11001D</u>		
668.0		1	19	9/11/25	45	87	FILL: Dense to very-dense dark-gray fine to	=					
666.3		2	2:		79	47	coarse sand, trace to little fine gravel, trace to little silt, moist. FILL: Stiff to hard brown and dark-brown silty						-
	- 5 -	3	3	³ /11/8	24	60	clay, some to "and" fine to coarse sand, little to some fine to coarse gravel, few pockets of gravel, dry becoming damp.						H=2.0
		4	8	¹ /9/15	30	67							H=4.5
		5 - 6	4	^{'9} / ₁₃	28 19	80 60							-
	- 10-	- 7	7	^{'6} /9	13	87							•
		8	4	/ 5 /10/	23	80							H=2.0-4.5
655.4		9	2	^{'8} / ₃	14	53							H=2.5
	- 15-	10	3	[/] 6 _{/5}	14	67	FILL: Medium-stiff to very-stiff brown mottled with gray silty clay, some fine to coarse sand, little fine to coarse gravel, moist.						H=3.5
		11	3		9	87							H=1.0-2.25
650.3		12 - 13	3	^{'3} ^{'5} ^{'3} [']	10 9	67 87	FILL: Very-loose to loose dark-gray fine to						H=0.75-1.5 H=2.0
	- 20-	- 14	3	4 /4,	9	67	coarse sand, trace to little fine gravel, little silt, moist becoming wet.						-
		15		Н / 3 SH 1 H	0	100	- Contains sand seams at 20.0' to 20.3'.						
644.7	- 25-	16 - 17	1	¹ 1 ₁ 1	3	100							H=0.5
643.9		17 	S	H SH	0	53	FILL: Very-loose dark-gray silt, trace fine to coarse sand, slightly organic, wet.						H=2.0
641.9		⊻ ₁₉	S	'з Ӊ			fine sand, trace medium to coarse sand, slightly organic, silt seams, damp. Medium-stiff dark-gray organic clayey silt, little fine sand, damp.						
	_ ₃₀ _		∇	/SH/	0	100	SYMBOLS USED TO INDICATE TEST R	ESULTS			Energy I		H=1.0 0.75
	ER LE TER N		<u> </u>	29. Inside			Q - Uncon Comp See H - Penetro		sf)		Energy I libration		<u>0.75</u> 8/2/2013
		ATE:		12/15			T - Triax Comp Copulate D - Relativ		±/		l Rig Nu		S&ME
JOR	7217-1	5-0071	B				-CONTINUED-						ATV 550-2

Page 2 of 2 BOTTOM ASH POND MONITORING WELL INSTALLATION CARDINAL PLANT, BRILLIANT, OH

	\$ 5	&ME
ATE:	12/2/15	- 12/4/15
APLETIO	N DEPTH:	45.0'

LOCA	TION:	N.	819,79	2, E.	2,513	3,707 ELEVATION: 66	9.9	DATI	Ξ:	12/2/15	5 - 12	/4/15
DRILL		-				D. Hollow-stem Auger		COMPL	ETION	DEPTH:	4	5.0'
SAMP	LER(S	5):		2" O).D. S	plit-barrel Sampler						
		· -					NA	TURAL C	ONSIST	ENCY IN	DEX	
ELEV.	C DEPTH, FEET SAMPLE	SAMPLE NUMBER SAMPLE	SAMPLE EFFORT	60	SAMPLE REC-%	DESCRIPTION		NATURA	L MOIS	TURE CO	NTENT	TEST
E	BE		SAN	N 60	RE	DESCIMI HOIV			тмт <i>т</i> — _	-X - 1 1 01110	LIMIT	RESUL
539.4	30							10 2	0		0	
						Stiff gray mottled with brown silty clay, little fine						-
		20	SH 1	5	100	sand, trace medium to coarse sand, slightly						H=1.5
		20	² /2		100	organic, damp.						11 1.5
												_
36.2			1			X A A A A A A A A A A						_
Ľ		21	¹ / ₃ / ₃	8	100	Loose fine to coarse sand, trace fine gravel, little to some silt, slightly organic, moist.						H=1.5
34.4	35-		/ 3			to some sin, singinity organic, moist.						-
34.4					-	Loose brown fine to coarse sand, trace fine						-
È			1			gravel, trace to little silt.						1
\vdash		22	4 _{/4}	10	53							-
F			4									
F]
-		23	² / ₂ / ₂	5	67							G
Ľ	40-	20	² /2									
-	40											-
F			2,									
		24	² / ₂ / ₃	6	100							
-			′ 3									-
-		25	2	5 100						_		
24.9		23	² / ₂ / ₂	5	100							
	45-		7 -									
-												
						- Encountered water at 14.5'. to 16.0'.						-
-						- Borehole converted to monitoring well upon						
F						completion - See separate well completion digram.						_
						- Boring location and elevation surveyed by AEP.						-
-	-					- Datum: Ohio State Plane South						-
È	50-					- NAD 27/NAVD 29 (Plant Grid).]
\vdash												-
F												1
F												4
⊢												-
E												-
\vdash												-
E	55-]
⊢												-
F												1
F												-
⊢												-
E												1
F												-
	60^{\perp}					SYMBOLS USED TO INDICATE TEST F	RESULTS	<u> </u>	rill Rod	Energy	Ratio •	0.75
VATEF WATE		LL	<u> </u>		_ =	Q - Uncon Comp See H - Penetro		(tsf) 1				8/2/2013
		TE: _	12/1			T - Triax Comp Separate W Onit Br C - Consol. Curves D - Relativ				ll Rig Nu		

LOG OF BORING NO. MW-BAP-3 Page 1 of 3 BOTTOM ASH POND MONITORING WELL INSTALLATION CARDINAL PLANT, BRILLIANT, OH LOCATION: N. 819,111, E. 2,513,519 11/11/15 - 11/12/15 ELEVATION: **669.9** DATE: 4-1/4" I.D. Hollow-stem Auger 55.0' DRILLING METHOD: COMPLETION DEPTH: 2" O.D. Split-barrel Sampler SAMPLER(S): NATURAL CONSISTENCY INDEX PTH, ET BER BER PLE PLE PLE ORT ORT EV. TEST DESCRIPTION

ELE	EE	AH H	H H G	09 Z	l₽ÿ	DESCRIPTION		NATOR	AL MOID	TURE CO	1410141	1151
Ξ	DEP	SAMP	SAMP SAMP FFFOI		SAMP REC-		$ \angle_{n_1}^{\wedge}$	ASTIC			LIMIT	RESUL
	- 0 -	~ ~		-		AGGREGATE - 12 INCHES		10	20		0	
668.9						AUDICEDATE - 12 INCITES						-
			20,			FILL: Medium-dense to dense gray and brown						-
		1	12	28	87	fine to coarse gravel, some to "and" fine to coarse						H=3.5
			1	0		sand, little to some silt or silty clay (variers),						
		_	10,	Ŭ.		contains pockets of fine to coarse sand, dry.						
		2	/13/	39	80	contains pockets of fine to coarse sand, dry.						H=4.0
		_		8								
			10,									
	- 5 -	3	['] 14 _'	43	67							_
	<u> </u>	_	_ ′2	0								_
		4	3	44	100							_
		4	$\frac{22}{22}$	44	100			1 1 1				-
		_	_ 1	3								-
		5	9/11	25	67							-
51.4		5	11/	9	0/							-
,,,,		-	3	9		FILL: Hard gray and brown silty clay, some fine						-
		6	¹ /10,	29	100	to coarse and, little fine to coarse gravel, damp.						H=4.5+
59.9	10	2	/1	2		to coarse and, nuce fine to coarse graver, damp.						1
	- 10-	-	¹¹ / _{27/3}	5		FILL: Very-dense fine to coarse black and gray						1
		7	/27.	71	67	sand, some fine to coarse gravel, damp.]
58.4				0								
		_	υ,			FILL: Very-stiff brown silty clay, some to "and"						
		8	[′] 6 _/	19	100	fine to coarse sand, some fine to coarse gravel,						H=3.5
		_	_ /	9		damp.						_
			6			1.						
		9	14	35	87							H=3.5-4.
55.4		-	4	4				1 1 1				_
	-15-	10	⁴ / ₅ /	14	80	FILL: Loose to medium-dense brown fine to						-
		10	5 _/	6	80	coarse gravel, some to "and" fine to coarse sand,						-
		-	6	0		some silty clay, damp to moist.						-
		11	[′] 6,	14	80							H=4.5
				5		- Contains zones of hard silty clay at 16.0'.						
			2,	-								
		12	[/] 4 _/	13	93							_
		_	/	6								_
		12	1		07							_
49.4	-20-	13	′4 _/	8	67							-
77.4		-	2	2		Medium-stiff to stiff brown clayey silt, "and" fine						-
		14	² /3 _/	9	53	to coarse sand, some fine to coarse gravel, wet.						H=1.0-2.0
			3/	_ ا		to coarse sand, some mile to coarse graver, wet.						1 1.0 2.1
47.3		15A	2.	4 6	100			1 : : :		1::::		H=0.5
	1		² / ₂ /			Loose gray fine to medium sand, trace coarse	-					1
		15B	-/	3		sand, trace fine gravel, little silt, wet.						
			1,	-		sand, date mie graver, mile sin, wet.						
		16	⁷ 3,	5	100							
	-25-		/	1								
4.4	25											4
			1			Very-loose gray silt, little fine to medium sand,						4
		17	1/.	0	100	wet.						-
		1/	1	ľ	100		$\left \begin{array}{c} \\ \end{array} \right $					-
1.9			S.	H								-
		$\overline{\Delta}$				Soft to stiff dark brown mottled with dark grow						1
			1			Soft to stiff dark-brown mottled with dark-gray						1
		18	¹ /2,	8	100	slithly organic to organic clayey silt, little to some			· · · · · · ·			H=1.0-1.
	20		<i>~</i> /			fine to medium sand, contains silt seams, fine						1
/ / T I	∟ 30- ER LE	VEL -	⊻ ,	0 7		SYMBOLS USED TO INDICATE TEST R	ESULTS	-	Drill Rod	Energy	Ratio :	0.75
	ER LE ER N	VLL.	- 4	8.2 le Well		G=Gradation See H - Penetro		(tsf)				8/2/2013
w A I		ATE:		<u>le wen</u> 11/15		T - Triax Comp Separate W - Unit Dr				ll Rig Nu		
	D	ATE.	1			-CONTINUED-		1.27				ATV 550

Page 2 of 3 LOG OF BORING NO. MW-BAP-3 BOTTOM ASH POND MONITORING WELL INSTALLATION CARDINAL PLANT, BRILLIANT, OH

						C	ARDINAL PLANT, BRILLIANT, OH						
LOC	ATIO	N: N	. 8	819,11	1, E.	2,51	3,519 ELEVATION: _66	9.9	DAT	Ъ: 1	1/11/1	5 - 11	/12/15
DRIL	LING	METH	ю				D. Hollow-stem Auger		COMPI	LETION	DEPTH	: 5	5.0'
SAM	PLER				2" C		plit-barrel Sampler						
ELEV.	02 DEPTH, 96 FEET	SAMPLE NUMBER	SAMPLE	SAMPLE EFFORT	N 60	SAMPLE REC-%	DESCRIPTION	×			TURE CO		TEST RESULTS
	- 30-						sand seams and roots, wet.		10110 .	20	30	40	-
		19		¹ / _{2/2}	5	100	Soft to stiff dark-brown mottled with dark-gray slithly organic to organic clayey silt, little to some fine to medium sand, contains silt seams, fine sand seams and roots, wet.						-
634.4	- 35-	20		sң ²∕ 1	4	100							-
		21		SӉ 2/1	4	100	Soft to medium-stiff dark-brown mottled with gray slightly organic to organic clayey silt, some to "and" fine to medium sand, wet.						
629.4	-40-	22		SӉ ¹ ∕2	4	100							-
047,4		23		sң 2 _{/1}	4	100	Soft to medium-stiff gray mottled with brown silty clay, trace to some fine to coarse sand, slightly organic, contains fine sand seams, wet.						
624.9	-45-	24		SӉ ⁴ ∕7	14	100	Medium-dense to very-dense brown fine to coarse						-
		25		6 / _{11/} 17	35	80	gravel, some to "and" fine to coarse sand, trace to little silt, wet.						
		26		22	75	53	- Contains zones of fine to coarse sand at 49.0'.						G
	- 50-			25 ²⁷ 35/25									-
(14.0		27		²¹ / ₈ /8	20	33							-
<u>614.9</u>	- 55-						- Encountered seepage at 16.0'. - Encountered water at 20.5'.						
							 Borehole converted to monitoring well upon completion - See separate well completion diagram. Datum: Ohio State Plane South. NAD 	ESIIL TQ					
WAT	ER LE	· LL.	Ā	28 Incida	.2		G - Gradation See H - Penetro	meter ((tsf)			Ratio :	
WAI	ER N D	OTE: ATE:		Inside 12/1			T - Triax Comp Separate W - Unit Dr C - Consol. Curves D - Relativ		/			n Date : umber :	
OB: '	7217-1	15-007	R				-CONTINUED-						ATV 550-

Pa	ge 3 o	of 3	BOT	ГОМ	I ASI	LOG OF BORING NO. MW-B H POND MONITORING WEL ARDINAL PLANT, BRILLIAN	L INSTALLA	ATION				58	ME
		N: N.					ELEVATION:	669.9		TE:	11/11/1		
	LLING MPLER	METHO				D. Hollow-stem Auger			COM	PLETIO	N DEPTH	:	55.0'
				20		pht-barrer Sampler			NATURAL	CONSI	STENCY I	NDEX	
ELEV.	DEPTH, FEET	SAMPLE NUMBER SAMPLE	SAMPLE EFFORT	N 60	SAMPLE REC-%	DESCRIPTIO	N			RAL MO	ISTURE CO		TEST RESULTS
	+60-	S/ S/	S. E		$^{S/}_{R}$	27/NAVD 29 (Plant Grid).			PLASTIC	LIMIT		<u>d limit</u> 40	
						,							_
													-
								· · · · · · · · · · · · · · · · · · ·					-
	-65-												-
													-
													_
													_
	-												-
	- 70-												-
													-
													-
													_
													_
	-75-												_
													_
													-
													-
													_
	- 80-									· · · · ·			_
	80												_
													_
													-
													-
													_
	- 85-												-
													-
													-
													-
													-
	90-												
WAT	TER LE	VEL:	⁷ 28			G - Gradation		netromete	r (tsf)		od Energy		
WA	TER N	OTE: ATE:	Inside 12/1			T - Triax Comp Poe	parate W-Uni	it Dry Wt lative De	(pcf)		Calibratio Frill Rig N		<u>8/2/2013</u> S&ME

LOG OF BORING NO. MW-BAP-4 Page 1 of 2 **BOTTOM ASH POND MONITORING WELL INSTALLATION** CARDINAL PLANT, BRILLIANT, OH LOCATION: N. 820,880, E. 2,513,617 11/20/15 - 11/23/15 ELEVATION: 661.1 DATE: 40.0' DRILLING METHOD: 4-1/4" I.D. Hollow-stem Auger COMPLETION DEPTH: SAMPLER(S): 2" O.D. Split-barrel Sampler SAMPLE NUMBER SAMPLE NATURAL CONSISTENCY INDEX SAMPLE REC-% SAMPLE EFFORT DEPTH TEST NATURAL MOISTURE CONTENT B \mathbf{N}_{60} DESCRIPTION EL RESULTS OUID LIMI T.TMT 0 **AGGREGATE - 12 INCHES** 10 20 30 40 660.1 FILL: Medium-dense to dense gray and brown 39 87 fine to coarse gravel, some to "and" fine to coarse H=4.25-4.5 1 15 16 sand, little to some silt, dry. 10 18 53 2 9 20 67 3 9 5 655.8 N60 655.3 FILL: Very-soft brown and gray silty clay, "and" 35 2010 NEW DEFAULT BORING LOG-W/ fine to coarse sand, little fine to coarse gravel. 31 4 87 • × G 13 FILL: Dense brown fine to coarse sand, little fine 20 5 653.6 50-3"R to coarse gravel, "and" clayey silt, cobbles, moist. Stiff to very-stiff dark-brown mottled with dark-gray silty clay, little fine to coarse sand, trace fine gravel, slightly organic, damp. 9 3 87 ×Ò H=2.0-3.0 6 \times - 10-Р H=1.25-2.5 15 644.9 Very-stiff brown mottled with gray silty clay, 7 5 14 87 H=2.0-3.5 little fine to medium sand, trace coarse sand, few 6 cobbles, contains silt seams near top of stratum, damp. 7 18 20-100 H=2.25-3.25 28 10 9 14 100 H=3.0 5 10 14 100 H=3.25 5 25 9 100 634.4 11A H=2.53 Medium-stiff to stiff brown clayey silt, "and" fine 11B H=0.5-1.5 to medium sand, trace coarse sand, includes sand seams, moist. 100 12 4 30 SYMBOLS USED TO INDICATE TEST RESULT ∇ Ţ Drill Rod Energy Ratio : 0.75 WATER LEVEL: 18.7 - Gradation - Uncon Comp See H - Penetrometer (tsf) Last Calibration Date : WATER NOTE: Inside Well 8/2/2013 Separate W-Unit Dry Wt (pcf) T - Triax Comp C - Consol. DATE: 12/15/15 Curves D-Relative Dens (%) Drill Rig Number : S&ME ATV 550-2

LOG OF BORING NO. MW-BAP-4 Page 2 of 2 BOTTOM ASH POND MONITORING WELL INSTALLATION CARDINAL PLANT, BRILLIANT, OH 11/20/15 - 11/23/15 LOCATION: N. 820,880, E. 2,513,617 ELEVATION: 661.1 DATE: 4-1/4" I.D. Hollow-stem Auger DRILLING METHOD: COMPLETION DEPTH: 40.0' 2" O.D. Split-barrel Sampler SAMPLER(S): SAMPLE NUMBER SAMPLE SAMPLE REC-% NATURAL CONSISTENCY INDEX SAMPLE EFFORT DEPTH, FEET TEST ELEV. NATURAL MOISTURE CONTENT N_{60} DESCRIPTION RESULTS LIMIT -LIQUID LIMIT PLASTIC - 30-630.6 Medium-stiff to stiff brown clayey silt, "and" fine 10 20 30 40 to medium sand, trace coarse sand, includes sand SH seams, moist. 1 13 0 100 SH, Very-loose brown and grav fine to medium sand

WATER N		Inside 12/15	Well		Q - Uncon Comp Separate W - Unit D T - Triax Comp Curves D - Relativ	ry Wt (p	pcf)					8/2/2013 S&ME
ATER LE		<u>⊻</u> 18.		_ <u>▼</u>	G-Gradation See U Bonotre	RESULTS	(+ e f)			Energy		
60-	1				OVMDATA HARA DA THATATA PARA			· ·	· · · ·			1
												-
												-
	1											-
									· · · ·			-
	1											1
												-
- 55-												-
	1								· · · ·			1
								: :	· · ·			-
												-
	1							: :	: : :			1
									· · ·			-
									· · ·			-
- 50-]]
50	1							· ·				1
								: :	· · · ·			1
	-							: :	<u>: : :</u>			-
								<u>.</u>				4
	1											1
									<u> </u>			1
	$\left \right $				27/NAVD 29 (Plant Grid).				· · · ·			-
43					- Datum: Ohio State Plane South, NAD							-
-45-]				- Boring location and elevation surveyed by AEP.				· · · ·]
	1				diagram.							1
					completion - See separate well completion				· · · ·			-
					- Borehole converted to monitoring well upon				<u> </u>			-
]				- Encountered cobbles at 18.5'.			: :]
	1				- Encountered water at 5.5'.			: :				1
												1
									<u> </u>			-
40-		/ 1		ļ					: :			-
	16	SH SH	0	100								G
	1	SH										1
								<u>: :</u> : :	<u>: : :</u> : : :			-
	-	1						: :	: : :			-
	15	1,	3	67				: :				_
		SH 1										1
												-
- 35-	-	· 1							· · ·			-
	14	SH SH	0	67								-
		SH			······································			: :				1
					with a trace of coarse sand, wet.				· · · ·			1
	-	· 1			little to "and" silt (percent varies), contains zones			: :	<u> </u>			G
		511/			Very-loose brown and gray fine to medium sand,						1	K ÷


Pag	je 1 o	f 3	B	ютт	ГОМ	I ASF	LOG OF BORING NO. MW-BAP-5 I POND MONITORING WELL INSTALLATIC ARDINAL PLANT, BRILLIANT, OH	DN			P.		58	ME
DRIL	LING	J: <u>N</u> Meth			4-1/4	4" I.C	. Hollow-stem Auger	9.2	DAT COMP			1/24/15 DEPTH:		/25/15 2.5'
SAM	PLER				2" O		plit-barrel Sampler							
ELEV.	DEPTH, FEET	SAMPLE NUMBER	SAMPLE	EFFORT	N_{60}	SAMPLE REC-%	DESCRIPTION	×	ATURAL NATUR	TEST RESULT				
668.2	- 0 -						AGGREGATE - 12 INCHES		10	20	3	0 4	0	-
		1		^{'8} / ₁₁	24	60	FILL: Medium-dense brown fine to coarse sand, some fine to coarse gravel, some to "and" silty clay, dry.							-
		2 _	16 / 4	5 _{/5}	13	60								-
663.7	- 5 -	3		4 _{/6}	13	73			• ×		>			G
		4	5	⁹ / ₃₂	51	87	FILL: Hard gray and brown silty clay, "and" fine to coarse sand, little to some fine to coarse gravel, damp.							H=4.5
660.7		5	10	15 _/ 16	39	80	FILL: Medium-dense brown and gray fine to							H=4.5
659.2	- 10-	6	_	13 _{/11}	30	87	coarse sand, little fine to coarse gravel, some silty clay, damp.		• ×		>			•
				Р			FILL: Hard brown silty clay, some fine to coarse sand, some fine to coarse gravel (shale fragments), damp.							H=4.5
655.7		7	3	[′] 5 _{/10}	19	80								H=4.5
	- 15-	8	10	11 _{/25}	45	80	FILL: Medium-dense to dense brown fine to coarse gravel, some fine to coarse sand, some silty clay becoming trace silt at bottom of stratum,							H=3.0
		9	11	7	16		damp.							-
652.3		10A 10B	4	6 6 10	20	100	Medium-stiff to stiff gray mottled with dark-gray and brown silty clay, trace fine to coarse sand,							-
		-		P			trace fine gravel, few roots, few silt seams, slightly organic, moist.							-
	- 20-													-
		11	Sŀ	1 1/3	5	100					×		× · · · · ×	H =0.5-1.25
646.2		12	2	[′] 2,	8	100	Medium-stiff to very-stiff brown mottled with gray silty clay, trace to little fine to coarse sand,							H=3.5
	-25-	12		² /4	0	100	damp.							
		⊻		Р							•			
				Р										-
	30-													
WATI	ER LE	VEL.	Ţ	27.	1	T	G = Gradation See U = Bonotro		I			Energy		
WAT	ER N		Ι	nside 12/15	Well		Q - Uncon Comp T - Triax Comp D - Separate D - Delativ	y Wt (pcf)	Las				8/2/2013 S&ME
		ATE: 5-0071		14/13	13		-CONTINUED-	C DellS	(~~)		וויזע	l Rig Nu	mper :	S&ME ATV 550-


Pag	e 2 of 3	}	BOTT	ГОМ	I ASE	LOG OF BORING NO. MW-BAP-5 I POND MONITORING WELL INSTALLATIO ARDINAL PLANT, BRILLIANT, OH	ON						58	ME
	ATION: .LING M					3,277 ELEVATION: 66	59.2	C	DAT COMPL				5 - 11	/25/15
SAM	PLER(S)	:		2" O).D. S	plit-barrel Sampler								
ELEV.	DEPTH, FEET SAMPLE	NUMBER SAMPLE	SAMPLE EFFORT	N 60	SAMPLE REC-%	DESCRIPTION	JRAL C IATURA	TEST						
ш		NUSA	SA EF	~	SA R			PLAS	STIC I	IMIT	<u>LIQUID LIMIT</u>			RESULT
			2 /	12	100	Medium-stiff to very-stiff brown mottled with gray silty clay, trace to little fine to coarse sand, damp.		10		20	30		40	
		.3	^{′4} ′6	13	100									H=2.0-3.5
	1	4	³ / ₄ /	11	100									H=2.5-3.0
	-35-													-
				100									H=2.5	
		.6	² / ₃	10	100									H=2.5
	-40-		³ /5	10										-
		7	SH_2/3	6	100									H=1.25
			SӉ									-		
623.7	- 45-	8	′sн SH	0	100									H=1.25
		.9	SH SH	0	100	Stiff gray mottled with brown and dark-gray silty clay, trace fine to coarse sand, slightly organic, damp.								H=0.75
621.2			́1 SӉ			Medium-stiff to stiff gray and dark-gray organic								-
6 18. 7	2 - 50-	20	SH SH SH	0	100	clayey silt, trace fine to coarse sand, damp.								H=0.75-1.2
	2	21	⁶ / _{9/9} /9	23	87	Medium-dense to dense fine to coarse gravel, some to "and" fine to coarse sand, trace to little silt, wet.								G
			_											-
613.8	2 - 55-	22	⁸ / ₂₁ / ₃₄	69	87									-
		23	¹⁴ / _{20/}	43	80	Medium-dense to dense gray and brown fine to coarse sand, "and" fine to coarse gravel, little silt, wet.								-
			14											-
λ/ Λ Τ Τ	$\begin{bmatrix} 2 \\ 60 \end{bmatrix}$ = 60 = 60 = 100 =	24 11. ⊻	¹ / ₁₂	35	60 	SYMBOLS USED TO INDICATE TEST F	RESUL	TS	D	rill R	od Er	nerøv	Ratio :	G 0.75
	ER LEVE ER NOT	·Ľ·	27. Inside	Well		Q - Uncon Comp See H - Penetro			sf)					8/2/2013
	DAT	Ъ:	12/15	5/15		T - Triax Comp Separate W - Onit Br C - Consol. Curves D - Relativ				D	rill F	Rig Nu	umber :	S&ME ATV 550-


LOG OF BORING NO. MW-BAP-5 Page 3 of 3 BOTTOM ASH POND MONITORING WELL INSTALLATION

Page	e 3 of 3	BOT	ГОМ	I ASF	LOG OF BORING NO. MW-BAP-5 H POND MONITORING WELL INSTALLATIC ARDINAL PLANT, BRILLIANT, OH	DN	\$ 58	ME
LOCA	ATION: N	. 820,0 5	2, E.	2,51	3,277 ELEVATION: _66	9.2 DATE:	11/24/15 - 11/	25/15
DRILI	LING MET	HOD:	4-1/4	4" I.E). Hollow-stem Auger	COMPLETIO	N DEPTH: 6	2.5'
SAMF	PLER(S):		2" ().D. S	plit-barrel Sampler			
ELEV.	00 FEET SAMPLE NUMBER	SAMPLE SAMPLE EFFORT	N 60	SAMPLE REC-%	DESCRIPTION	NATURAL CONSI	STENCY INDEX ISTURE CONTENT	TEST
Е	DA ND	SA SA EF		SA RI			<u> LIQUID LIMIT</u>	RESULT
	00				Medium-dense to dense gray and brown fine to	10 20	30 40	
606.7	25	⁸ /4/5	11	60	coarse sand, "and" fine to coarse gravel, little silt, wet.			
	- 65-				 Encountered water at 17.0'. Borehole converted to monitoring well upon completion. See separate well completion diagram. Boring location and elevation surveyed by AEP. Datum: Ohio State Plane South NAD 27/NAVD 29 (Plant Grid). 			
-	- 80-							
-	- 85-							
-								
ŀ								
	-90 ^{_]}	⊥ ⊻ 27	· 1		SYMBOLS USED TO INDICATE TEST F	RESULTS Drill R	od Energy Ratio :	0.75
WATE	R LEVEL: ER NOTE:	$\frac{\underline{\vee}}{1}$ 27 Inside			Q - Uncon Comp See H - Penetro		Calibration Date :	
WAT					T - Triax Comp Separate W - Unit Dr	WE (DOT) LASU		

								S&ME
Elevation (Feet above	Depth Below Ground							¥
(I eet above MSL)	Surface (Feet)							
672.65	-2.86	Top of Cover						
672.29	-2.50	Top of PVC					4 - Inch Di	ameter Protective Steel Casing
0/2.29	-2.50							
							2 - Inch Di	ameter Flush-Thread PVC Casing
						\downarrow		
669.79	0.0	Ground Surface	•			X	Ground Surface	
667.2	2.6	Top of Grout					Concrete	
007.2	2.0	TOP OF GIOUL					Concrete	
							Boring Diameter	
						Ja-	8 " 0.0) to 52.0
								to
								to
						×		
							Grout: Portland	1 8 Quick Col
							Glout. Fortiant	
						8		
638.9	30.9	Top of Bentonit	е			3		
					\mathbb{K}	X	Bentonite Seal:	3 - 5 gallon buckets (15 gal.)
						Ø .		bentonite pellets
632.2	37.6	Top of Filter Pa	ck		KA K			
032.2	57.0		UK					
							10 - Slot Sc	reen
628.2	41.6	Top of Screen	Joonin	ae				
020.2	41.0		openin	ys				
					 	M /	Filter Pack: 4 - 5	0 lb bags (200 lb.) #5 quartz sand
						4		
					\ge			
					<u> </u>			
618.4	51.4	Bottom of Scre	en Ope	nings				
					\sim			
617.8	52.0	Bottom of Well						
						8		
047.0	FO O	Detters of D	~		(NOT TO SCA	LE)		
617.8	52.0	Bottom of Borin	y					
Depth to	Static Water:	28.7 2	7.5					
	ater Elevation:	638.6 63	39.8					
	Date:	12/11/15 12/	15/15					
			-		•			
Well Develo		c . ,			· · · ·			WELL COMPLETION DIAGRAM
		of water (appropumping. NTU						Broiget Name
		Bailed additional						Project Name: AEP CD Bottom Ash Pond Monitoring Wells
intially high	but decreased	to NTU = 25.4.	-		-		-	Project Location:
		t on 12/15 was i crete pad. Prot					crete nad	Cardinal Plant / Brilliant, Ohio
		orete pau. FIUL	COUVE		arus piaceu		ncie pau.	Project Number:
			-				_	7217-15-007A
	ity Readings (I					a		Boring Number:
Cumu	llative Gallons		С	ms/cm	PH	ORPmV		MW-BAP-1
	175		3.09	1.31	7.15	-6		Date Well Installed:
Location:	N. 820,305.3'	E. 2,513,927.4		Datu	m: NAD27/	NGVD29 OH	5	12/10/2015







Elevation (Feet above MSL) Depth Below Ground Surface (Feet) 672.28 -3.10 Top of Cover	&ME
(Feet above Ground MSL) Surface (Feet)	
MSL) Surface (Feet)	
672 28 -3 10 Top of Cover	
672.00 -2.82 Top of PVC 4 - Inch Diameter Protective Steel Casing	I
	ing
669.18 0.0 Ground Surface Ground Surface	
662.6 6.6 Top of Grout Concrete	
Boring Diameter (in inches)	
<u>8</u> " <u>0.0</u> to <u>62.1</u> to	
Grout: Portland & Quick Gel	
625.0 44.2 Top of Bentonite	
Bentonite Seal: <u>3 - 5 gallon buckets (15 ga</u>	al.)
bentonite pellets	
619.5 49.7 Top of Filter Pack	
617.5 51.7 Top of Screen Openings	
Filter Pack: 7 - 50 lb. bags (350 lb.) #5 quartz	sand
607.7 61.5 Bottom of Screen Openings	
607.1 62.1 Bottom of Well	
(NOT TO SCALE)	
606.7 62.5 Bottom of Boring	
Depth to Static Water: 27.3 27.6 27.2 27.1	
Static Water Elevation: 639.1 638.8 639.2 639.2	
Date: 11/29/15 12/7/15 12/11/15 12/15/15	
Well Development: WELL COMPLETIO 12/10 - Bailed 61.5 gallons of water (approx. 13 well volumes) out of well via submersible WELL COMPLETIO	N DIAGRAM
pump, water level stayed steady. Project Name:	
-Measurement on 12/15 was immediately before slug testing.	Monitoring Wells
- Top cover set in 3'x3' concrete pad. Protective steel bollards placed around concrete pad. Project Location:	
Water Quality Readings (Horiba U-52) Cardinal Plant / Brilliant, Oh	io
Cumulative Gallons NTU C ms/cm PH ORPmV Project Number: 61.5 24.3 15.08 1.46 6.86 -56 7217-15-007A	
01.5 24.3 15.06 1.40 0.60 -50 /217-15-00/A Boring Number:	
Location: N. 820,052.1' E. 2,513,277.5' MW-BAP-5	
Datum: NAD27/NGVD29 OH S Date Well Installed:	
11/25/2015	

40 CFR 257.101 (f)(1)(iv)(B)(2)(iii)

Maps that characterize the direction of groundwater flow accounting for seasonal variations



• Groundwater Monitoring Well

→ Approximate Groundwater Flow Direction


----- Groundwater Elevation Contour

Notes

Notes
Monitoring well coordinates and water level data (collected from June 21 to June 22, 2016) provided by AEP.
Site features based on information available in Groundwater Monitoring Network Evaluation - Cardinal Site - Bottom Ash Pond (Geosyntec, 2016) provided by AEP.
Groundwater elevation units are feet above mean sea level.

Bot	urface Map - Uppermos tom Ash Complex June 2016 ardinal Generating Plant Brilliant, Ohio	st Aquifer
Geos	yntec ^{>} nsultants	Figure 1
Columbus, Ohio	2017/08/16	I

Ν



- Groundwater Monitoring Well
- → Approximate Groundwater Flow Direction
- ----- Groundwater Elevation Contour

Notes

Monitoring well coordinates and water level data (collected from October 3 to October 4, 2016) provided by AEP.
Site features based on information available in Groundwater Monitoring Network Evaluation - Cardinal Site - Bottom Ash Pond (Geosyntec, 2016) provided by AEP.
Groundwater elevation units are feet above mean sea level.

		Z
		4
Potentiometric Su	rface Map - Uppermos	st Aquifer
AEP Ca	rface Map - Uppermos om Ash Complex October 2016 Irdinal Generating Plant Brilliant, Ohio	·
Geosy con Columbus, Ohio	/ntec isultants 2017/08/16	Figure 3



• Groundwater Monitoring Well


- → Approximate Groundwater Flow Direction
- ----- Groundwater Elevation Contour

Notes

- Monitoring well coordinates and water level data (collected on November 14, 2016) provided by AEP.

Site features based on information available in Groundwater Monitoring Network
Evaluation - Cardinal Site - Bottom Ash Pond (Geosyntec, 2016) provided by AEP.
Groundwater elevation units are feet above mean sea level.

		N
		18
		Sale -
		-
		Real
	Side 1	
	2.52	The state of
		1. T
Potentiometric S Bo	Surface Map - Uppermos ttom Ash Complex November 2016	st Aquifer
AEP	Cardinal Generating Plant Brilliant, Ohio	
Geos	syntec⊳	Figure
Columbus, Ohio	2017/08/16	4
	2011/00/10	




- Groundwater Monitoring Well
- → Approximate Groundwater Flow Direction
- ----- Groundwater Elevation Contour

Notes

Notes
Monitoring well coordinates and water level data (collected on January 9, 2016) provided by AEP.
Site features based on information available in Groundwater Monitoring Network Evaluation - Cardinal Site - Bottom Ash Pond (Geosyntec, 2016) provided by AEP.
Groundwater elevation units are feet above mean sea level.

		Z
		1
		Cold Marcol
	rface Map - Uppermos om Ash Complex January 2017 rdinal Generating Plant Brilliant, Ohio	st Aquifer
Columbus, Ohio	/ntec isultants 2017/08/16	Figure 6



- Groundwater Monitoring Well
- → Approximate Groundwater Flow Direction
- ----- Groundwater Elevation Contour


Notes

Monitoring well coordinates and water level data (collected on February 8, 2017) provided by AEP.
Site features based on information available in Groundwater Monitoring Network Evaluation - Cardinal Site - Bottom Ash Pond (Geosyntec, 2016) provided by AEP.
Groundwater elevation units are feet above mean sea level.

125 250 0

	Geosy	/ntec [▷] isultants	Figure 7
		rdinal Generating Plant Brilliant, Ohio	
et	Potentiometric Su Bott F	rface Map - Uppermo om Ash Complex ebruary 2017	st Aquifer
			1.0.
			3
			17
			×.
			÷.
			L

Ν



- Groundwater Monitoring Well
- → Approximate Groundwater Flow Direction
- ----- Groundwater Elevation Contour

Notes

Monitoring well coordinates and water level data (collected on April 10, 2017) provided by AEP.
Site features based on information available in Groundwater Monitoring Network Evaluation - Cardinal Site - Bottom Ash Pond (Geosyntec, 2016) provided by AEP.
Groundwater elevation units are feet above mean sea level.

125 0 250

			\$
			4
			Carl Street
et	Bott	rface Map - Uppermo com Ash Complex April 2017 ardinal Generating Plant Brilliant, Ohio	st Aquifer
		/ntec ^D nsultants	Figure 8
	Columbus, Ohio	2017/08/23	0

N ٨



- Groundwater Monitoring Well
- → Approximate Groundwater Flow Direction
- ----- Groundwater Elevation Contour

Notes - Monitoring well coordinates and water level data (collected on May 23, 2017) provided by AEP. - Site features based on information available in Groundwater Monitoring Network Evaluation - Cardinal Site - Bottom Ash Pond (Geosyntec, 2016) provided by AEP. - Groundwater elevation units are feet above mean sea level.

125 0

	Columbus, Ohio	ntec ^D sultants 2017/08/23	Figure 9
		rdinal Generating Plant Brilliant, Ohio	
et	Potentiometric Su Bott	rface Map - Uppermo om Ash Complex May 2017	ost Aquifer
		A.	all the state
			1 6
			4
			Å

N



- Groundwater Monitoring Well
- ----- Groundwater Elevation Contour
- → Approximate Groundwater Flow Direction

Notes - Monitoring well coordinates and water level data (collected on July 25, 2017) provided by AEP. - Site features based on information available in Groundwater Monitoring Network Evaluation - Cardinal Site - Bottom Ash Pond (Geosyntec, 2016) provided by AEP. - Groundwater elevation units are feet above mean sea level.

125 250 0

et	AEP Ca	rdinal Generating Plant Brilliant, Ohio /ntec sultants	Figure 11
et	AEP Ca	rdinal Generating Plant Brilliant, Ohio	
et			
	Potentiometric Su Bott	rface Map - Uppermo om Ash Complex July 2017	st Aquifer
			10-5
			te t
			State of the
			ALC: NO
			Stand 1
			1
			22
			8
			Δ
			Y

N

40 CFR 257.101 (f)(1)(iv)(B)(3)

Constituent concentrations, summarized in table form, at each groundwater monitoring well monitored during each sampling event

		MW-BAP-1									
Parameter	Unit	1/12/2017	10/20/2016	5/3/2017	5/31/2017	6/20/2017	6/28/2016	8/1/2017	8/10/2016	9/26/2017	
			Background								
Antimony	μg/L	0.06	0.08	0.07	0.04J	0.04J	0.07	0.03J	0.08	-	
Arsenic	μg/L	1.13	1.6	1.56	0.78	0.53	1.45	0.4	1.05	-	
Barium	μg/L	86.5	107	85.3	72.6	63.6	93.6	61.5	107	-	
Beryllium	μg/L	0.043	0.06	0.061	0.03	0.01J	0.072	0.01J	0.037	-	
Boron	mg/L	1.95	1.73	2.27	2.11	2.4	1.71	2.69	1.83	2.7	
Cadmium	μg/L	0.13	0.11	0.15	0.12	0.1	0.12	0.09	0.11	-	
Calcium	mg/L	157	166	159	148	153	167	170	162	175	
Chloride	mg/L	96.1	94.5	95.2	94.3	95.4	98.4	100	93.4	93.7	
Chromium	μg/L	1.45	2	2.1	0.811	0.355	1.8	0.185	1.3	-	
Cobalt	μg/L	1.1	1.29	1.3	0.951	0.74	1.49	0.665	1.2	-	
Combined Radium	pCi/L	1.093	1.238	0.301	1.174	0.602	0.343	0.452	0.21	-	
Fluoride	mg/L	0.34	0.35	0.33	0.3	0.3	0.38	0.41	0.33	0.33	
Lead	μg/L	1.24	1.69	1.72	0.786	0.314	2.09	0.073	1.03	-	
Lithium	mg/L	0.021	0.015	0.02	0.017	0.029	0.035	0.022	0.019	-	
Mercury	μg/L	0.005U	0.007	0.006	0.004J	0.005U	0.01	0.003J	0.005U	-	
Molybdenum	μg/L	26.4	28.6	26.8	27.4	29	19.6	29.2	27.5	-	
Selenium	μg/L	0.2	0.4	0.3	0.1	0.06J	0.2	0.04J	0.2	-	
Total Dissolved Solids	mg/L	918	942	948	952	957	953	926	916	977	
Sulfate	mg/L	405	407	411	419	458	402	471	397	469	
Thallium	μg/L	0.071	0.226	0.058	0.059	0.05J	0.05	0.05J	0.122	-	
pН	SU	7.06	7.08	6.98	7.62	7.28	7.06	6.94	7.17	6.76	

Notes:

mg/L: milligrams per liter

µg/L: micrograms per liter

pCi/L: picocuries per liter

SU: standard unit

U: Component was not present in concentrations above method detection limit

and is reported as the reporting limit

J: Estimated value. Component was detected in concentrations below the reporting limit

		MW-BAP-2									
Parameter	Unit	1/12/2017	10/20/2016	5/3/2017	5/31/2017	6/20/2017	6/28/2016	8/1/2017	8/10/2016	9/5/2017	9/26/2017
						Background					Detection
Antimony	μg/L	0.03J	0.1	0.05J	0.03J	0.03J	0.07	0.03J	0.04J	0.03J	-
Arsenic	μg/L	26	29.6	10.6	13.1	11.1	11.3	17.1	11.1	9.08	-
Barium	μg/L	104	123	104	106	91.5	94.3	93.8	89.5	78.4	-
Beryllium	μg/L	0.035	0.083	0.032	0.02J	0.01J	0.02J	0.02J	0.02J	0.01J	-
Boron	mg/L	2.08	1.79	2.2	2.09	2.16	2.28	1.95	2.04	1.75	1.73
Cadmium	μg/L	0.05	0.09	0.04	0.04	0.02J	0.04	0.02	0.03	0.03	-
Calcium	mg/L	86.4	92.3	82.4	87.6	84.6	98.7	86	89.5	81.6	86.8
Chloride	mg/L	72.9	79.6	72	70.7	71.9	74.1	71.4	75.9	69.1	68.2
Chromium	μg/L	0.65	1.8	0.704	0.292	0.213	0.5	0.371	0.3	0.217	-
Cobalt	μg/L	1.59	2.17	1.61	1.37	1.21	1.52	1.2	1.36	1.06	-
Combined Radium	pCi/L	0.776	0.849	0.376	1.206	0.993	0.749	1.086	0.588	0.731	-
Fluoride	mg/L	0.62	0.79	0.42	0.33	0.34	0.35	0.46	0.33	0.35	0.33
Lead	μg/L	0.965	2.16	0.77	0.325	0.234	0.439	0.33	0.307	0.197	-
Lithium	mg/L	0.016	0.006	0.013	0.009	0.02	0.011	0.01	0.01	0.013	-
Mercury	μg/L	0.002J	0.004J	0.005U	0.005U	0.005U	0.005U	0.005U	0.005U	0.005U	-
Molybdenum	μg/L	26.2	31.9	42.1	46.6	49	37.6	46.1	38.4	42.7	-
Selenium	μg/L	0.1	0.4	0.2	0.09J	0.07J	0.09J	0.08J	0.08J	0.09J	-
Total Dissolved Solids	mg/L	583	628	557	562	563	612	560	544	538	552
Sulfate	mg/L	176	190	213	222	234	239	218	228	226	230
Thallium	μg/L	0.03J	0.075	0.03J	0.02J	0.02J	0.03J	0.02J	0.03J	0.03J	-
pН	SU	6.73	6.76	6.85	7.15	7.1	6.75	6.74	6.31	-	6.94

Notes:

mg/L: milligrams per liter

µg/L: micrograms per liter

pCi/L: picocuries per liter

SU: standard unit

U: Component was not present in concentrations above method detection limit

and is reported as the reporting limit

J: Estimated value. Component was detected in concentrations below the reporting limit

		MW-BAP-3									
Parameter	Unit	1/12/2017	10/20/2016	5/3/2017	5/31/2017	6/20/2017	6/28/2016	8/1/2017	8/11/2016	9/5/2017	9/26/2017
						Background					Detection
Antimony	μg/L	0.03J	0.02J	0.02J	0.02J	0.02J	0.03J	0.02J	0.04J	0.04J	-
Arsenic	μg/L	0.99	0.69	0.39	0.36	0.32	0.42	0.31	0.75	0.74	-
Barium	μg/L	52.2	55.8	47.7	51.7	46.7	49.1	47.4	65.3	66.4	-
Beryllium	μg/L	0.009J	0.009J	0.006J	0.005J	0.02U	0.008J	0.005J	0.022	0.036	-
Boron	mg/L	1.77	1.8	1.87	1.91	2.05	1.92	2.12	2.03	1.99	2.03
Cadmium	μg/L	0.07	0.05	0.06	0.1	0.09	0.04	0.08	0.05	0.17	-
Calcium	mg/L	62.6	65.7	60.6	60.3	62.1	64.1	67	63	65.6	69.1
Chloride	mg/L	60.7	60.1	61.9	61.8	62.8	59.8	63.4	58.8	63.5	63.8
Chromium	μg/L	0.427	0.4	0.257	0.128	0.111	0.5	0.126	0.8	1.05	-
Cobalt	μg/L	0.779	0.759	0.721	0.675	0.591	0.759	0.579	0.962	0.92	-
Combined Radium	pCi/L	0.546	1.738	0.853	0.506	0.373	0.358	0.00513	0.76	0.767	-
Fluoride	mg/L	0.16	0.1J	0.16	0.1J	0.1J	0.17	0.1J	0.1J	0.1J	0.1
Lead	μg/L	0.216	0.184	0.091	0.088	0.065	0.164	0.066	0.487	0.814	-
Lithium	mg/L	0.012	0.001U	0.003	0.001U	0.013	0.018	0.005	0.005	0.007	-
Mercury	μg/L	0.003J	0.002J	0.005U	0.005U	0.007	0.002J	0.005U	0.003J	0.004J	-
Molybdenum	μg/L	2.7	2.45	3.57	2.51	2.21	2.13	1.87	5.63	1.8	-
Selenium	μg/L	0.03J	0.07J	0.06J	0.1U	0.1U	0.05J	0.1U	0.09J	0.1	-
Total Dissolved Solids	mg/L	390	396	402	410	421	418	424	400	417	421
Sulfate	mg/L	119	129	131	135	145	130	148	134	142	146
Thallium	μg/L	0.05J	0.059	0.04J	0.05J	0.05J	0.05J	0.05J	0.061	0.052	-
pН	SU	6.67	6.7	6.74	7.22	6.95	6.65	6.52	6.7	-	6.53

Notes:

mg/L: milligrams per liter

µg/L: micrograms per liter

pCi/L: picocuries per liter

SU: standard unit

U: Component was not present in concentrations above method detection limit

and is reported as the reporting limit

J: Estimated value. Component was detected in concentrations below the reporting limit

		MW-BAP-4									
Parameter	Unit	1/12/2017	10/20/2016	5/2/2017	5/31/2017	6/20/2017	6/30/2016	8/1/2017	8/10/2016	9/26/2017	
			Background								
Antimony	μg/L	0.09	0.1	0.05J	0.04J	0.03J	0.06	0.05	0.07	-	
Arsenic	μg/L	44.8	42.4	41.9	35.9	42.7	36.3	43.7	42.2	-	
Barium	μg/L	59.9	69.8	44.9	51.7	41.9	54.9	49.9	54.7	-	
Beryllium	μg/L	0.176	0.227	0.071	0.111	0.046	0.119	0.092	0.117	-	
Boron	mg/L	0.02	0.064	0.16	0.024	0.038	0.115	0.034	0.062	0.033	
Cadmium	μg/L	0.14	0.18	0.05	0.1	0.03	0.11	0.06	0.1	-	
Calcium	mg/L	197	214	197	181	190	233	202	220	203	
Chloride	mg/L	27.5	28.6	27.5	27.6	27.5	30	27.6	30.6	27.1	
Chromium	μg/L	4.16	4.4	1.48	1.96	0.834	1.7	1.89	2.4	-	
Cobalt	μg/L	20.3	19.8	19.2	20.2	18	18.7	19.9	18.2	-	
Combined Radium	pCi/L	0.703	1.17	0.377	0.599	0.645	0.535	1.069	0.722	-	
Fluoride	mg/L	0.1J	0.1J	0.1J	0.1J	0.1J	0.15	0.1J	0.16	0.1	
Lead	μg/L	4.63	5.67	1.66	2.94	0.955	3.2	2.06	2.78	-	
Lithium	mg/L	0.012	0.006	0.009	0.005	0.02	0.015	0.013	0.012	-	
Mercury	μg/L	0.005	0.007	0.005U	0.004J	0.005U	0.005U	0.005U	0.004J	-	
Molybdenum	μg/L	1.76	1.87	1.56	1	2.15	1.35	1.52	4.51	-	
Selenium	μg/L	0.7	0.9	0.3	0.4	0.2	0.5	0.4	0.5	-	
Total Dissolved Solids	mg/L	1200	1300	1250	1270	1280	1400	1330	1320	1250	
Sulfate	mg/L	620	617	584	590	655	661	631	629	618	
Thallium	μg/L	0.102	0.106	0.03J	0.03J	0.02J	0.03J	0.04J	0.063	-	
pН	SU	6.37	6.72	6.45	6.63	6.81	6.37	6.27	6.28	6.36	

Notes:

mg/L: milligrams per liter

µg/L: micrograms per liter

pCi/L: picocuries per liter

SU: standard unit

U: Component was not present in concentrations above method detection limit

and is reported as the reporting limit

J: Estimated value. Component was detected in concentrations below the reporting limit

		MW-BAP-5									
Parameter	Unit	1/12/2017	10/20/2016	5/2/2017	5/31/2017	6/20/2017	6/28/2016	8/1/2017	8/10/2016	9/26/2017	
			Background								
Antimony	μg/L	0.06	0.12	0.07	0.05	0.03J	0.07	0.03J	0.09	-	
Arsenic	μg/L	8.78	16.1	11.5	11.7	9.1	11.3	10.6	12.1	-	
Barium	μg/L	87.9	118	88.2	95.3	77.7	92.7	83.1	102	-	
Beryllium	μg/L	0.061	0.157	0.095	0.075	0.045	0.068	0.039	0.112	-	
Boron	mg/L	0.043	0.058	0.116	0.073	0.05	0.072	0.043	0.043	0.059	
Cadmium	μg/L	0.02	0.06	0.04	0.03	0.02J	0.03	0.01J	0.05	-	
Calcium	mg/L	207	226	201	176	200	228	206	209	209	
Chloride	mg/L	15.3	14.3	14.8	13.3	15.7	13.4	14.7	13.5	15.3	
Chromium	μg/L	2.35	5.7	2.83	2.1	1.33	2	1.16	3.4	-	
Cobalt	μg/L	1.34	3.06	1.92	1.47	0.966	1.28	0.855	2.03	-	
Combined Radium	pCi/L	1.411	1.497	0.364	0.894	0.788	0.6516	0.686	1.026	-	
Fluoride	mg/L	0.09J	0.08	0.1J	0.06J	0.08J	0.1J	0.08J	0.09J	0.09	
Lead	μg/L	1.72	4.6	2.77	1.95	1.18	1.92	1.04	3.08	-	
Lithium	mg/L	0.008	0.007	0.01	0.012	0.016	0.02	0.012	0.01	-	
Mercury	μg/L	0.005U	0.003J	0.005U	0.005U	0.005U	0.005U	0.005U	0.003J	-	
Molybdenum	μg/L	0.74	1.15	0.62	0.94	0.52	0.8	0.52	1.22	-	
Selenium	μg/L	0.2	0.7	0.4	0.3	0.2	0.2	0.1	0.4	-	
Total Dissolved Solids	mg/L	1050	1010	1010	955	1080	1050	1050	1060	1050	
Sulfate	mg/L	474	433	418	404	472	449	448	456	442	
Thallium	μg/L	0.058	0.114	0.059	0.04J	0.03J	0.03J	0.02J	0.059	-	
pН	SU	6.6	6.59	6.6	7.07	6.94	6.6	6.55	6.7	6.72	

Notes:

mg/L: milligrams per liter

µg/L: micrograms per liter

pCi/L: picocuries per liter

SU: standard unit

U: Component was not present in concentrations above method detection limit

and is reported as the reporting limit

J: Estimated value. Component was detected in concentrations below the reporting limit

		BAP-1				BAP-2			BAP-3		BA	P-4	BA	P-5
Parameter	Unit	1/23/2018	5/17/2018	8/29/2018	1/23/2018	5/17/2018	8/29/2018	1/23/2018	5/17/2018	8/29/2018	5/21/2018	8/29/2018	5/21/2018	8/29/2018
		Detection	Asses	sment	Detection	Asses	sment	Detection	Asses	sment	Asses	sment	Asses	sment
Antimony	µg/L	-	0.0400 J	0.5 U	-	0.0300 J	0.5 U	-	0.0200 J	0.5 U	0.0300 J	0.5 U	0.0400 J	0.5 U
Arsenic	µg/L	-	0.430	0.5 U	-	12.4	122	-	0.270	0.5 U	34.1	44.2	7.78	6.20
Barium	µg/L	-	56.0	57.6	-	92.3	135	-	48.1	46.8	38.8	49.7	72.1	78.7
Beryllium	µg/L	-	0.0100 J	0.1 U	-	0.0200 J	0.1 U	-	0.00800 J	0.1 U	0.0360	0.100	0.0500	0.1 U
Boron	mg/L	2.91	2.70	3.44	1.97	1.57	1.92	1.91	1.97	2.45	0.137	0.0217	0.112	0.0956
Cadmium	µg/L	-	0.100	0.140	-	0.0200	0.1 U	-	0.110	0.1 U	0.0200	0.1 U	0.0200 J	0.1 U
Calcium	mg/L	-	159	153	-	82.0	79.5	-	66.8	69.4	202	216	203	222
Chloride	mg/L	86.2	76.9	74.4	61.1	60.0	70.0	64.1	67.2	67.2	27.7	28.5	17.0	19.2
Chromium	µg/L	-	0.598	1 U	-	0.345	1 U	-	0.270	1 U	0.715	2.10	1.45	1 U
Cobalt	µg/L	-	0.649	0.790	-	1.16	1.30	-	0.521	0.5 U	19.1	20.1	0.950	0.770
Combined Radium	pCi/L	-	0.227	0.686	-	0.643	0.225	-	0.385	0.312	0.987	1.06	0.865	1.01
Fluoride	mg/L	0.370	0.380	0.360	0.390	0.490	0.620	-	0.130	0.110	0.160	0.140	0.0900	0.0930
Lead	µg/L	-	0.246	0.5 U	-	0.217	0.5 U	-	0.0720	0.5 U	0.601	1.70	1.19	0.540
Lithium	mg/L	-	0.0100	0.0166	-	0.00400	10 U	-	0.001 U	10 U	0.00600	10 U	0.00300	10 U
Mercury	µg/L	-	0.00300 J	0.00126	-	0.005 U	0.000930	-	0.005 U	0.5 U	0.005 U	0.00266	0.005 U	0.00123
Molybdenum	µg/L	-	27.4	30.6	-	37.4	36.3	-	1.73	1.50	1.31	1.50	0.460	0.510
pН	SU	7.09	7.04	6.96	6.90	6.81	6.86	6.71	6.48	6.59	6.26	6.32	6.48	6.56
Selenium	µg/L	-	0.100	0.5 U	-	0.100 J	0.5 U	-	0.0400 J	0.5 U	0.200	0.5 U	0.200	0.5 U
Total Dissolved Solids	mg/L	-	924	927	-	518	519	-	416	415	1260	1240	1030	974
Sulfate	mg/L	-	446	494	-	228	217	-	157	159	590	628	433	464
Thallium	µg/L	-	0.0610	0.5 U	-	0.0300 J	0.5 U	-	0.0680	0.5 U	0.0500 J	0.5 U	0.0300 J	0.5 U

Notes:

mg/L: milligrams per liter

 μ g/L: micrograms per liter

SU: standard unit

pCi/L: picocuries per liter

U: Parameter was not present in concentrations above method detection limit and is reported as the reporting limit

J: Estimated value. Parameter was detected in concentrations below the reporting limit

Table 1 - Groundwater Data SummaryCardinal Plant - Bottom Ash Pond

Parameter	Unit	BA	P-1	BAP-2		BAP-3		BAP-4		BAP-5	
Parameter	Umt	4/8/2019	10/9/2019	4/8/2019	10/9/2019	4/8/2019	10/10/2019	4/8/2019	10/10/2019	4/8/2019	10/10/2019
Antimony	μg/L	0.500 U	0.500 U	0.500 U	0.500 U	0.500 U	0.500 U	0.500 U	0.500 U	0.500 U	0.500 U
Arsenic	μg/L	0.500 U	0.500 U	122	34.9	0.500 U	0.500 U	39.0	54.8	5.20	5.80
Barium	μg/L	52.3	50.0	225	121	44.4	44.3	42.4	47.1	77.4	83.4
Beryllium	μg/L	0.100 U	0.100 U	0.260	0.100 U	0.100 U	0.100 U	0.100 U	0.100 U	0.100 U	0.100 U
Boron	μg/L	2,680	3,050	1,960	1,560	2,020	2,100	19.8	19.5	92.0	118
Cadmium	μg/L	0.130	0.120	0.230	0.100 U	0.100 U	0.100	0.100 U	0.100 U	0.100 U	0.100 U
Calcium	μg/L	167,000	158,000	91,100	82,800	76,000	71,900	209,000	184,000	224,000	213,000
Chloride	mg/L	64.7	68.9	59.4	64.5	64.6	68.4	20.9	25.3	14.9	16.7
Chromium	μg/L	1.00 U	1.00 U	5.50	1.00 U	1.00 U	1.00 U	1.20	1.70	1.00 U	2.20
Cobalt	μg/L	1.00	0.700	4.60	1.20	0.570	0.500 U	17.8	19.1	1.00	1.10
Combined Radium	pCi/L	1.10	6.52	0.617	1.06	0.552	0.371	0.564	1.48	0.765	1.27
Fluoride	mg/L	0.380	0.370	0.800	0.560	0.140	0.110	0.150	0.140	0.0990	0.0680
Lead	μg/L	0.500 U	0.500 U	5.30	0.500 U	0.500 U	0.500 U	1.20	1.40	1.10	1.20
Lithium	μg/L	17.1	19.8	10.0 U	10.0 U	10.0 U	10.0 U	10.0 U	10.0 U	10.0 U	10.0 U
Mercury	μg/L	0.000500 U	0.000500 U	0.00965	0.000670	0.000500 U	0.000500 U	0.00186	0.00117	0.00123	0.000785
Molybdenum	μg/L	30.4	32.3	36.3	40.0	1.30	1.60	1.30	1.40	0.500 U	0.500 U
Selenium	μg/L	0.500 U	0.500 U	0.570	0.500 U	0.500 U	0.500 U	0.500 U	0.500 U	0.500 U	0.500 U
Sulfate	mg/L	419	416	167	202	149	164	471	560	404	433
Thallium	μg/L	0.500 U	0.500 U	0.500 U	0.500 U	0.500 U	0.500 U	0.500 U	0.500 U	0.500 U	0.500 U
Total Dissolved Solids	mg/L	905	874	563	484	415	425	1,260	1,210	1,050	983
pН	SU	6.82	7.10	7.12	6.95	6.53	6.05	6.35	6.26	6.65	6.43

Notes:

mg/L: milligrams per liter

µg/L: micrograms per liter

SU: standard unit

pCi/L: picocuries per liter

U: Parameter was not present in concentrations above method detection limit and is reported as the reporting limit

J: Estimated value. Parameter was detected in concentrations below the reporting limit

All samples were collected as part of the assessment monitoring program in accordance with 40 CFR 257.90(e)(3).

Spring 2020 App III & IV Parameters Cardinal Plant - Bottom Ash Pond

Parameter	Unit	BAP-1	BAP-2	BAP-3	BAP-4	BAP-5
		4/08/2020	4/08/2020	4/08/2020	4/08/2020	4/08/2020
Antimony	μg/L	0.50 U				
Arsenic	μg/L	2.4	24.2	1.1	45.1	2.3
Barium	μg/L	89.1	160	83.6	42.8	80.1
Beryllium	μg/L	0.15	0.10 U	0.10 U	0.10 U	0.10 U
Boron	μg/L	2770	1860	1940	20.7	138
Cadmium	μg/L	0.15	0.10 U	0.15	0.10 U	0.10 U
Calcium	μg/L	147000	88000	69700	186000	234000
Chloride	mg/L	73.9	83.7	77.3	29	22.1
Chromium	μg/L	4.6	1.5	3.5	1.4	1.0 U
Cobalt	μg/L	2.3	1.8	1.9	19.6	0.99
Combined Radium	pCi/L	1.63	0.736	0.641	0.552	0.794
Fluoride	mg/L	0.38	0.58	0.12	0.11	0.08
Lead	μg/L	3.3	1.1	1.5	1.1	0.50 U
Lithium	μg/L	27.5	12.1	10.0 U	12.9	11.4
Mercury	μg/L	0.0137	0.00249	0.0084	0.00223	0.000734
Molybdenum	μg/L	29.9	35.2	2.7	1.4	0.50 U
pН	SU	6.82	6.67	6.36	6.31	6.47
Selenium	μg/L	0.50 U				
Total Dissolved Solids	mg/L	825	527	430	1170	1080
Sulfate	mg/L	389	208	158	637	511
Thallium	μg/L	0.50 U				
Notes:	-	-	-	-	-	-

mg/L: milligrams per liter

µg/L: micrograms per liter pCi/L: picocuries per liter SU: standard unit

U: Component was not present in concentrations above method detection limit and is reported as the reporting limit

J: Estimated value. Component was detected in concentrations below the reporting limit

2019 ANNUAL GROUNDWATER MONITORING REPORT

FEDERAL CCR RULE

CARDINAL PLANT – BOTTOM ASH POND BRILLIANT, OHIO

Submitted to



Cardinal Operating Company

306 County Road 7E Brilliant, Ohio 43913

Submitted by



consultants

engineers | scientists | innovators

941 Chatham Lane, Suite 103 Columbus, Ohio 43221

January 10, 2020

CHA8468

TABLE OF CONTENTS

1.	INTRODUCTION	1
2.	SITE DESCRIPTION	1
	2.1 Site Description2.2 Regional Physiographic Setting	
3.	GROUNDWATER MONITORING SYSTEM	2
4.	CCR RULE GROUNDWATER KEY ACTIVITIES COMPLETED	2
	 4.1 2018 Statistical Evaluation Activities	3 3 3
5.	PROBLEMS ENCOUNTERED AND RESOLUTIONS	3
6.	STATUS OF MONITORING PROGRAM	4
7.	PLANNED KEY ACTIVITIES FOR 2020	4
8.	REFERENCES	4

LIST OF TABLES

Table 1:	2019 Groundwater Data Summary
----------	-------------------------------

 Table 2:
 Residence Time Calculation Summary

LIST OF FIGURES

i

- Figure 1: Site Location Map
- Figure 2: Groundwater Monitoring Well Network
- Figure 3: Potentiometric Surface Map Uppermost Aquifer April 2019
- Figure 4: Potentiometric Surface Map Uppermost Aquifer October 2019

LIST OF ACRONYMS AND ABBREVIATIONS

BAP	Bottom Ash Pond
CCR	Coal Combustion Residuals
CFR	Code of Federal Regulations
ESP	Electrostatic Precipitator
FGD	Flue Gas Desulfurization
GWPS	Groundwater Protection Standards
MCL	Maximum Contaminant Level
MW	Megawatt
RSW	Residual Solid Waste
SCR	Selective Catalytic Reduction
SSI	Statistically Significant Increase
SSL	Statistically Significant Level
USEPA	United States Environmental Protection Agency

1. INTRODUCTION

The Federal Coal Combustion Residuals (CCR) Rule (40 Code of Federal Regulations [CFR] Part 257.90(e)) (USEPA, 2015) requires owners and or operators of existing CCR landfills and surface impoundments to prepare a Groundwater Monitoring and Corrective Action Report (Report) no later than January 31 annually. Geosyntec Consultants (Geosyntec) has prepared this Report for the Bottom Ash Pond (BAP), an existing CCR unit at the Cardinal Plant in Brilliant, Ohio (Site). This Report summarizes the groundwater monitoring activities conducted pursuant to the CCR Rule through December 31, 2019.

2. SITE DESCRIPTION

2.1 Site Description

The Site is located one-mile south of Brilliant, Ohio in Jefferson County (**Figure 1**) and is operated by Buckeye Power, Inc. (Buckeye Power). Located along the Ohio River, the generating station consists of three coal-powered units with an 1,800 megawatt (MW) capacity and annual coal use of 5.2 million tons (Geosyntec, 2016). Units 1 and 2 began operation in 1967 and Unit 3 began operation in 1977. As of 2012, all three units were equipped with an electrostatic precipitator (ESP), a selective catalytic reduction (SCR) system, and a flue gas desulfurization (FGD) system.

The BAP is situated along the Ohio River south of Cardinal Plant Unit 3. The BAP perimeter dikes enclosing the facility are approximately 6,500 feet (ft) in length with a 20-foot average height. The dikes were originally constructed in the 1960s, with major reconstruction in 1974 as part of the Unit 3 addition. The BAP receives bottom ash, pyrite, and other wastes from the coal burning process in addition to stormwater drainage and wastewater flows from the property. Site features and locations are outlined in **Figure 2**.

2.2 Regional Physiographic Setting

The Site is underlain by horizontal sequences of lower Permian and upper Pennsylvanian sedimentary rock. The Conemaugh Group, 500 ft thick in Jefferson County, consists of shale, sandstone, limestone, claystone, and coal. This group includes the Morgantown Sandstone underlain by the Elk Lick Limestone, the Skelly Limestone and Shale, the Ames Limestone, and the Cow Run Sandstone (Geosyntec, 2016). Above the current grade of the Residual Solid Waste (RSW) Landfill lies the Monongahela Group consisting of shale, sandstone, limestone, coal, claystone, and siltstone. Overlying the Monongahela Group, at approximately 1,250 feet in elevation, is the Permian-age Dunkard Group.

The uppermost aquifer at the Site consists of fine to coarse sand and gravel below a silty clay, interbedded organic clay and silt. The uppermost aquifer is hydraulically connected to the Ohio River. Groundwater in the uppermost aquifer generally flows southeast towards the Ohio River

with hydraulic conductivity ranging from 1×10^{-1} to 1×10^{-4} centimeters per second (cm/s) (Geosyntec, 2016).

3. GROUNDWATER MONITORING SYSTEM

The BAP's groundwater monitoring network was designed to comply with 40 CFR 257.91. The groundwater monitoring network utilizes monitoring wells initially installed as part of a separate site-wide hydrogeologic investigation and is used to monitor groundwater quality in the uppermost aquifer at the Site. Monitoring well construction and soil boring logs were provided in the *Groundwater Monitoring Network Design Report* (Geosyntec, 2016).

The BAP groundwater monitoring well network consists of five monitoring wells, as shown in **Figure 2**. Two upgradient monitoring wells (MW-BAP-4 and MW-BAP-5) are used to measure background conditions and three downgradient monitoring wells (MW-BAP-1, MW-BAP-2, and MW-BAP-3) are used as compliance wells.

4. CCR RULE GROUNDWATER KEY ACTIVITIES COMPLETED

4.1 2018 Statistical Evaluation Activities

A Groundwater Protection Standard (GWPS) was established for each Appendix IV parameter in accordance with the United States Environmental Protection Agency (USEPA's) *Statistical Analysis of Groundwater Monitoring Data at RCRA Facilities – Unified Guidance* (Unified Guidance; USEPA, 2009) and the Site's Statistical Analysis Plan (Geosyntec, 2017). The established GWPSs were determined to be the greater value of the background concentration and the maximum contaminant level (MCL) or risk-based screening level for each Appendix IV parameter. GWPSs determined in 2018 are provided in the *2018 Annual Groundwater Monitoring Report* (Geosyntec, 2019a).

A statistical evaluation of the 2018 assessment monitoring data compared against the GWPSs was completed in January 2019 and is described in the *Statistical Analysis Summary* – *Bottom Ash Pond* (Geosyntec, 2019b). The statistical analysis report included an evaluation of significant levels (SSLs) for Appendix IV parameters and an evaluation of statistically significant increases (SSIs) for Appendix III parameters. Additionally, prediction limits for interwell tests were recalculated using data collected during the 2018 assessment monitoring events. No SSLs were identified at the BAP. SSIs for boron and chloride were identified at MW-BAP-1, MW-BAP-2, and MW-BAP-3 and SSIs for fluoride were identified at MW-BAP-1 and MW-BAP-2 (Geosyntec, 2019b). Based on these results, the CCR unit remained in assessment monitoring.

4.2 2019 Sampling and Data Evaluation Activities

4.2.1 Assessment Monitoring Program

The BAP remained in assessment monitoring throughout 2019. Assessment monitoring sampling events were conducted in April and October 2019 in accordance with 40 CFR 257.95(b) and 40 CFR 257.95(d)(1), respectively. Samples from both events were analyzed for all Appendix III and Appendix IV parameters; results are shown in **Table 1**. A revision of the GWPS and statistical evaluation of the 2019 assessment monitoring data is ongoing and will be completed outside of the timeframe of this report.

4.2.2 Groundwater Elevation and Flow Velocities

Prior to sampling, a synoptic round of groundwater level measurements was collected from compliance and background monitoring wells. Potentiometric surface maps based on groundwater elevations measured during the April and October 2019 assessment monitoring events are presented in **Figure 3** and **Figure 4**, respectively. The potentiometric maps show that groundwater near the BAP flows southeast towards the Ohio River. The groundwater residence time (inverse of velocity) at the BAP ranged from 1.4 days at well MW-BAP-3 to 6.5 days at MW-BAP-2 and MW-BAP-3. A summary of hydraulic gradients and groundwater residence times at the BAP is provided in **Table 2**.

4.2.3 Data Usability

Upon receipt of laboratory analytical reports, the data were evaluated for usability. Analytical data were checked for the following:

- Samples were analyzed within the method specified hold times;
- Samples were received within holding temperature;
- The chain of custody form was complete;
- Precision was within control limits using relative percent differences of blind duplicate samples;
- Matrix spike and matrix spike duplicate recoveries and laboratory control samples were within the control limits; and
- Potential for positive bias was evaluated using method blanks.

All data received during 2019 were considered complete and usable.

5. PROBLEMS ENCOUNTERED AND RESOLUTIONS

No problems were encountered during 2019 that were related to assessment monitoring activities at the BAP. No monitoring wells were gauged dry, abandoned, or added to the well network during 2019. All analytical data received were deemed to be of acceptable quality.

6. STATUS OF MONITORING PROGRAM

During the time period of this report, the Site has remained in assessment monitoring. Assessment monitoring events were conducted in April and October 2019. The BAP's status will be re-evaluated after completion of the ongoing statistical evaluation.

7. PLANNED KEY ACTIVITIES FOR 2020


The following activities are planned for 2020 at the BAP:

- The 2019 Annual Groundwater Monitoring Report will be entered into the facility's operating record and posted to the public internet site;
- A statistical evaluation of the 2019 assessment monitoring event will be completed in January 2020, which will evaluate potential SSIs against revised GWPSs. The BAP's monitoring well status will be confirmed following the evaluation;
- Assuming the unit remains in assessment monitoring, two semi-annual groundwater assessment monitoring program events will be conducted and tested for potential SSLs and SSIs; and
- The 2020 Annual Groundwater Monitoring will be prepared for submittal in January 2021.

8. REFERENCES

- Geosyntec Consultants, Inc. 2016. Groundwater Monitoring Network Evaluation, Cardinal Site Bottom Ash Pond, July.
- Geosyntec Consultants, Inc. 2017. Statistical Analysis Plan. January.
- Geosyntec Consultants, Inc. 2019a. 2018 Annual Groundwater Monitoring Report, Federal CCR Rule, Cardinal Plant – Bottom Ash Pond. January.
- Geosyntec Consultants, Inc. 2019b. Statistical Analysis Summary Bottom Ash Pond, Cardinal Plant. 2019.
- United States Environmental Protection Agency (USEPA). 2009. Statistical Analysis of Groundwater Monitoring Data at RCRA Facilities Unified Guidance. EPA 530/R-09-007. March.
- United States Environmental Protection Agency (USEPA). 2015. Hazardous and Solid Waste Management System; Disposal of Coal Combustion Residuals from Electric Utilities (Final Rule). Fed. Reg. 80 FR 21301, pp. 21301-21501, 40 CFR Parts 257 and 261, April.

FIGURES





Monitoring Well Network

- Compliance Sampling Location
 Background Sampling Location


Bottom Ash Pond


Notes - Monitoring well coordinates provided by **Buckeye Power**. - Site features based on information available in Groundwater Monitoring Network Evaluation - Cardinal Site - Bottom Ash Pond (Geosyntec, 2016) provided by **Buckeye Power.**





	Site Layout Bottom Ash Complex							
Buckeye Pow	nt							
Geosy		Figure						
con	2							
Columbus, Ohio	2							





TABLES

Table 1 - Groundwater Data SummaryCardinal Plant - Bottom Ash Pond

Parameter	Unit	BA	P-1	BAP-2		BAP-3		BAP-4		BAP-5	
Parameter	Umt	4/8/2019	10/9/2019	4/8/2019	10/9/2019	4/8/2019	10/10/2019	4/8/2019	10/10/2019	4/8/2019	10/10/2019
Antimony	μg/L	0.500 U	0.500 U	0.500 U	0.500 U	0.500 U	0.500 U	0.500 U	0.500 U	0.500 U	0.500 U
Arsenic	μg/L	0.500 U	0.500 U	122	34.9	0.500 U	0.500 U	39.0	54.8	5.20	5.80
Barium	μg/L	52.3	50.0	225	121	44.4	44.3	42.4	47.1	77.4	83.4
Beryllium	μg/L	0.100 U	0.100 U	0.260	0.100 U	0.100 U	0.100 U	0.100 U	0.100 U	0.100 U	0.100 U
Boron	μg/L	2,680	3,050	1,960	1,560	2,020	2,100	19.8	19.5	92.0	118
Cadmium	μg/L	0.130	0.120	0.230	0.100 U	0.100 U	0.100	0.100 U	0.100 U	0.100 U	0.100 U
Calcium	μg/L	167,000	158,000	91,100	82,800	76,000	71,900	209,000	184,000	224,000	213,000
Chloride	mg/L	64.7	68.9	59.4	64.5	64.6	68.4	20.9	25.3	14.9	16.7
Chromium	μg/L	1.00 U	1.00 U	5.50	1.00 U	1.00 U	1.00 U	1.20	1.70	1.00 U	2.20
Cobalt	μg/L	1.00	0.700	4.60	1.20	0.570	0.500 U	17.8	19.1	1.00	1.10
Combined Radium	pCi/L	1.10	6.52	0.617	1.06	0.552	0.371	0.564	1.48	0.765	1.27
Fluoride	mg/L	0.380	0.370	0.800	0.560	0.140	0.110	0.150	0.140	0.0990	0.0680
Lead	μg/L	0.500 U	0.500 U	5.30	0.500 U	0.500 U	0.500 U	1.20	1.40	1.10	1.20
Lithium	μg/L	17.1	19.8	10.0 U	10.0 U	10.0 U	10.0 U	10.0 U	10.0 U	10.0 U	10.0 U
Mercury	μg/L	0.000500 U	0.000500 U	0.00965	0.000670	0.000500 U	0.000500 U	0.00186	0.00117	0.00123	0.000785
Molybdenum	μg/L	30.4	32.3	36.3	40.0	1.30	1.60	1.30	1.40	0.500 U	0.500 U
Selenium	μg/L	0.500 U	0.500 U	0.570	0.500 U	0.500 U	0.500 U	0.500 U	0.500 U	0.500 U	0.500 U
Sulfate	mg/L	419	416	167	202	149	164	471	560	404	433
Thallium	μg/L	0.500 U	0.500 U	0.500 U	0.500 U	0.500 U	0.500 U	0.500 U	0.500 U	0.500 U	0.500 U
Total Dissolved Solids	mg/L	905	874	563	484	415	425	1,260	1,210	1,050	983
pН	SU	6.82	7.10	7.12	6.95	6.53	6.05	6.35	6.26	6.65	6.43

Notes:

mg/L: milligrams per liter

µg/L: micrograms per liter

SU: standard unit

pCi/L: picocuries per liter

U: Parameter was not present in concentrations above method detection limit and is reported as the reporting limit

J: Estimated value. Parameter was detected in concentrations below the reporting limit

All samples were collected as part of the assessment monitoring program in accordance with 40 CFR 257.90(e)(3).

Table 2: Residence Time Calculation SummaryCardinal Plant - Bottom Ash Pond

		201	9-03	2019-10		
CCR Management Unit	Monitoring Well	Well Diameter (inches)	Groundwater Velocity (ft/year)	Groundwater Residence Time (days)	Groundwater Velocity (ft/year)	Groundwater Residence Time (days)
	MW-BAP-1 ^[2]	2.0	30.6	2.0	32.4	1.9
	MW-BAP-2 ^[2]	2.0	9.4	6.5	12.4	4.9
Bottom Ash Pond	MW-BAP-3 ^[2]	2.0	20.8	2.9	9.3	6.5
1 Ollu	MW-BAP-4 ^[1]	2.0	16.6	3.7	42.8	1.4
	MW-BAP-5 ^[1]	2.0	10.1	6.0	20.1	3.0

Notes:

[1] - Upgradient Well

[2] - Compliance Well

40 CFR 257.101 (f)(1)(iv)(B)(4)

A decryption of site hydrogeology including stratigraphic cross-sections



2.4.2 Regional and Local Geologic Setting

The BAP is located in an area of Ohio which was unglaciated during the last ice age. The surficial geology at the BAP consists of alluvial silt, clay, and sand deposited by the Ohio River floodwaters, underlain by glacial outwash deposits of sand and gravel. The glacial outwash deposits extend to the bedrock surface, which occurs at approximately 60 feet below the natural ground surface at the pond. Bedrock consists of interbedded shale, sandstone, coal, and limestone of the Pennsylvanian-aged Conemaugh Formation (BBC&M, 2009; CHA, 2009).

2.4.3 Surface Water and Surface Water-Groundwater Interactions

The BAP is located immediately west of the Ohio River. According to United States Army Corps of Engineers records, the Ohio River elevation at this location is controlled by the Pike Island Dam, with a regular pool elevation of 644.0 ft above msl (USACE, 2003). Notes on an AEP plan drawing provide 50-year and 100-year flood elevations for the Ohio River of 664.0 ft and 666.0 ft above msl, respectively.

Surface water near the BAP enters a tributary to the Ohio River. According to USACE maps, the nearest tributary entering the Ohio River is Salt Run, located approximately 0.5 miles to the north (USACE, 2003). Riddles Run and Blockhouse Run are located approximately 1.25 and 1.5 miles to the north, respectively. Groundwater also flows towards and recharges the Ohio River. Seasonal fluctuations in the Ohio River pool stage near the BAP are expected to reflect seasonal precipitation values for Brilliant, Ohio with the highest pool elevations in the spring and summer months. The BAP is separated from the lower aquifer by a confining silt and clay layer of at least 5 feet in thickness. However, limited seepage may occur from the BAP to the near-surface zone of saturation, which drains towards the Ohio River.

2.4.4 Water Users

Based on water well records obtained from the Ohio Department of Natural Resources (ODNR, 2016) online search tools, the nearest domestic water supply wells are located approximately one mile west of the BAP. The well records indicate well depths ranging from 30 to 110 feet below



ground surface within shale and sandstone aquifers. According to the Jefferson County Water and Sewer District, there are no surface water intakes supplying water to the town of Brilliant, Ohio. Brilliant's water source comes from two groundwater wells located at a water treatment plant approximately three miles northeast of the BAP.



3. MONITORING NETWORK EVALUATION

3.1 <u>Hydrostratigraphic Units</u>

3.1.1 Horizontal and Vertical Position relative to CCR Unit

The principal regional aquifer is comprised of the alluvial sediments along the Ohio River, located below and east of the BAP. The identified uppermost aquifer in the vicinity of the BAP is the Sand and Gravel aquifer, which is hydraulically connected to the Ohio River. The BAP is lies above and is separated from the uppermost aquifer by a lower conductivity layer of silty clay and silt which thickens toward the west away from the Ohio River. The five (5) groundwater monitoring wells that make up the groundwater monitoring network around the BAP are screened to target the Sand and Gravel beneath the lower conductivity separation layer. Cross-sections illustrating the horizontal and vertical position of BAP relative to the uppermost aquifer are provided in Appendix B.

3.1.2 Overall Flow Conditions

Regionally, the most productive aquifer is the surficial aquifer, comprised of sand and gravel alluvial deposits along the Ohio River. Water supply wells within this aquifer can sustain yields of up to several hundred gallons per minute (gpm). This surficial aquifer is likely recharged through direct precipitation, infiltration from the Ohio River, and to a smaller extent, discharge from the surrounding bedrock (Geosyntec, 2006). Seasonal variation in the groundwater table beneath the BAP is expected to reflect the seasonal variation in precipitation with the highest groundwater elevations in the spring and summer months as well as the season fluctuation in the pool stage of the Ohio River.

Based on ODNR water well logs, the surficial aquifer of alluvial sediments along the Ohio River near the BAP can generally sustain yields of up to several hundred gpm.

3.2 <u>Uppermost Aquifer</u>

3.2.1 CCR Rule Definition

According to the 2015 CCR rule, the term "uppermost aquifer" has the same provisions as in §257.40: "The geologic formation nearest the natural ground surface that is an aquifer, as well as lower aquifers that are hydraulically interconnected with this aquifer within the facility's property boundary. This definition includes a shallow, deep, perched, confined, or unconfined aquifer, provided that it yields usable water" (40 CFR 257.60).

For purposes of this report, it is assumed that the uppermost useable aquifer has the following characteristics: (1) groundwater production rate over a 24-hour period of at least 0.1 gallons per

minute (gpm); and (2) groundwater quality with total dissolved solids (TDS) less than 10,000 milligrams per liter (mg/L).

3.2.2 Identified Onsite Hydrostratigraphic Unit

Based on boring log and monitoring well data around the BAP, the uppermost aquifer system is comprised of fine to coarse sand and gravel associated with the alluvial sediments of the Ohio River valley. The sand and gravel of the uppermost aquifer has an estimated range of hydraulic conductivity from 1 x 10-1 to 1 x 10-4 centimeters per second (cm/sec). in the area of the BAP. The direction of flow is generally to the east and southeast toward the Ohio River. Contours depicting the groundwater elevations and general direction of flow in the uppermost aquifer are shown in Figure 3-1. The uppermost aquifer is separated from an upper zone of saturation and the bottom of the BAP unit by a layer of silty clay, organic clay and silt that varies in thickness from 9.5 ft to 33.6 ft. The thicker portions of the layer are typically found along the west side of the BAP farthest from the Ohio River. Boring logs also suggest that the top of top of the uppermost aquifer ranges in elevation from approximately 619 ft to 635 ft. above mea sea level (amsl).


3.3 <u>Review of Existing Monitoring Network</u>


3.3.1 Overview

The groundwater monitoring network is shown on Figure 3-2 and consists of two (2) wells located upgradient (MW-BAP-4 and MW-BAP-5) and three (3) monitoring wells located downgradient (MW-BAP-1, MW-BAP-2 and MW-BAP-3) of the BAP and provide detection monitoring for the uppermost aquifer (Sand and Gravel Aquifer). The number, spacing, and depth of groundwater monitoring wells included in the groundwater monitoring network are based on site-specific geochemical, geologic and hydrogeologic information of the uppermost aquifer. Well construction details are summarized in Table 3-1. Boring and well construction logs for the groundwater monitoring wells network wells are provided in Appendix C.


3.3.2 Compliance Assessment


Review of the existing groundwater monitoring well network in relation to the geologic and hydrogeologic conditions in the area of the BAP indicates that the monitoring well network consists of a sufficient number of wells installed at the appropriate depths to collect groundwater samples from the uppermost aquifer that accurately represent the groundwater quality upgradient and downgradient of the BAP. The groundwater monitoring well network is also capable of providing upgradient background groundwater quality and downgradient detection monitoring for a potential contaminant release to the uppermost aquifer (Sand and Gravel Aquifer) nearest the waste boundary. Based on the above review, the groundwater monitoring network around the Cardinal BAP meets the requirements of 40 CFR 257.91.





Car Geologic Ci Currer Cardin Bri	
Geosyn	Figure
consu	Ya
Columbus, Ohio	Ха





Car Geologic Ci Currer Cardin Bri	
Geosyn	Figure
consu	Xb
Columbus, Ohio	D A

40 CFR 257.101 (f)(1)(iv)(B)(5)

Any corrective measures assessment conducted as required at 40 CFR 257.96

Not applicable. The Bottom Ash Pond is currently in Assessment Monitoring.

40 CFR 257.101 (f)(1)(iv)(B)(6)

Any progress reports on corrective action remedy selection and design and the report of final remedy selection required at 40 CFR 257.97(a)

Not applicable. The Bottom Ash Pond is currently in Assessment Monitoring.

40 CFR 257.101 (f)(1)(iv)(B)(7)

The most recent structural stability assessment required at 40 CFR 257.73(d)

STRUCTURAL STABILITY ASSESSMENT

CFR 257.73(d)

Bottom Ash Pond Complex Cardinal Plant Brilliant, Ohio

October, 2016

Prepared for: Cardinal Operating Company - Cardinal Plant Brilliant, Ohio

Prepared by: Geotechnical Engineering Services

American Electric Power Service Corporation

1 Riverside Plaza

Columbus, OH 43215




GERS-16-135

STRUCTURAL STABILITY ASSESSMENT CFR 257.73(d) BOTTOM ASH COMPLEX CARDINAL PLANT

GERS-16-135

10/4/2016 PREPARED BY DATE Mohammad A. Ajlouni, Ph.D., P.E. **REVIEWED BY** DATE 10 4 2016 1/ohn Massey **APPROVED BY** DATE 10 Gary F. Zych, P Manager – AEP Geotechnical Engineering



I certify to the best of my knowledge, information and belief that the information contained in this structural stability assessment meets the requirements of 40 CFR 257.73(d)

TABLE OF CONTENTS

1.0 OBJECTIVE 257.73(d)	1
2.0 NAME AND DESCRIPTION OF CCR SURFACE IMPOUNDMENT	1
3.0 STABLE FOUNDATION AND ABUTMENTS 257.73(d)(1)(i)	1
4.0 SLOPE PROTECTION 257.73(d)(1)(ii)	2
5.0 EMBANKMENT CONSTRUCTION 257.73 (d)(1)(iii)	2
6.0 VEGETATION CONTROL 257.73 (d)(1)(iv)	2
7.0 SPILLWAY SYSTEM 257.73(d)(1)(v)	3
8.0 BURIED HYDRAULIC STRUCTURES 257.73 (d)(1)(vi)	3
9.0 SUDDEN DRAWDOWN 257.73 (d)(1)(vii)	3

1.0 OBJECTIVE 257.73(d)

This report was prepared by AEP- Geotechnical Engineering Services (GES) section to fulfill requirements of CFR 257.73(d) and document whether the design, construction, operations, and maintenance of the CCR unit is consistent with recognized and generally accepted good engineering practices. This is the initial assessment as per the Rule.

2.0 NAME AND DESCRIPTION OF CCR SURFACE IMPOUNDMENT

The Cardinal Power Plant in Wells Township, Jefferson County, near the town of Brilliant in eastern Ohio. The Cardinal Power Plant is owned by Buckeye Power and AEP Generation Resources (GENCO) a unit of American Electric Power. is operated by Cardinal Operating Company. The facility operates two surface impoundments for storing CCR; the Bottom Ash Pond (BAP) Complex and Cardinal Fly Ash Reservoir II (FAR II) Dam. The focus of this report is the Bottom Ash Pond Complex.

The BAP complex is comprised of diked embankments on the east and west sides while the north and south sides of the BAP are incised. The complex consists of two separate ponds, the larger bottom ash pond and the smaller recirculation pond. The entire crest length is just over a mile, and the nominal crest width is 20 feet. The north end of the pond has been partially filled in with ash and the exact limits of the pond are poorly defined.

The pond complex was originally developed as part of the construction of Units 1 and 2 in the 1960s. The crest of the dikes forming the original pond was at El. 658.0. However, the pond complex was raised to a crest elevation of 970.0 and extensively modified in 1974 as part of the construction of Unit 3.

3.0 STABLE FOUNDATION AND ABUTMENTS 257.73(d)(1)(i)

[Was the facility designed for and constructed on stable foundations and abutments? Describe any foundation improvements required as part of construction.]

Based on the historical cross-sections extending through both the Bottom Ash Pond and the Recirculation Pond from the vertical expansion, the original ash pond embankments along the Ohio River ranged in height from 4 to 6 feet above the bottom of the ash pond.

A subsurface investigation was conducted in 2009 and the strength parameters of the foundation as well as the embankment were defined based on laboratory tests or correlations to known strengths based on blow counts. Table 1 lists the material properties for the foundation material.

The original ground surface at the site is generally located between El. 645 and 655. Near surface soils generally consist of a layer of alluvium silt, clay and fine sand (organic in some locations) over glacial outwash deposits of variable thickness overlying the bedrock surface. The alluvium clays and silts were deposited in the backwater of the Ohio River, while the outwash materials typically consist of sand, gravel and silt deposits deposited during the last ice age. Based on geological literature, the glacial outwash extends to the bedrock surface, estimated to be roughly 50 to 60 feet below the natural ground surface at the pond. The upper most bedrock consists of shale and/or sandstone belonging to the Conemaugh Group of Pennsylvanian Age. The soils were screened for liquefaction potential and found to be non-liquefiable.

Lover	γm	c'	φ'
Layer	pcf	psf	degrees
Newer Embankment Fill	125	0	31
Original Embankment Fill	125	100	30
Alluvium Silt/Clay	125	0	30
Organic Clayey Silt	125	0	30
Loose Glacial Outwash Sand/Gravel	115	0	29
MDe Glacial Outwash Sand/Gravel	120	0	34

Table 1 Strength Parameters for main Natural/constructed zones.

4.0 SLOPE PROTECTION 257.73(d)(1)(ii)

[Describe the slope protection measures on the upstream and downstream slopes.]

The Bottom Ash Complex was designed and constructed with soil embankment covered with a layer of bottom ash built up along the inboard slopes providing further protection. The outboard slopes primarily consist of grass vegetation with portions of the outboard slope protected by coarse riprap.

Operation and maintenance of the aggregate primarily includes periodic spraying for vegetation control. Grassed slopes are mowed regularly. Any erosion or slips that may occur is repaired within a timely period.

5.0 EMBANKMENT CONSTRUCTION 257.73 (d)(1)(iii)

[Describe the specifications for compaction and/or recent boring to give a relative comparison of density.]

The BAP complex embankments have maximum height of approximately 25 feet and are constructed of compacted clay on a slope ranging from 2.5:1 (2.5 feet horizontal, 1 foot vertical). The elevation at the top of the embankment around the perimeter of the BAP is approximately 670 feet msl, and the normal operating level is approximately 665 feet msl. The embankment fill materials dike ranged from hard silty Clay to fine and coarse gravel, overlying native material. The interior bottom elevation of the BAP Complex is approximately 645 feet msl.

The pond complex was originally developed as part of the construction of Units 1 and 2 in the 1960s. The crest of the dikes forming the original pond was at El. 658.0. However, the pond complex was raised to a crest elevation of 970.0 and extensively modified in 1974 as part of the construction of Unit 3.

No construction specifications are available for the Bottom Ash Pond. Recent borings through the embankment indicate that the embankment material is a medium stiff to very stiff sandy lean clay and representative of a compacted earthen material. A stability analysis of the diking system was also conducted which demonstrates that the facility has a factor of safety great than minimum values required by the CCR rule.

6.0 VEGETATION CONTROL 257.73 (d)(1)(iv)

[Describe the maintenance plan for vegetative cover.]

The vegetative areas are mowed to facilitate inspections and maintain the growth of the vegetative layer; and prevent the growth of woody vegetation.

7.0 SPILLWAY SYSTEM 257.73(d)(1)(v)

[Describe the spillway system and its capacity to pass the Inflow Design Flood as per its Hazard Classification.]

The Bottom Ash Complex has been determined to be a Significant Hazard potential CCR impoundment. Based on this hazard classification the design flood is determined by section 257.82(a)(3) to be the 1000-year storm. An analysis was performed for the 50% Probable Maximum Flood (PMF), which looks at 50% of the runoff from PMP storm of 33 inches in 24 hours. This produces significantly more runoff than the 1000-year storm and therefore exceeds the requirements of section 257.82(a)(3).

The Cardinal Bottom Ash Complex is comprised of diked embankments on three sides which directs storm water away from the impoundment and limits runoff to that which falls directly on the pond surface. The area of the pond is approximately 24.3 acres. The pond also receives pumped inflow from plant facilities and stormwater collection areas.

Discharge to the Ohio River is through a principal spillway located at the south end of the recirculation pond (a drop outlet and a 36"-pipe). During normal operation, there is no discharge to the river; rather all flows are re-circulated into the plant via the pump station located on the west side of the re-circulation pond.

Based on the flood routing, the calculated peak discharge from the dam is 67.7 cfs at a maximum pool elevation of 668.1 feet NGVD.

8.0 BURIED HYDRAULIC STRUCTURES 257.73 (d)(1)(vi)

[Describe the condition of the sections of any hydraulic structure that in buried beneath and/or in the embankment.]

The discharge pipe does not show any sign of corrosion or deterioration based on an exterior visual inspection.

9.0 SUDDEN DRAWDOWN 257.73 (d)(1)(vii)

[If the downstream slope is susceptible to inundation, discuss the stability due to a sudden drawdown.]

The downstream slope of the Bottom Ash Complex is not expected to be inundated from any adjacent water bodies.

40 CFR 257.101 (f)(1)(iv)(B)(8)

The most recent safety factor assessment required at 40 CFR 257.73(e)

Bottom Ash Pond Initial Safety Factor Assessment Cardinal Power Plant Brilliant, Ohio S&ME Project No. 7217-15-007A



Prepared for: American Electric Power 1 Riverside Plaza, 22nd Floor Columbus, Ohio 43215

> Prepared by: S&ME, Inc. 6190 Enterprise Court Dublin, OH 43016

December 30, 2015



Table of Contents

1.0	Introduction
1.1	Background1
1.2	Location and Geologic Conditions1
1.3	Previous Investigations
2.0	Scope of Work
3.0	Information Review and Site Visit
4.0	Field and Laboratory Work4
5.0	Subsurface Conditions
5.1	Stratigraphy5
5.2	Groundwater Conditions
5.3	Shear Strength and Permeability6
6.0	Safety Factor Assessment
6.1	Limit Equilibrium Analyses7
6.2	Liquefaction Potential of Embankment Soils8
6.3	Summary of Results9
7.0	Certification



List of Figures

0		
Figure 1-1 -	- Cardinal Plant	2

List of Tables

Table 5-1 – Shear Strength Parame	ters
Table 6-1 – Safety Factor Summary	

Appendices

Appendix I – 2009 & 2015 Site Investigation Figures
Appendix II – 2009 & 2015 Laboratory Testing Results
Appendix III – Shear Strength Parameter Justification
Appendix IV – Limit Equilibrium Analysis
Appendix V – 2009 Investigation Report Text
Appendix VI – Excerpt from 2010 Follow-Up Investigation Report



1.0 Introduction

1.1 Background

In April of 2015, the US EPA formally published national regulations for disposal of coal combustion residuals (CCR) from electric facilities. As part of the rule, the owner or operator of the CCR unit must obtain a certification from a qualified professional engineer stating that aspects of the CCR impoundments are in accordance with the rules. Based on our understanding of the Request for Fee Estimate received from AEP on April 29, 2015, AEP specifically requested P.E. certification to fulfill the requirements of 40 CFR § 257.73(e), *Periodic Safety Factor Assessments*. In the employment of BBC&M Engineering, Inc., the undersigned engineers conducted site investigations at the bottom ash pond in 2009 and 2010. Due to our familiarity with the site, S&ME was selected to perform the Safety Factor Assessment for this facility. S&ME understands that certification and/or documentation for other structural integrity criteria will be performed by AEP or other consultants.

1.2 Location and Geologic Conditions

The Cardinal Generating Plant is located along the Ohio River between Brilliant, Ohio and Tiltonsville, Ohio. The Bottom Ash Pond Complex is located along the west bank of the river just to the south of the Unit 3 area. The Bottom Ash Complex consists of two components: the Bottom Ash Pond and the Recirculation Pond. The Bottom Ash Pond is located north of the Recirculation Pond and they are separated by an earthen embankment. The crest elevation for all of the embankments has a minimum Elevation of 670 feet. The total length of the exterior embankment along the Ohio River is approximately 2,000 feet. Based on the current topography around the bottom ash complex, there is no discernable embankment on the north and south ends, thus the areas of the pond embankments are typically identified by referencing the eastern or western embankments. The bottom ash pond is operated at a constant Elevation of 664.5 feet. For comparison, the normal pool for this stretch of the Ohio River is EL. 644, as controlled by the Pike Island Dam Both ponds are isolated from exterior surface water inflow and during normal operation, all water that enters the pond is pumped back to the plant via the pump station located within the Recirculation Pond. The exception is during high rainfall events where the principal spillway may activate releasing water into the Ohio River through an NPDES outfall. The discharge is controlled by a 4-foot wide weir surveyed at Elevation 666.2. A review of the historical plans available for the bottom ash pond facility is included in Appendix V.

The original ground surface at the site is generally located between El. 645 and 655. Near surface soils generally consist of a layer of alluvium silt, clay and fine sand (organic in some locations) over glacial outwash deposits of variable thickness overlying the bedrock surface. The alluvium clays and silts were deposited in the backwater of the Ohio River, while the outwash materials typically consist of sand, gravel and silt deposits deposited during the last ice age. Based on geological literature, the glacial outwash extends to the bedrock surface, estimated to be roughly 50 to 60 feet below the natural ground surface at the pond. The upper most bedrock most likely consists of shale and/or sandstone belonging to the Conemaugh Group of Pennsylvanian Age.



Figure 1-1 – Cardinal Plant



1.3 **Previous Investigations**

In 2009, the undersigned engineers, when in the employment of BBC&M Engineering, Inc., completed a subsurface investigation and geotechnical assessment of the bottom ash pond embankments. The assessment, dated August 4, 2009, concluded that the embankment exhibited adequate factors of safety against slope failure under steady-state seepage and seismic loading conditions relative to typical US Army Corps of Engineers requirements. In 2010, BBC&M Engineering, Inc. performed additional geotechnical analyses and an hydrology and hydraulic evaluation of the pond. As part of this work, additional slope stability failure modes were examined, including the maximum surcharge pool and rapid drawdown load cases. A report documenting the additional geotechnical analysis, dated December 17, 2010, was submitted as an addendum to the 2009 report. The text from the 2009 report and an excerpt from the 2010 follow-up report is Appendices V and VI.



2.0 Scope of Work

In accordance with AEP's request, the following work items were performed by S&ME:

- 1. S&ME completed a cursory review of previously conducted assessment work performed by the undersigned engineers, as well as a limited number of construction documents made available by AEP.
- 2. S&ME visited the site along with personnel from AEP. The site visit was not a formal inspection, but rather served to document any significant modifications or changed conditions that may have taken place since the time of the previous investigations.
- 3. Upon completing Tasks 1 and 2, S&ME determined that there was insufficient information to certify the structural integrity of the surface impoundment in accordance with the requirements of 40 CFR § 257.73(e). To this end, S&ME was authorized to perform a supplemental investigation to support the safety factor assessment. Details regarding the investigation are described in the following sections of this report.

3.0 Information Review and Site Visit

S&ME conducted a cursory review of previous documents relating to the bottom ash pond and conducted a site visit at the facility. AEP provided S&ME with the following documents:

- Site Development Plan 1973 (Dwg. 3-3017-5 and 3-3027-3)
- Assessment of Dam Safety Final Report, Clough Harbour, & Assoc., December, 2009
- Bottom Ash Pond Subsurface Investigation & Analysis, BBC&M Engineering, Inc., August, 2009
- Addendum to Bottom Ash Pond Investigation, BBC&M Engineering, Inc., December, 2010

On August 18, 2015, the undersigned S&ME personnel met with Dr. Mohammad Ajlouni (AEP Civil Engineering) and Mr. Randy Sims (Landfill Operations) at the Cardinal Plant and conducted a site visit at the bottom ash pond. The participants discussed and observed the operations of the bottom ash and recirculation ponds, including the hydraulic structures within the ponds. During our visit, two localized possible seepage areas were observed on the outboard slope of the eastern embankment of the recirculation pond. Based on discussions with the group, it was believed that the seepage areas were relatively new.

One apparent seepage area was located immediately north of the existing riprap and the other was approximately 300 feet north of the riprap. The limits of the possible seepage areas were delineated with a handheld GPS unit. The apparent seepage areas range from 35 to 50 feet wide by 6 to 8 feet high. The seepage areas were observed to be wetter than the surrounding area and were muddy in some areas, which may be a result of mowing operations. While the ground surface has been softened as a result of seepage, there was no indication of flowing water emanating at either of the areas at the time of our visit. Additionally there was no indication of piping of soil. S&ME understands the riprap on the outboard slope of the recirculation pond to the south of the new seepage area was constructed as an inverted filter; similar seepage conditions were observed in this area resulting in construction of the filter. Based on the historical drawings, the embankments do not contain any internal drains to intercept/control the phreatic



surface within the embankment. Despite this, S&ME understands the embankments have otherwise performed well, particularly in regard to shallow sloughs along the outboard slope of the 41 years that they have been in service in the current configuration.

While no other visual observations suggested dam safety concerns, S&ME noted the following modifications to the bottom ash pond complex since the 2009 and 2010 assessments:

- The northern section of the western bottom ash pond embankment was widened on the outboard side to create additional space for construction staging.
- Crest improvements were made to raise low areas and establish a consistent top of dam Elevation of 670 feet.
- The 2009 investigation focused only on the river side embankment. Although the river side embankment is significantly taller than the west embankment, investigation of the west embankment was believed to be warranted.

4.0 Field and Laboratory Work

As part of the 2009 investigation, 7 soil borings were performed along the eastern embankment of the bottom ash pond and recirculation pond. For the 2015 supplemental investigation, S&ME performed 4 soil borings along the western embankments, as well as two additional shallow borings through the eastern embankment crest upstream from the identified seepage areas. The borings are designated as CD-BAP-1501 through B-1505 and MW-BAP-4 through MW-BAP-5. Boring CD-BAP-1503, originally planned to be located at the toe of the west embankment could not be accessed and was not performed. Boring numbers with 'MW' indicate a monitoring well was installed at this location, which were performed as part of a separate hydrogeology study. Additionally, S&ME installed three other monitoring wells, designated MW-BAP-1 through MW-BAP-3, and advanced one soil boring designated CD-BAP-1506 as part of the separate hydrogeology study at the bottom ash pond facility. Although not performed as part of this factor of safety assessment, the results from these explorations were considered in developing our understanding of the embankments and foundation soils. Locations of all explorations are shown on the Plan of Borings included as Drawing No. 1 in Appendix I.

Laboratory testing was performed on selected representative soil samples obtained during the field investigations to determine natural moisture content (ASTM D2216), liquid and plastic limits (S&ME adjustment to ASTM D4318), and grain size analyses (ASTM D422). The results of these and other tests permit an evaluation of the strength, compressibility and permeability characteristics of the soils encountered at this site.

The results of the moisture content testing and of the liquid and plastic limits are graphically displayed on the individual boring logs presented in Appendix I. All laboratory test results, including a summary of laboratory test results and grain size analyses are presented in Appendix II.



5.0 Subsurface Conditions

5.1 Stratigraphy

Borings CD-BAP-1501,CD-BAP-1502, and MW-BAP-5 were performed from the crest of the western embankment, while Boring MW-BAP-4 was performed from the toe of the western embankment. Based on the descriptions of the samples recovered in the borings and laboratory testing, the subsurface stratigraphy for each section can generally be described in descending order from the top of the western embankment as follows:

- Borings CD-BAP-1502 and MW-BAP-5 were performed from the crest of the embankment encountered 15 inches of aggregate at the ground surface overlying 10 to 13 feet of embankment fill consisting of medium-dense to dense fine to coarse sand and gravel and hard clayey silt. SPT N-values (corrected for 60% energy) ranged from 13 to 60 while hand penetrometer measurements on samples exhibiting cohesion ranged from __ to 4.5+ tons per square foot (tsf).
- Boring CD-BAP-1501 was performed from the widened crest area. The boring encountered 15 inches aggregate underlain by 11.5 feet of embankment fill consisting of a thin stratum of medium-stiff clayey silt over of loose to medium dense fine to coarse sand.
- Underlying the embankments, the borings encountered alluvial soils consisting of

Borings CD-BAP-1504 and CD-BAP-1505 were performed from the crest of the eastern embankment adjacent to the observed seepage areas. The main purpose of these boring was to identify potential anomalies within the embankments that would suggest a unique circumstance which could be contributing to the observed seepage. Both borings were advanced to a depth of 16 feet within the embankment fill. For reference, the seepage areas were observed to begin approximately 6 to 8 feet below the crest. These borings, along with results from the sampling from monitoring wells MW-BAP-1, MW-BAP-2 and MW-BAP-3 did not reveal any appreciable differences from the crest borings performed during the 2009 investigation, such as a layer or zone of clean sand, as the embankment fill was already known to contain soils of a varying degree.

The stratigraphy of the eastern embankments is summarized in the text from the 2009 Investigation included as Appendix V.

5.2 Groundwater Conditions

Groundwater observations were made as each boring was being advanced and measurements were made at the completion of drilling. The groundwater observations are graphically displayed on the boring logs and also noted at the bottom of the log, and are referenced from the ground surface. Groundwater was encountered within the crest borings at a depth of approximately 15 feet. Groundwater in Boring MW-BAP-4 was encountered at a depth of 5.5 feet. The groundwater readings correlate to an approximate Elevation of 655 feet.

Temporary open standpipe piezometers were installed in Borings CD-BAP-1504 and CD-BAP-1505 to obtain groundwater information in relation to the observed seepage area. Unfortunately, owing to the presence of overhead electric along the outboard side of the crest, the borings had to be performed near the inboard side of the crest. Several longer term groundwater readings were taken during the course of



the field work. The readings are summarized on the individual well logs, and generally range between Elevation 661 and Elevation 663. The readings indicate a small decrease in water level from the recirculation pond operating pool. It should be noted that all of the wells positioned within the crest are located on the inboard side to avoid blocking the road as well as the overhead power lines.

5.3 Shear Strength and Permeability

The laboratory testing results for the 2015 investigation were compared to laboratory testing completed as part of the 2009 investigation. The comparison of the index testing was performed to determine if there was any justification for developing different shear strength and permeability values for the subsurface materials encountered in the western side of the complex than had been previously been estimated for cross-sections on the eastern side in 2009. As the results of the 2009 laboratory index testing are very similar to the new index testing results, S&ME is of the opinion that the strength parameters used to characterize the eastern embankment and foundation soils in 2009 are applicable to the supplemental investigation of the western embankment and foundation soils.

The shear strength parameters used in the slope stability analysis are shown in Table 5-1.

Material Description	Ywet	Effective		
Material Description	(pcf)	φ′	c' (psf)	Reference
Newer Embankment Fill	125	31°	0	SPT and Index Testing Correlations
Original Embankment Fill	125	30°	100	Index Testing Correlations
Alluvium Silt and Clay	125	30°	0	Index Testing Correlations
Organic Clayey Silt	125	30°	0	Index Testing Correlations and CU Triaxial Test (BBCM 2009)
Very Loose to Loose Glacial Outwash Sand and Gravel	115	29°	0	SPT and Grain Size Correlations
Medium Dense Glacial Outwash Sand and Gravel	120	34°	0	SPT and Grain Size Correlations
Granular Embankment Fill ⁽¹⁾	115	30°	0	SPT and Grain Size Correlations

Table 5-1 – Shear Strength Parameters

⁽¹⁾Applies only to widened crest area on the northwestern side of bottom ash pond

6.0 Safety Factor Assessment

As part of the safety factor assessment, S&ME completed Parts 1 and 2 of Section 257.73(e) of the Final Rules for the Disposal of Coal Combustion Residuals from Electric Utilities published on April 17, 2015 in the Federal Register. In accordance with the Rule, the analysis was performed for the critical cross-sections(s) that are anticipated to be most susceptible of all cross-sections to structural failure based on appropriate engineering considerations. The Rule specified the following loading conditions for analysis:



- i. Static Factor of Safety under the long-term, maximum storage pool loading condition must equal or exceed 1.50.
- ii. Calculated static factor of safety under the maximum surcharge pool loading condition must equal or exceed 1.50.
- iii. The calculated seismic factor of safety must equal or exceed 1.00.
- iv. For dikes constructed of soils susceptible to liquefaction, the calculated liquefaction factor of safety must equal or exceed 1.20.

6.1 Limit Equilibrium Analyses

The 2009 Investigation Report and the 2010 Addendum discuss in detail the subsurface investigation, laboratory testing, parameter justification, seepage analyses and limit equilibrium slope stability analyses that were performed to develop safety factors for the bottom ash pond embankments. As mentioned previously, engineering parameters developed as part of the 2009 and 2010 investigations were utilized for the new analyses associated with the western embankment as the laboratory testing and subsurface investigation did not encounter soil properties that differed greatly from the soils encountered in the previous investigations.

In summary, four sections along the eastern (river-side) embankment and two sections along the western embankment were studied. Both cross-sections through the western embankment are located within the bottom ash pond as the embankment adjacent to the recirculation pond is only 4 to 6 feet high and access to the toe was not readily available. Subsurface information for each section was obtained by performing borings through the crest and toe of the embankment. Based on a review of all six sections explored, three were selected for detailed limit equilibrium stability analysis (two on the eastern embankment and one on the western embankment).

Prior to performing the limit equilibrium stability analyses as part of the 2009 assessment, seepage analyses were performed to develop a better understanding of the likely phreatic surface within the embankment and foundation. The models were calibrated by adding additional total head boundary conditions within the subsurface to best model the groundwater table as observed in the observation wells. Although a classically shaped phreatic surface extending from the ash pond level to the Ohio River was generated by the seepage analyses, much of the seepage emanating from the ponds appears to be moving downward through the newer embankment fill and thin stratum of alluvium soils and into the glacial outwash sand and gravel stratum which essentially serves as a drain.

Results of the slope stability analysis indicate that the critical cross-section occurs through the eastern embankment of the bottom ash pond (referred to as Section D in the 2009 and 2010 assessments). The design cross-section does not vary along the eastern embankment, but Section D yielded the lowest factors of safety due to slight variations in the outboard slope. All load cases performed for the Safety Factor Assessment as well as additional load cases evaluated for typical US Army Corps of Engineer's requirements met the minimum factor of safety for global stability.

One observed seepage area is located just north of Section B and the other is located approximately 200 feet south. Comparison of boring logs for CD-BAP-1504 and CD-BAP-1505 with the log for boring CD-PZ-BAP-0902 located at Section B do not reveal any key differences in the embankment fill. In fact, Boring CD-PZ-BAP-0902 exhibited a larger zone of granular embankment fill located within the observed



elevation of seepage on the outboard slope, but no seepage was observed adjacent to this boring. The fill soils are believed to vary laterally through the embankment as much as it was observed to vary vertically at the boring locations, suggesting that the granular layers observed in the borings are unlikely to extend all the way through the embankment. Considering this, it is the opinion of S&ME that at this time, the seepage areas are representative of localized pockets of more permeable soils within the overall embankment matrix. As such, it is not believed that the phreatic surface intercepts the outboard face, but rather that there are narrow zones of seepage with unsaturated soils beneath. Nonetheless, these areas should be addressed, as further discussed below.

As noted, the seepage observed during our August, 2015 site visit appeared to occur in two isolated areas. With time, the outboard slope at these locations may weaken due to the presence of groundwater within close proximity to the ground surface resulting in reduced shear strength and shallow slope failures. Though such a failure would typically be minor in extent, S&ME recommends these areas be addressed in the near future before they lead to more significant issues over time. Construction of an inverted filter may be suitable given the performance of the existing inverted filter on the south end. S&ME also recommends continued monitoring of these areas to ensure soils particles are not being carried from inside the embankment.

6.2 Liquefaction Potential of Embankment Soils

S&ME evaluated the potential of the embankment soils to liquefy during a seismic event. The embankment material is classified as a fined grained material and the recovered samples with gradation testing were evaluated following guidelines presented in the 2003 NEHRP (National Earthquake Hazards Reduction Program) Recommended Provisions for Seismic Regulations for New Buildings and Other Structures. The provisions in Chapter 7 indicate that liquefaction potential in fine grained soils should be assessed provided the following criteria are met (Seed and Idriss 1982; Seed et al., 1983): the weight of the soil particles finer than 0.005 mm is less than 15 percent of the dry unit weight of a specimen of the soil; the liquid limit of soil is less than 35 percent; and the moisture content of the in-place soil is greater than 0.9 times the liquid limit. If all of these criteria are not met, the soils may be considered non-liquefiable.

Laboratory testing results from 16 fine grained samples that were available from the 2009 and 2015 investigations for evaluation of the screening criteria. Of the 16 samples, 8 samples contained data to check all three screening criteria, and 7 samples contained data to check two screening criterion. Based on the results of the screening, no sample met all 3 criteria; therefore, these fine grained embankment fill can be considered non-liquefiable. A table depicting this evaluation is included in Appendix IV.

The potential for the coarse grained embankment soils to resist liquefaction was evaluated. The fine grained (cohesive) and coarse grained (granular) embankment soils appear to be from the same borrow source as there are no well-defined layers and often only minor variations in the percent by weight of the recovered sample change the main description from fine grained to coarse grained. Although construction records were not available, the density of the coarse grained samples and consistency of the fine grained samples within the embankment fill suggest they were well compacted. Based on the controlled manner in which the fill was placed, the coarse grained embankment soils can be considered non-liquefiable.



6.3 Summary of Results

A summary of the computed safety factors for the critical cross-section is provided in Table 5-2. Also included in the table are the minimum values defined in 40 CFR § 257.73(e)(1) subparts (i) through (iv). Graphical output corresponding to the analysis cases are presented in Appendix IV along with additional slope stability load cases evaluated during the course of the bottom ash pond assessments.

Analysis Case	Minimum Safety Factor	Computed Safety Factor
Long-term, maximum storage pool	1.50	1.52
Maximum surcharge pool	1.40	1.52
Pseudo-static seismic loading	1.00	1.09
Embankment Liquefaction	1.20	Non-liquefiable

Table 6-1 – Safety Factor Summary

7.0 Certification

Based on our previous investigations and current assessment of the Bottom Ash Pond facility, S&ME certifies that this assessment meets the requirements of paragraphs (e)(1) and (e)(2) of Part 257.73 for the critical cross-section of the embankment.

We appreciate having been given the opportunity to be of service on this project. If you have any questions, please do not hesitate to contact this office.

Sincerely,

S&ME, Inc.




Micha D. La

Michael G. Rowland, P.E. Senior Engineer Registration No. 65559

Appendices

Appendix I – 2009 & 2015 Site Investigation Figures



В	С

EASTING	ELEVATION										
2513493.10	668.68										
2513568.73	668.04										
2513647.44	650.07										
2513666.53	668.05										
2513742.24	650.11										
2513791.36	668.64										
2513886.71	650.34										
2513678.00	671										
2513713.00	671										
2513525.00	670										
2513591.00	670										
2513205.00	671										
2513925.00	670										
2513705.00	670										
2513518.00	670				LEG	END					
2513614.00	660					EXISTING GROUND CONTOUR (1 FT.	INTERVAL)				
2513275.00	670				<u> </u>	EXISTING WATER SURFACE (AT TIME					
							LOF SURVET)				
					XXXX	FENCE LINE					
					~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	EXISTING VEGETATION					
					CV-PZ-BAP-0901	BORING NUMBER AND LOCATION 2009 INVESTIGATION					
	50	ALE IN FEET			CD-BAP-1501	BORING NUMBER AND LOCATION		PROJECT NUMBER:	7217-15-007B	DRAWN BY:	MF
					Ť	2015 INVESTIGATION		DRAWING DATE:	12-30-2015	ENGINEER:	MT
	0	100 200			MW-BAP-1	MONITORING WELL NUMBER AND LOCATION 2015 INVESTIGATION		LAST UPDATED:	12-30-2015	APPROVED BY:	: MC
										SCALE:	1" :
								<u> </u>			
D		E	CM 1 2 3 F 4 5 6	7   G	3 16 INCH 4 H	12 16 J	I _{tenths} I ₁₀ K I ₂₀	30 L	INCHES	_s I ₁ M I	2

#### EXPLANATION OF SYMBOLS AND TERMS USED ON BORING LOGS FOR SAMPLING AND DESCRIPTION OF SOIL

#### SAMPLING DATA



- Blocked-in "SAMPLES" column indicates sample was attempted and recovered within this depth interval.

- Sample was attempted within this interval but not recovered.
- 2/5/9 The number of blows required for each 6-inch increment of penetration of a "Standard" 2-inch O.D. split-barrel sampler, driven a distance of 18 inches by a 140-pound hammer freely falling 30 inches. Addition of one of the following symbols indicates the use of a split-barrel other than the 2" O.D. sampler:

2S -3S -

- 2¹/₂"O.D. split-barrel sampler

- 3" O.D. split-barrel sampler

- P Shelby tube sampler, 3" O.D., hydraulically pushed.
- R Refusal of sampler in very-hard or dense soil, or on a resistant surface.
- 50-2" Number of blows (50) to drive a split-barrel sampler a certain number of inches (2), other than the normal 6-inch increment.
- S/D Split-barrel sampler (S) advanced by weight of drill rods (D),
- S/H Split-barrel sampler (S) advanced by combined weight of rods and drive hammer (H).

#### SOIL DESCRIPTIONS

All soils have been classified basically in accordance with the Unified Soil Classification System, but this system has been augmented by the use of special adjectives to designate the approximate percentages of minor components as follows:

Adjective	Percent by Weight
trace	1 to 10
little	11 to 20
some	21 to 35
"and"	36 to 50

The following terms are used to describe density and consistency of soils:

<u>Term (Granular Soils)</u>	Blows per foot
Very-loose	Less than 5
Loose	5 to 10
Medium-dense	11 to 30
Dense	31 to 50
Very-dense	Over 50
Term (Cohesive Soils)	<u>Qu (tsf)</u>
Very-soft	Less than 0.25
Soft	0.25 to 0.5
Medium-stiff	0.5 to 1.0
Stiff	1.0 to 2.0
Very-stiff	2.0 to 4.0
Hard	Over 4.0

#### LOG OF BORING NO. CD-BAP-1501 Page 1 of 1 **BOTTOM ASH POND SUPPLEMENTAL INVESTIGATION** CARDINAL PLANT, BRILLIANT, OH LOCATION: N. 820,853, E. 2,513,678 11/17/15 - 11/18/15 ELEVATION: 671 DATE: 4-1/4" I.D. Hollow-stem Auger 16.0' DRILLING METHOD: COMPLETION DEPTH: 2" O.D. Split-barrel Sampler SAMPLER(S): SAMPLE NUMBER NATURAL CONSISTENCY INDEX SAMPLE SAMPLE REC-% SAMPLE DEPTH EFFORT TEST ELEV NATURAL MOISTURE CONTENT DESCRIPTION $N_{60}$ RESULTS OUID LIMI T.TMT 0 **AGGREGATE - 15 INCHES** 20 30 40 669.8 12 FILL: Medium-stiff gray clayey silt, "and" fine to 87 45 1 15 coarse sand, little fine gravel, intermixed with 21 668.2 silty clay, damp. 13 2 67 FILL: Loose to medium-dense brown and gray 6 fine to coarse sand, little to some silty fine to 4 coarse gravel, little to some silt, damp. 8 53 3 3 G 5 3 2010 NEW DEFAULT BORING LOG-W/ N60 4 6 53 3 5 10 80 3 5 18 80 6 G 6 8 10-7 0 50-1"R 659.5 FILL: Dense brown fine to coarse sand, trace fine 40 73 8 19 gravel, some to "and" clayey silt, damp. . × 658.0 13 9A 43 100 FILL: Stiff to very-stiff gray silty clay, some to H=1.75-2.25 10 15 "and" fine to coarse sand, little fine to coarse 9B H=3.0-4.0 656.5 gravel, damp. 15 FILL: Dense brown and gray fine to coarse sand, 10 34 67 8 little fine to coarse gravel, some silt, damp. 655.0 19 - Boring backfilled with cement bentonite grout. - Boring location recorded with a hand-held GPS unit. Elevation estimated from March, 2015 plant survey. 20 -- Datum: Ohio State Plane South NAD 27/ NAVD 29 (Plant Grid). 25 30 SYMBOLS USED TO INDICATE TEST RESULTS $\overline{\Delta}$ Ţ Drill Rod Energy Ratio : 0.75 WATER LEVEL: - Gradation - Uncon Comp G See H - Penetrometer (tsf) Last Calibration Date : 2/20/2013 WATER NOTE: Separate W-Unit Dry Wt (pcf) T - Triax Comp C - Consol. Curves D-Relative Dens (%) Drill Rig Number : S&ME DATE: ATV 550-2

JOB: 7217-15-007A

PLATE 3

#### LOG OF BORING NO. CD-BAP-1502 Page 1 of 2 **BOTTOM ASH POND SUPPLEMENTAL INVESTIGATION** CARDINAL PLANT, BRILLIANT, OH LOCATION: N. 820,839, E. 2,513,713 11/18/15 ELEVATION: 671 DATE: 41.5' 4-1/4" I.D. Hollow-stem Auger COMPLETION DEPTH: DRILLING METHOD: SAMPLER(S): 2" O.D. Split-barrel Sampler SAMPLE NUMBER SAMPLE NATURAL CONSISTENCY INDEX SAMPLE SAMPLE REC-% DEPTH, FEET EFFORT TEST ELEV NATURAL MOISTURE CONTENT DESCRIPTION $N_{60}$ RESULTS ASTIC T.TMT LTOUTD LTM 0 **AGGREGATE - 12 INCHES** 10 20 30 40 670.0 FILL: Dense brown and gray fine to coarse 38 53 1 12 gravel, some fine to coarse sand, little silt, damp. 668.5 18 FILL: Hard brown and gray clayey silt, "and" fine 60 2 80 H=4.5 to coarse sand, little fine gravel, damp. 18 667.2 30 FILL: Medium-dense to very-dense brown and gray fine to coarse sand, little to some fine to 51 80 3 23 5 coarse gravel, little to some silt, silty clay, or 18 2010 NEW DEFAULT BORING LOG-W/ N60 clayey silt (varies), damp. 31 80 4 × × G 13 5 26 93 10 662.5 11 FILL: Hard gray and brown clayey silt, some to 33 87 H=4.5 6 "and" fine to coarse sand, little fine to coarse 11 15 gravel, damp. -10-41 7 53 H=4.5 15 Ρ 657.5 FILL: Medium-dense gray and brown fine to 14 8 67 coarse sand, some fine to coarse gravel, some 4 silty clay, moist becoming wet. 15 Р 654.0 FILL: Medium-dense gray fine to coarse sand, 9 19 87 • * 7 some fine to coarse gravel, some clayey silt, wet. × G 652.7 8 Stiff gray clayey silt, some fine to coarse sand, some fine gravel, moist. 10 11 100 H=1.25 6 3 20 -Ρ H=1.25 649.2 Stiff brown silty clay, some fine to coarse sand, little to some fine to coarse gravel, moist. 13 73 H=2.5 11 0 12 33 . H=1.25 'SH ŚΗ 25 645.5 Very-stiff red-brown mottled with gray silty clay, SH trace to little fine to coarse sand, contains silt H=3.0-3.75 93 13 5 16 seams, damp. 93 13 H=3.5 14 - 30 SYMBOLS USED TO INDICATE TEST RESULTS Ţ Drill Rod Energy Ratio : 0.75 WATER LEVEL: Gradation See H - Penetrometer (tsf) - Uncon Comp Last Calibration Date : 2/20/2013 WATER NOTE: Separate W-Unit Dry Wt (pcf) Triax Comp Curves D - Relative Dens (%) Drill Rig Number : S&ME DATE: Ĉ - Consol ATV 550-2

-CONTINUED-

#### LOG OF BORING NO. CD-BAP-1502 Page 2 of 2 **BOTTOM ASH POND SUPPLEMENTAL INVESTIGATION** CARDINAL PLANT, BRILLIANT, OH LOCATION: N. 820,839, E. 2,513,713 11/18/15 ELEVATION: 671 DATE: 4-1/4" I.D. Hollow-stem Auger 41.5' DRILLING METHOD: COMPLETION DEPTH: 2" O.D. Split-barrel Sampler SAMPLER(S): SAMPLE NUMBER NATURAL CONSISTENCY INDEX SAMPLE SAMPLE REC-% SAMPLE DEPTH, FEET EFFORT ELEV TEST NATURAL MOISTURE CONTENT $N_{60}$ DESCRIPTION RESULTS OUID LIMI T.TMT 30 Very-stiff red-brown mottled with gray silty clay, 20 30 40 trace to little fine to coarse sand, contains silt seams, damp. [/] 5 6 15 87 15 H=3.5 638.5 Stiff to very-stiff brown mottled with gray silty clay, some to "and" from to medium sand, trace Ρ H=1.5-2.25 coarse sand, damp. 636.5 Loose red-brown from to medium sand, trace 35-8 100 16 3 coarse sand, "and" silt, damp. 2010 NEW DEFAULT BORING LOG-W/ N60 3 634.0 Stiff red-brown silty clay, "and" fine to medium sand, trace coarse sand, trace fine gravel, damp. 632.7 100 17 2 6 H=1.75 Very-loose brown fine to medium sand, "and" silt, damp. 40-18 5 67 629.5 - Encountered water at 15.0' - Boring backfilled with cement bentonite grout. - Boring location surveyed with a hand-held GPS unit. Elevation estimated from March 2015 plant 45 survey, - Datum: Ohio State Plane South NAD 27/NAVD 29 (Plant Grid). 50-55 60 SYMBOLS USED TO INDICATE TEST RESULTS $\overline{\Delta}$ Ţ Drill Rod Energy Ratio : 0.75

G - Gradation Q - Uncon Comp T - Triax Comp C - Consol.

See

Separate

Curves

H - Penetrometer (tsf)

W-Unit Dry Wt (pcf)

D-Relative Dens (%)

WATER LEVEL:

WATER NOTE:

DATE:

S&ME

Last Calibration Date : 2/20/2013

Drill Rig Number :

## LOG OF BORING NO. CD-BAP-1504 BOTTOM ASH POND SUPPLEMENTAL INVESTIGATION CARDINAL PLANT, BRILLIANT, OH



				819,154			3,525 ELEVATION:(	<b>570</b>				1/16/15	5 8.0'
	LING PLER	METH	10				plit-barrel Sampler		COMPL	ETION	DEPTH	<b>I</b>	0.0
		· · ·	ш					NA	FURAL C	ONSIST	ENCY IN	IDEX	
ELEV.	DEPTH, FEET	SAMPLE NUMBER	SAMPLE	SAMPLE EFFORT	N ₆₀	SAMPLE REC-%	DESCRIPTION				TURE CO		TEST RESULT
668.7	- 0 -			27			AGGREGATE - 16 INCHES			20	~	40	-
667.5		1		18/ 18/ 14	40	87	FILL: Hard gray and brown silty clay, some fine to coarse sand, brown fine gravel, dry.						-
666.0		2		¹⁸ / _{10/ 9}	24	80	FILL: Medium-dense dark-brown fine to coarse sand, trace fine gravel, trace silt, dry.						H=4.0
664.5	- 5 -	3		⁴ / _{20/19}	49	93	FILL: Hard gray and brown silty clay, "and" fine to coarse sand, little fine gravel, dry.						H=4.0
663.0		4		11/ 18/	53	100	FILL: Dense dark-gray and brown fine to coarse sand, little to some fine to coarse gravel, some						H=4.0
661.5		⊻5		24 24 17 14	39	67	silty clay, dry. FILL: Hard brown silty clay, some fine to coarse sand, little fine gravel, dry.						-
	10	6		11 /14 21	44	33	FILL: Medium-dense to dense brown and dark-gray fine to coarse sand, little to some fine to coarse gravel (sandstone fragments), little to						-
	- 10-	7		7 / 11/ 11/ 16	34	67	"and" silty clay, dry.						G
		8		¹¹ /8/10	23	27			•				G
		9		⁸ / ₂₇ / ₁₆	54	47							-
654.0	- 15-	10		² /4/7	14	0							H=1.5-2.0
		<b>2</b> 5		11 1 _/ 4,	10	100	FILL: Medium-stiff to stiff brown and gray silty clay, some fine to coarse sand, little fine to coarse gravel, damp becoming wet.						H=1.3-2.0 H=0.75-1.5
<u>652.0</u>				⁷ 4									
	-20-	-					- No seepage encountered. - Encountered water at 16.5'.						•
							<ul> <li>Borehole converted to temporary piezometer upon completion - See Separate Well Log.</li> <li>Boring backfilled with cement bentonite grout.</li> </ul>						-
							- Boring location surveyed with a hand-held GPS unit. Elevation estimated from March 2015 plant						
	-25-						survey. - Datum: Ohio State Plane South NAD 27/NAVD 29 (Plant Grid).						-
													-
													-
													-
	<u>-</u> 30-		Ţ				SYMBOLS USED TO INDICATE TEST R	L ESULTS	::::: P	rill Dod	: : : :	Ratio :	0.75
	ER N	v LL.	<u> </u>	7.9 In W 12/10	/ell		G - Gradation See H - Penetro Q - Uncon Comp Separate W - Unit Dr T - Triax Comp Curves D - Relativ	y Wt (p	(tsf) pcf)	Last Ca	alibration		2/20/2013

#### LOG OF BORING NO. CD-BAP-1505 Page 1 of 1 **BOTTOM ASH POND SUPPLEMENTAL INVESTIGATION** CARDINAL PLANT, BRILLIANT, OH 11/17/15 LOCATION: N. 819,448, E. 2,513,591 ELEVATION: 670 DATE: 4-1/4" I.D. Hollow-stem Auger 17.5' DRILLING METHOD: COMPLETION DEPTH: 2" O.D. Split-barrel Sampler SAMPLER(S): SAMPLE NUMBER NATURAL CONSISTENCY INDEX SAMPLE SAMPLE SAMPLE REC-% DEPTH, FEET EFFORT TEST ELEV NATURAL MOISTURE CONTENT $N_{60}$ DESCRIPTION RESULTS T.TMT OUTD LITMI 0 **AGGREGATE - 16 INCHES** 20 30 40 668.7 FILL: Medium-dense to dense brown and gray 31 60 12 fine to coarse sand, some fine to coarse gravel, 13 little silt, dry. 65 53 2 12 666.0 40 FILL: Medium-dense brown fine to coarse gravel, 24 3 53 10 some fine to coarse sand, little to some silt, dry. 5 q 4 29 13 q 14 5 28 80 9 661.5 13 FILL: Very-stiff to hard brown clayey silt, "and" 15 53 H=3.5 6 fine to coarse sand, little to some fine to coarse Ó 5 gravel, damp to moist. 10 7A 23 100 H=1.5 659.2 FILL: Medium-dense brown and gray fine to 7B11 coarse sand, some fine to coarse gravel, little silty clay, dry. 8 18 73 657.0 FILL: Hard brown and gray silty clay, some fine 9 16 67 H=4.5 to coarse sand, little fine to coarse gravel, moist. 15 10 16 87 H=4.5 Ò 654.0 G 8 FILL: Medium-stiff brown and gray silty clay, 11 11 53 H=0.5-1.0 3 some fine to coarse sand, little fine to coarse 652.5 gravel, moist. 6 - No seepage encountered. - Encountered water at 14.5'. 20 -- Borehole converted to temporary piezometer well upon completion - See Separate Well Log. - Boring backfilled with cement bentonite grout. - Boring location surveyed with a hand-held GPS unit. Elevation estimated from March 2015 plant survey. - Datum: Ohio State Plane South NAD 27/NAVD 29 (Plant Grid). 25

SYMBOLS USED TO INDICATE TEST RESULTS

H - Penetrometer (tsf

W-Unit Dry Wt (pcf)

D - Relative Dens (%)

See

Separate

Curves

Gradation

- Uncon Comp

T - Triax Comp C - Consol.

G Q

30

WATER LEVEL:

WATER NOTE:

DATE:

 $\overline{\Delta}$ 

8.8

In Well

12/10/15

Ţ

2010 NEW DEFAULT BORING LOG-W/ N60

S&ME

Drill Rod Energy Ratio : 0.75

Drill Rig Number :

Last Calibration Date : 2/20/2013


#### LOG OF BORING NO. MW-BAP-4 Page 1 of 2 BOTTOM ASH POND SUPPLEMENTAL INVESTIGATION CARDINAL PLANT, BRILLIANT, OH LOCATION: N. 820,884, E. 2,513,614 11/20/15 - 11/23/15 ELEVATION: 660 DATE: 4-1/4" I.D. Hollow-stem Auger 40.0' DRILLING METHOD: COMPLETION DEPTH: SAMPLER(S): 2" O.D. Split-barrel Sampler SAMPLE NUMBER NATURAL CONSISTENCY INDEX SAMPLE REC-% SAMPLE SAMPLE DEPTH, FEET EFFORT TEST ELEV NATURAL MOISTURE CONTENT $N_{60}$ DESCRIPTION RESULTS OUTD LIMI T, TMT 0 **AGGREGATE - 12 INCHES** 10 20 30 40 659.0 FILL: Medium-dense to dense gray and brown 15 39 fine to coarse gravel, some to "and" fine to coarse 87 H=4.25-4.5 1 sand, little to some silt, dry. 16 9 2 18 53 5 2010 NEW DEFAULT BORING LOG-W/ N60 9 3 20 67 5 654.7 FILL: Very-soft brown and gray silty clay, "and" 654.2 35 fine to coarse sand, little fine to coarse gravel. 13 4 31 87 FILL: Dense bown fine to coarse sand, little fine 12 to coarse gravel, "and" clayey silt, cobbles, moist. 20 5 -50-3"R 652.5 Stiff to very-stiff dark-brown mottled with dark-gray silty clay, little fine to coarse sand, trace fine gravel, slightly organic, damp. 3, 9 87 H=2.0-3.06 Δ 10 Р H=1.25-2.5 15 643.8 Very-stiff brown mottled with gray silty clay, 5 7 14 87 H=2.0-3.5 little fine to medium sand, trace coarse sand, few 6 cobbles, contains silt seams near top of stratum, damp. 7 18 100 H=2.25-3.25 20 10 28 5 9 100 H=3.0 14 5 100 H=3.25 10 14 25 SYMBOLS USED TO INDI CATE TEST RESULTS Ţ Drill Rod Energy Ratio : 0.75 WATER LEVEL: - Gradation - Uncon Comp See H - Penetrometer (tsf) Last Calibration Date : 8/2/2013 WATER NOTE: Separate W-Unit Dry Wt (pcf) Triax Comp Curves D - Relative Dens (%) **Drill Rig Number :** S&ME DATE: Ĉ - Consol ATV 550-2

JOB: 7217-15-007B

#### LOG OF BORING NO. MW-BAP-4 Page 2 of 2 **BOTTOM ASH POND SUPPLEMENTAL INVESTIGATION** CARDINAL PLANT, BRILLIANT, OH LOCATION: N. 820,884, E. 2,513,614 11/20/15 - 11/23/15 **ELEVATION:** 660 DATE: 4-1/4" I.D. Hollow-stem Auger 40.0' DRILLING METHOD: COMPLETION DEPTH: 2" O.D. Split-barrel Sampler SAMPLER(S): SAMPLE NUMBER NATURAL CONSISTENCY INDEX SAMPLE SAMPLE REC-% SAMPLE EFFORT DEPTH FEET TEST ELEV NATURAL MOISTURE CONTENT DESCRIPTION $N_{60}$ RESULTS OUID LIMI T, TMT 25 Very-stiff brown mottled with gray silty clay, 10 20 30 40 little fine to medium sand, trace coarse sand, few cobbles, contains silt seamsnear top of stratum, 11A 9 100 H=2.5 633.3 3, damp. 11B H=0.5-1.5 Δ Medium-stiff to stiff brown clayey silt, "and" fine to medium sand, trace coarse sand, includes sand seams, moist. 12 12 4 100 2010 NEW DEFAULT BORING LOG-W/ N60 30 629.5 Very-loose brown and gray fine to medium sand, little to "and" silt (percent varies), contains zones SH ′SH, with a trace of coarse sand, wet. 13 0 100 SH ′SΗ, 0 67 14 35 SH 15 1 3 67 S₽ 'SH, 0 100 16 620.0 40-- Encountered water at 5.5'. - Encountered cobbles at 18.5'. - Borehole converted to monitoring well upon completion - See separate well log. - Boring elevation recorded with a hand held GPS unit. Elevation estimated from March 2015 survey. - Datum: Ohio State Plane South, NAD 45 27/NAVD 29 (Plant Grid). 50 SYMBOLS USED TO INDI CATE TEST RESULTS $\overline{\Delta}$ Ţ Drill Rod Energy Ratio : 0.75 G - Gradation Q - Uncon Comp T - Triax Comp C - Consol. WATER LEVEL: See H - Penetrometer (tsf) Last Calibration Date : 8/2/2013 WATER NOTE: Separate W-Unit Dry Wt (pcf) Curves D-Relative Dens (%) **Drill Rig Number :** S&ME DATE:


JOB: 7217-15-007B


#### LOG OF BORING NO. MW-BAP-5 Page 1 of 3 **BOTTOM ASH POND SUPPLEMENTAL INVESTIGATION** CARDINAL PLANT, BRILLIANT, OH 11/24/15 - 11/25/15 LOCATION: N. 820,057, E. 2,513,275 ELEVATION: 670 DATE: 62.5' 4-1/4" I.D. Hollow-stem Auger DRILLING METHOD: COMPLETION DEPTH: 2" O.D. Split-barrel Sampler SAMPLER(S): SAMPLE NUMBER NATURAL CONSISTENCY INDEX SAMPLE SAMPLE SAMPLE DEPTH EFFORT REC-% TEST ELEV NATURAL MOISTURE CONTENT $N_{60}$ DESCRIPTION RESULTS T.TMT 0 **AGGREGATE - 12 INCHES** 10 20 30 40 669.0 FILL: Medium-dense brown fine to coarse sand, 8 some fine to coarse gravel, some to "and" silty 24 60 1 11 clay, dry. 5 2 13 60 2010 NEW DEFAULT BORING LOG-W/ N60 4 3 13 73 5 6 664.5 FILL: Hard gray and brown silty clay, "and" fine 9 to coarse sand, little to some fine to coarse gravel, 4 51 87 H=4.5 32 damp. 15 5 39 80 H=4.5 16 661.5 FILL: Medium-dense brown and gray fine to 13 30 87 coarse sand, little fine to coarse gravel, some silty 6 clay, damp. 11 660.0 10 FILL: Hard brown silty clay, some fine to coarse Р sand, some fine to coarse gravel (shale H=4.5 fragments), damp. 5 19 7 80 H=4.5 '10656.5 10 FILL: Medium-dense to dense brown fine to 11 coarse gravel, some fine to coarse sand, some 80 8 45 H=3.0 25 silty clay becoming trace silt at bottom of stratum, 15damp. 7 9 16 6 653.1 10A 20 100 Medium-stiff to stiff gray mottled with dark-gray 6 10**B** and brown silty clay, trace fine to coarse sand, 10 trace fine gravel, few roots, few silt seams, slightly organic, moist. Р 20-S₽ 1, 5 100 H=0.5-1.25 11 647.0 Medium-stiff to very-stiff brown mottled with gray silty clay, trace to little fine to coarse sand, 2 8 100 damp. 12 H=3.5 25 SYMBOLS USED TO INDICATE TEST RESULTS Drill Rod Energy Ratio : 0.75 ▼ WATER LEVEL: Gradation See H - Penetrometer (tsf) - Uncon Comp Last Calibration Date : WATER NOTE: 8/2/2013 Separate W-Unit Dry Wt (pcf) Triax Comp Curves D - Relative Dens (%) **Drill Rig Number :** S&ME DATE: Ĉ - Consol ATV 550-2





JOB: 7217-15-007B

#### LOG OF BORING NO. MW-BAP-5 Page 3 of 3 BOTTOM ASH POND SUPPLEMENTAL INVESTIGATION CARDINAL PLANT, BRILLIANT, OH LOCATION: N. 820,057, E. 2,513,275 11/24/15 - 11/25/15 **ELEVATION:** 670 DATE: 4-1/4" I.D. Hollow-stem Auger 62.5' DRILLING METHOD: COMPLETION DEPTH: 2" O.D. Split-barrel Sampler SAMPLER(S): SAMPLE NUMBER NATURAL CONSISTENCY INDEX SAMPLE REC-% SAMPLE SAMPLE EFFORT DEPTH, FEET TEST ELEV NATURAL MOISTURE CONTENT DESCRIPTION $N_{60}$ RESULTS T, TMT 50 619.5 Medium-stiff to stiff gray and dark-gray organic 10 20 30 40 clayey silt, trace fine to coarse sand, damp. Medium-dense to dense fine to coarse gravel, 9 23 some to "and" fine to coarse sand, trace to little 21 87 q silt, wet. 21 22 69 87 2010 NEW DEFAULT BORING LOG-W/ N60 34 55 614.6 Medium-dense to dense gray and brown fine to coarse sand, "and" fine to coarse gravel, little silt, 4 wet. 20 23 43 80 12 35 24 60 16 60 4 25 11 60 607.5 - Encountered water at 17.0'. - Borehole converted to monitoring well upon 65 completion. See separate well log. - Boring location recorded with a hand-held GPS unit. Elevation estimated from March 2015 plant survey. - Datum: Ohio State Plane South NAD 27/NAVD 29 (Plant Grid). 70-75 SYMBOLS USED TO INDI CATE TEST RESULTS $\overline{\Delta}$ Ţ Drill Rod Energy Ratio : 0.75 G - Gradation Q - Uncon Comp T - Triax Comp C - Consol. WATER LEVEL: See H - Penetrometer (tsf) Last Calibration Date : 8/2/2013 WATER NOTE: Separate W-Unit Dry Wt (pcf) Curves D-Relative Dens (%) **Drill Rig Number :** S&ME DATE: ATV 550-2










**2009 SITE INVESTIGATION** 



Images: ~Tiltonsville Ohio Quad Map.tif Xrefs: File Last Updated: Jul 06, 2009

PLATE 1

DWG. NO. PLATE 3					
			AP-0902		
	675         675         675           670         0         0         670         670		675 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 670 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770 770	67	<u>375</u> 670
-	665         ASH POND         665           660         660         660		665	66 66 67	<u>365</u> 660
_	655         FIL: V.ST - HD SILTY CLAY         655           650         4/9/09          650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650         650<		655 650 FILL: V.ST - HD SILTY CLAY	65 00 67	<u>i55</u> 650
_	645     FILL: M.DE FINE TO COARSE GRAVEL     OHIO RIVER     645       640     VST SILTY CLAY     640		640 FILL: SO - M.ST SILTY CLAY V.LO SILT	FILL: V.ST- HD SILTY CLAY UNIO RIVER 64	<u>i45</u> 640
_	635         VLO SILT         635           630         V.SO ORG CLAYEY SI LT         630		635 630 VSO - SO ORG CLAYEY SILT	4/8/09 V.SO ORG CLAYEY SILT 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 639 63	<u>.35</u> 630
-	625		625 V.LO - LO F-M SAND	V.SO SILTY CLAY INTERBEDDED WITH SILT 629 M.DE F-C SAND 620	<u>;25</u> 620
_	615         615         615           610         610         610		615 M.DE F-M SAND	<u> </u>	<u>615</u> 610
	605     605       600     605       600     600       0+00     1+00		605 600 0+00 1+00	60	<u>05</u> 300
				2+00	3
	SECTION 'A' Boring BAP-0901		SECTION 'B' Borings BAP-0902 & BAP-09	903	
	4				
	060- 		9060-4V		
_	675     N m     675     675       670     0     0     0     670		675           675         8         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6         6 </td <td><u> </u></td> <td><u>)</u></td>	<u> </u>	<u>)</u>
-	665         ASH POND         665           660         FILL: V.ST - HD SILTY CLAY         660           655         FILL: M.DE - V.DE GRAVEL         655		665         ▼ ASH POND         FILL: M.DE F-C GRAVEL           660	Lo 665 660 d 660	<u>.</u> <u>)</u>
_	650 4/10/09 ▼ FILL: HD SILTY CLAY FILL: M.DE - V.DE GRAVEL LO ORG SILT 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.110 0.1100 0.110 0.1100 0.1100 0.1100 0.1100 0.110		655 FILL: M.DE F-C SAND AND GRAVEL		<u>)</u> <u>)</u>
-	640     VLO SAND     4/10/09 V     VLO SILT       640     VLO SILT     FILL: V.ST - HD SILTY CLAY     640       005     V.SO - ST ORG CLAYEY SILT     640		640 V.LO - LO SILT	FILL: V.ST - HD SILTY CLAY OHIO RIVER 645	<u></u> )
-	630         Comparison         Comparison <td></td> <td>630 V.SO - M.ST ORG CLAYEY SILT</td> <td>V.SO - SO ORG CLAYEY SILT 630</td> <td></td>		630 V.SO - M.ST ORG CLAYEY SILT	V.SO - SO ORG CLAYEY SILT 630	
-	620     615     615     615     615     615     615     615		620         M.DE F-C SAND AND GRAVEL	M.DE F-C SAND AND GRAVEL 620	<u>)</u> 5
-	610         V.DE SAND AND GRAVEL         610         610         610         610         610         610         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605         605		610 605	610	
-	600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600         600 <td></td> <td>600         1+00</td> <td>600 2+00</td> <td><u>)</u></td>		600         1+00	600 2+00	<u>)</u>
	SECTION 'C'		SECTION 'D'		
	Borings BAP-0904 & BAP-0905		Borings BAP-0906 & BAP-090	07	
			LEGEND		
		4/20/09 💌	OBSERVATION WELL READING: ELEVATION AND DATE		
		4/3/09 🔽	SEEPAGE ENCOUNTERED DURING DRILLING		
			SOFT / VERY SOFT		
		M.ST ST / V.ST	M. STIFF STIFF / VERY STIFF		
		ST/V.ST HD	HARD		
		V.LO / LO			
		M.DE	MEDIUM DENSE		
		DE / V.DE	DENSE / VERY DENSE	PROJECT NUMBER: 011-11497-013	DRAWN
				FRUJEUT NUMBER: 011-1149/-013	URAWN
	SCALE IN FEET	ORG	ORGANIC	DRAWING DATE: 7-1-09	ENGINE

	LEGE
4/20/09 💌	OBSER
4/3/09 🔽	SEEPAG
V.SO / SO	SOFT / \
M.ST	M. STIFF
ST / V.ST	STIFF / \
HD	HARD
V.LO / LO	VERY LO
M.DE	MEDIUM
DE / V.DE	DENSE /
ORG	ORGAN



	3AP-0902			
75	а Ба			675
70	EOP CD-PZ-F (EOP)			670
65 ASH POND	FILL: V.ST - HD SILTY CLAY	-0803		665
	4/8/09 ▽ 4/10/09 ▼ FILL: M.DE F-C GRAVEL			660
55		CD-BA		655
<u>i0</u>		8		650
5	FILL: SO - M.ST SILTY CLAY	FILL	V.ST-HD SILTY CLAY VOHIO RIVER	645
10			-	640
5	VSO - SO ORG CLAYEY SILT	4/8/09 ▽ SILT	/ SAND	635
0		V.SC	ORG CLAYEY SILT	630
5	V.LO - LO F-M SAND		SILTY CLAY INTERBEDDED WITH SILT	625
20		M.DI	E F-C SAND	620
5	M.DE F-M SAND			615
10				610
5				605
00				600



		ECPP ECPP			
675					675
670					670
665	ASH POND	FILL: M.DE F-C GRAVEL			665
660		FILL: V.ST SILTY CLAY			660
655		4/8/09 ▽			655
650				-	650
645		+		FILL: V.ST - HD SILTY CLAY OHIO RIVER	२ 645
640		V.LO - LO SILT	-	- · · · · · · · · · · · · · · · · · · ·	640
635		+			635
630		V.SO - M.ST ORG CLAYEY SILT		V.SO - SO ORG CLAYEY SILT	630
625		-		-	625
620				M.DE F-C SAND AND GRAVEL	620
615		M.DE F-C SAND AND GRAVEL		_	615
610					610
605					605
600					600
0+00		1+00		24	+00

# LEGEND

- **OBSERVATION WELL READING: ELEVATION AND DATE**
- SEEPAGE ENCOUNTERED DURING DRILLING
- SOFT / VERY SOFT
- M. STIFF
- STIFF / VERY STIFF
- VERY LOOSE / LOOSE
- MEDIUM DENSE
- DENSE / VERY DENSE
- ORGANIC

PROJECT NUMBER:	011-11497-013	DRAWN BY:	RSH
DRAWING DATE:	7-1-09	ENGINEER:	MTR
LAST UPDATED:	7-23-09	APPROVED BY:	MGR
		SCALE:	1" = 20'

	N				0			
								1
								2
								3
								4
								5
								6
								7
		ELEC UPON O OR COP NISHIN WRITI FOR AN	TRIC F Conditi Pied, i Ng info Ten cons Ny purp	OWER S ON THAT N WHOLE RMATION SENT OF OSE DETF	SERVICE IT IS N OR IN P TO ANY THEAEP RIMENTAL		D IS LOANE EPRODUCED ED FOR FUR HOUT THE CORP.,OR	
			ILLI	DIN ant otto inve	M AS	PLAN ohi h pone gation	0	
	 BBCM	DWG. scale: dr: ch: engr: proj engr:	NO. F		E 3	ENGINEERING		9
)'	Solutions To Build On Columbus (614) 793-2226 Cleveland (216) 901-1000 Cincinnati (513) 771-8471 Dayton (937) 424-1011	DATE:	AME ELECT POK/E	RICAN	IR	° SERVICI IVERSIDE JMBUS, OI	PLAZA	

I U SYSTEM DATE- DD-MMM-YYYY SYSTEM TIME- HOUR:MINUTE

 $\mathbb{N}$ 

## EXPLANATION OF SYMBOLS AND TERMS USED ON BORING LOGS FOR SAMPLING AND DESCRIPTION OF SOIL

## SAMPLING DATA



- Blocked-in "SAMPLES" column indicates sample was attempted and recovered within this depth interval.

- Sample was attempted within this interval but not recovered.
- 2/5/9 The number of blows required for each 6-inch increment of penetration of a "Standard" 2-inch O.D. split-barrel sampler, driven a distance of 18 inches by a 140-pound hammer freely falling 30 inches. Addition of one of the following symbols indicates the use of a split-barrel other than the 2" O.D. sampler:

2S -3S -

- 2¹/₂"O.D. split-barrel sampler

- 3" O.D. split-barrel sampler

- P Shelby tube sampler, 3" O.D., hydraulically pushed.
- R Refusal of sampler in very-hard or dense soil, or on a resistant surface.
- 50-2" Number of blows (50) to drive a split-barrel sampler a certain number of inches (2), other than the normal 6-inch increment.
- S/D Split-barrel sampler (S) advanced by weight of drill rods (D),
- S/H Split-barrel sampler (S) advanced by combined weight of rods and drive hammer (H).

## SOIL DESCRIPTIONS

All soils have been classified basically in accordance with the Unified Soil Classification System, but this system has been augmented by the use of special adjectives to designate the approximate percentages of minor components as follows:

<u>Adjective</u>	Percent by Weight
trace	1 to 10
little	11 to 20
some	21 to 35
"and"	36 to 50

The following terms are used to describe density and consistency of soils:

<u>Term (Granular Soils)</u>	Blows per foot
Very-loose	Less than 5
Loose	5 to 10
Medium-dense	11 to 30
Dense	31 to 50
Very-dense	Over 50
Term (Cohesive Soils)	<u>Qu (tsf)</u>
Very-soft	Less than 0.25
Soft	0.25 to 0.5
Medium-stiff	0.5 to 1.0
Stiff	1.0 to 2.0
Very-stiff	2.0 to 4.0
Hard	Over 4.0


# LOG OF BORING NO. CD-BAP-0901 CARDINAL PLANT ASH POND INVESTIGATION

Pag	e 1 c	of 3			CA		OG OF BORING NO. CD-BAP-0901 NAL PLANT ASH POND INVESTIGATION BRILLIANT, OHIO				BE	BC	$\mathbb{R}$
							endix A ELEVATION: 668		DAT		4/8/09		
DRIL	LINC	METH	HOD				). Hollow-stem Auger		COMPL	ETION	DEPTH:	6	0.0'
SAM	PLER	· · -			2'' O		Split-barrel Sampler 3" O.D. Shelby Tube Sample	er					
ELEV.	DEPTH, FEET	SAMPLE NUMBER	SAMPLE SAMPLE	EFFORT	$N_{60}$	SAMPLE REC-%	DESCRIPTION				ENCY IND STURE CO		TEST RESULT
	- 0 -	<u>S</u> Z	δ J	ы		$_{\rm R}^{\rm S/}$	GRAVEL FILL - 0.9 FEET		astic 10	<u>LIMIT ∠</u> 20		<u>LIMIT</u>	-
667.8										20	50 -		-
666.2		1	8	/13/ 8	30	80	FILL: Hard gray and brown silty clay, some fine to coarse sand, some fine to coarse gravel (sandstone, siltstone, and shale fragments), dry.						H=4.5+
000.2		2	6	′4,	16	67	FILL: Medium-dense to dense brown and gray fine to coarse gravel (sandstone, siltstone, and						H=2.5-3.1
		_	10	[′] 7			shale fragments), some fine to coarse sand, "and" silty clay, dry.						_
	- 5 -	3	12	/12/30	60	100	sinty clay, dry.		•				H=2.5
		-	13										_
661.7		4		^{/22} /20	60	80							H=4.5+
660.2		5	5	/10 _{/16}	37	93	FILL: Hard gray clayey silt, some fine to coarse sand, some fine to coarse gravel (sandstone, siltstone and shale fragments), dry.		•	<	<		H=4.5+
000.2		6	6	8/16	34	87	FILL: Very-stiff brown and gray silty clay, some fine to coarse sand, some fine to coarse gravel						H=3.0-4.0
658.7	- 10-	-	24	/16	-	100	(sandstone, siltstone, and shale fragments), dry. FILL: Medium-dense to dense gray and brown						-
		7	10	25 _{/24}	70	100	fine to coarse gravel (sandstone, siltstone, and shale fragments), some fine to coarse sand, some silty clay becoming "and" clayey silt with depth,						H=4.5+
1		8	10	7 ₇ 777	20	67	dry.						-
		⊻9	8	6/14	29	73			• ×	×			H=4.5+
654.2	- 15-	-10	5	[/] 8 _{/14}	32	80	FILL: Very-stiff to hard brown and gray silty clay, some fine to coarse sand, some fine to coarse gravel (sandstone, siltstone, and shale						H=4.0- 4.5+
		- 11	3	¹ 5 ₁ 9	20	67	fragments), medium-dense gray and brown fine to coarse gravel (shale fragments) seam from 17.5' to 18.3', moist to wet.						H=3.8-
		_	3	,			17.5 to 10.5, moist to wet.						4.5+
		12	ĺ	⁵ /10	22	53			•	×	×		G
610 2	- 20-	13	3	′9 _{/9}	26	53							H=4.5
648.2		- 14	7	·9,	32	67	FILL: Medium-dense gray fine to coarse gravel (shale fragments), little fine to coarse sand, little						H=4.5
646.7		-	6	/13 /9	~-		silty clay, moist to wet. Medium-dense gray silt, trace clay, trace fine to						-
		15 -	Ē	⁹ /10	27	80	medium sand, moist to wet.				•		G
643.7	- 25-	16A											-
WATE	ERLE	·	Ā	13.		_ 1	G-Gradation See H-Penetrome		ef)		Energy I		
WAT	D	ATE:		nside 4/9/			Q - Uncon Comp T - Triax Comp C - Consol. -CONTINUED-	Wt (pc	f)		l Rig Nu		02/17/09 TRUCK 5

Page	2	of	3
------	---	----	---

# LOG OF BORING NO. CD-BAP-0901 CARDINAL PLANT ASH POND INVESTIGATION BRU LIANT OHIO

Page	2 of	3			CA		OG OF BORING NO. CD-BAP-0901 NAL PLANT ASH POND INVESTIGATION BRILLIANT, OHIO				BE	BC	X
LOCAT	TION	: Se	e F	Plate	2 of	Арре	endix A ELEVATION: 668	8.7	DA	TE:	4/8/09	- 4/9	/09
DRILL	ING	METH	HOE				). Hollow-stem Auger		COMP	LETION D	DEPTH:	6	).0'
SAMPI		-			2'' C		plit-barrel Sampler 3'' O.D. Shelby Tube Sampl						
ELEV.	HLAELEL	SAMPLE NUMBER	SAMPLE SAMPLE	EFFORT	N ₆₀	SAMPLE REC-%	DESCRIPTION	×		CONSISTE URAL MOIS		NTENT	TEST RESULTS
	25	16B_				•	Very-stiff brown mottled with gray silty clay,		10			0	
638.7		17	3	[/] 6 _{/9}	22	67	trace fine sand, damp.						H=2.5-3.5
													_
638.7		18	3	[/] 3 _{/4}	10	100				× •	×		H=1.6-2.5
	30-		Р				Gray mottled with dark-gray and brown clayey silt, some fine sand, trace medium to coarse sand, few seams and lenses of silty clay and fine sand,						-
635.9		19	-				damp.			*	•×		H=1.0-1.5 G
			1	/		-	Very-loose dark-brown and gray organic silt, some fine sand, moist to wet.						_
633.2	35-	20		² /2/2	6	100				×-	- ×	•	H=0.7 G
		21	2	[/] 2 _{/2}	6	100	Soft to medium-stiff gray mottled with dark-gray organic clayey silt, little to some fine sand, trace medium to coarse sand, few lenses of fine sand interbedded with organic silt near top of stratum, moist to wet.		-         -         -           -         -         -         -           -         -         -         -           -         -         -         -           -         -         -         -           -         -         -         -           -         -         -         -           -         -         -         -           -         -         -         -           -         -         -         -           -         -         -         -           -         -         -         -           -         -         -         -           -         -         -         -           -         -         -         -           -         -         -         -           -         -         -         -           -         -         -         -           -         -         -         -           -         -         -         -           -         -         -         -           -         -         -	>		•	H=0.4 G
		22	2	[/] 3 _{/3}	0	100							H=0.5-0.8
	40-	22		3/3	9	100				×			
		23	2	¹ 2 ₁ 3	7	67							H=0.3-0.7
625.7				5		-	Medium-dense to dense brown and gray fine to						_
	45-	24	9	/11 _{/13}	34	53	coarse gravel, some fine to coarse sand, trace silt, wet.						_
			9	/10									-
		25		[/] 12 _/ 16	40	53							-
		26	11	19,	56	53							-
	50⊥	101		['] 20			SYMBOLS USED TO INDICATE TEST RES	SULTS	<u> </u>	Drill Rod I	Therew T	Patia ·	0.86
WATER WATE	ER NO		<u>*</u> 	13. Inside 4/9/	HSA		G - Gradation See H - Penetrom Q - Uncon Comp Separate W - Unit Dry T - Triax Comp Curves D - Relative	y Wt (p	tsf) cf)	Last Cali	bration	Date :	





# LOG OF BORING NO. CD-PZ-BAP-0902 CARDINAL PLANT ASH POND INVESTIGATION BRILLIANT, OHIO

Pag	e 1 o	f 3		CA		G OF BORING NO. CD-PZ-BAP-0902 NAL PLANT ASH POND INVESTIGATION BRILLIANT, OHIO				BE	BC	X	
LOCA	ATIO	N: <u>Se</u>	e Plate				s.0	DATE	:	4/3	8/09		
DRIL	LING	METH				). Hollow-stem Auger	C	OMPLE	TION E	DEPTH:	6	0.5'	
SAM		· · -		2'' C		plit-barrel Sampler							
ELEV.	DEPTH, FEET	SAMPLE NUMBER	SAMPLE SAMPLE EFFORT	N 60	SAMPLE REC-%	DESCRIPTION	-NATUR#	URAL CONSISTENCY INDEX -NATURAL MOISTURE CONTENT					
	- 0 -					GRAVEL FILL - 1.0 FEET				30 4		_	
667.0		1	⁵ / _{5/7}	17	87	FILL: Very-stiff to hard brown silty clay, some fine to coarse sand, some fine to coarse gravel (sandstone, siltstone, and shale fragments), dry.						H=3.5-4.0	
		2	6 ⁶ /6 _{/8}	20	80	FILL: Medium-dense brown and gray fine to coarse gravel (sandstone, siltstone, and shale fragments), some fine to coarse sand, some silty clay, cobbles near top of stratum, dry.						H=3.75- 4.25	
	- 5 -	3	⁶ /9/10	27	73	ciay, coooles hear top of stratum, dry.						H=4.0- 4.5+	
		4	⁸ / ₅ / ₇	17	73			• *	×			H=3.0- 4.25	
		5 ⊈	⁹ / _{9/} 7	23	53							H=3.5-4.0	
	- 10-	6	¹² / ₆ / ₅	16	27							H=3.75- 4.0	
		<u>₹</u> 7	¹⁰ / ₉ / ₁₁	29	60				•			H=4.0- 4.5+	
655.0		8	³ / ₅ / ₇	17	73			• ×	×			H=3.0- 3.75 G	
		9	$\frac{3}{3}$	10	33	FILL: Very-stiff to hard brown and gray silty clay, some fine to coarse sand, trace to some fine gravel (siltstone and shale fragments), damp to wet.						H=3.75- 4.5+	
652.0	- 15-	10	² / ₂ / ₃	7	40							H=2.5- 2.75	
		11	³ /4/5	13	67	FILL: Soft to medium-stiff brown and gray silty clay, some fine to coarse sand, trace to some fine gravel (siltstone and shale fragments), brown and gray fine to coarse grayal some mean middle of		×	•	×		H=1.0-2.0 H=1.5-	
		12	¹ / ₂ / ₂	6	40	gray fine to coarse gravel, some near middle of stratum, wet.		×-	•	- X		- 2.25 - G - H=0.0-	
647.5	- 20-	13	¹ / _{SH}	1	20			×-	, , , , , , , , , , , , , , , , , , ,			- 0.25 - G	
		14	² / _{2/1}	4	100	Very-loose gray and dark-gray silt, little to some clay, trace becoming some with depth fine sand, wet.			•			G	
		15	2/1/1/1	3	53							G	
643.0	-25-	16	SH SH_1	1	53	SYMBOLS USED TO INDICATE TEST RESU	JLTS						
WATE WAT	ER N		⊻ 10. Inside 4/8/	HSA		8.4     G - Gradation     See     H - Penetrome       Inside Well     Q - Uncon Comp     Separate     W - Unit Dry       4/10/09     C - Consol.     Curves     D - Relative	eter (ta Wt (pc:	f) L	ast Cali		Date :	0.86 02/17/09 TRUCK 55	

Page 2 of 3

## LOG OF BORING NO. CD-PZ-BAP-0902 CARDINAL PLANT ASH POND INVESTIGATION BRILLIANT, OHIO





Page	1	of	2
------	---	----	---

# LOG OF BORING NO. CD-BAP-0903 CARDINAL PLANT ASH POND INVESTIGATION BRILLIANT, OHIO

Page	e 1 of	2		CA		OG OF BORING NO. CD-BAP-0903 NAL PLANT ASH POND INVESTIGATION BRILLIANT, OHIO					<b>3</b> F	<b>3C</b>	R
LOCA	TION	Se	e Plat	e 2 of	f Ann	endix A ELEVATION: 650	).1	DA	TE:			/8/09	
	LING N	-				D. Hollow-stem Auger				ON D	EPTH:		0.0'
SAMP	PLER(S	): _		2" (	0. <b>D</b> . §	Split-barrel Sampler 3'' O.D. Shelby Tube Sampl	er						
ELEV.	HLL       H												TEST RESULT
649.7	- 0					TOPSOIL - 0.4 FEET	-	10	20			40	_
-		1	² / ₅ /	6 15	67	FILL: Very-stiff to hard brown mottled with gray and dark-brown silty clay, trace fine to medium sand, few roots, damp.							H=3.6-3.8
646.1		2	⁴ / ₆ /	6 16	53					•		<u> </u>	<h=3.3-4.5 G</h=3.3-4.5 
-	- 5 -	3	2 [/] 5/	6 15	80	FILL: Very-stiff to hard brown mottled with gray silty clay, trace fine sand, damp.				<u> </u>			H=2.6-4.1
		4	⁸ /11/1	3 33	80								H=4.5
643.1		5	6 _/ 6 _/	6	67	FILL: Very-stiff to hard brown mottled with dark-gray and gray silty clay, little fine to coarse sand, trace fine gravel, few lenses of dark-gray silt, damp.							H=3.5-4.5
-	- 10-	6	⁵ / ₆ /	6	67	Medium-stiff dark-gray organic clayey silt, trace fine sand, many lenses of fine sand, few decayed roots, damp to moist.					×	×	• H=0.6 G
_			P										_
636.6			sн			Very-soft gray mottled with dark-gray organic							_
-	- 15-	7	1/	1 3	67	clayey silt interbedded with organic silt, little fine sand, few seams and lenses of silt and fine sand, moist to wet.							
-	 	8	sң ₁/	1 3	67					×	×	•	H=0.0 G
		9	sң 1 _/	3	73					×	X	•	H=0.0 G
629.6	- 20-	10	¹ / _{2/}	8	60	Very-soft gray silty clay interbedded with silt, trace fine sand, few seams of fine sand, few roots, moist to wet.							 H=0.2
627.6		11	2 / 4 /	4	47	Medium-dense brown and gray fine to coarse sand, trace medium to coarse sand, trace fine to coarse gravel, little silt, few seams of silty clay,							
$\vdash$		11	*/	7 15	47	wet.							G
WATE	- 25-⊥ R LEV ER NO' DA'	TE:	Insid	6.5 e HSA 8/09	<u>_</u>	SYMBOLS USED TO INDICATE TEST RESI       G - Gradation     See       Q - Uncon Comp     Separate       T - Triax Comp     Curves       C - Consol.     D - Relative	eter (t Wt (pc	f)	Las	t Calil	oration	Ratio : Date : mber :	11/19/07


Pag	ge 2 c	of 2			CA		OG OF BORING NO. CD-B NAL PLANT ASH POND IN BRILLIANT, OHIO					BE	BC	$\mathbb{R}$
LOC	ATIO	N: <b>S</b>	ee 🛛	Plate	2 of	Арр	endix A	ELEVATION: 65	0.1	DATE	:	4	 /8/09	
		6 MET		D:	3-1/4	4" I.I	). Hollow-stem Auger			COMPLE	TION	DEPTH:	3	0.0'
SAM	PLER				2'' C	).D. S	plit-barrel Sampler 3" O.D.	Shelby Tube Samp						
ELEV.	, HTTA -52- FEET	SAMPLE NUMBER	SAMPLE	SAMPLE EFFORT	N 60	SAMPLE REC-%	DESCRIPTI	ON	NA ×			ENCY INI STURE CC		TEST RESULT
624.6	-25-	NI NI	Š	S Ш		N N				ASTIC L	<u>іміт </u> 20		0 LIMIT 40	
620.1		12	6	⁰ /10/12	30	33	Medium-dense brown and gra gravel, some fine to coarse sa	y fine to coarse nd, trace silt, wet.						
620.1	- 30-	13	7	′′7 _{/7}	19	47								
							<ul> <li>Seepage encountered at 13.5</li> <li>Groundwater encountered at</li> <li>At 26.0', 1.8' heave, shook a</li> </ul>	22.5'.						
	- 35-						<ul> <li>Borehole grouted upon com</li> <li>Boring location and elevation</li> </ul>	bletion. n surveyed by AEP.						
4														
														_
	- 40-													-
														_
	- 45-													
WATI	- 50- ER LE	EVEL:		16.			G - Gradation	TO INDICATE TEST RES See H - Penetron		of)		Energy 1		
WAT	ER N	OTE: ATE:		Inside 4/8/			O Ungon Comp	Curves D - Relative	y Wt (po	ef) L		libration l Rig Nu		<u>11/19/07</u> D50


# LOG OF BORING NO. CD-PZ-BAP-0904 CARDINAL PLANT ASH POND INVESTIGATION BRILLIANT, OHIO

Page	e 1 o	f 3		CA		G OF BORING NO. CD-PZ NAL PLANT ASH POND IN BRILLIANT, OHIO					<b>3</b> [	BC	$\mathbf{N}$
LOCA	ATIO	N: Se	e Plat			endix A	ELEVATION: 668	8.1	DATE	8:	4,	/7/09	
DRILLING METHOD:       4-1/4" I.D. Hollow-stem Auger       COMPLETION DEPTH:       60.0"         Complexity       2" O.D. Split housed Security 2" O.D. Shellow Type Security       Complexity       60.0"													
SAMPLER(S):       2" O.D. Split-barrel Sampler 3" O.D. Shelby Tube Sampler         NATURAL CONSISTENCY INDEX       NATURAL CONSISTENCY INDEX													
ELEV.	PTH,	SAMPLE NUMBER	SAMPLE SAMPLE EFFORT		SAMPLE REC-%	DESCRIPT		NA			TURE CO		TEST
EL	, DEPTH, FEET	NUN	SAN EFF	$N_{60}$	SAM	DESCRIPT	ION		ASTIC I			LIMIT	RESULTS
	- 0 -					GRAVEL FILL -	1.0 FEET					40	
667.1			6			FILL: Very-stiff to hard bro	wn and grav silty						-
-		1	°′6,	20	100	clay, some fine to coarse san	d, some fine to						H=4.25-
-		_	-	8		coarse gravel (sandstone, silt fragments), fine to coarse gra							4.5+
_		2	°/ ₈ ,	27	53	middle of stratum, dry.	iver seams near						H=4.5+
			1	1									
-		3	⁹ / ₁₁ ,	33	93				•				H=3.5-4.0
-	- 5 -	3	1		95								-
		-	12										
-		4	'15 _{/1}	7 46	7								-
-		-	12										-
		5	′ 8 _/	8 23	13								_
-		-	2	8									H=2.75-
-		6	⁻ /8/.	36	80				• • ×				3.5
658.1	- 10-	_	′1	7			1						G
656.6		7	20 50-3"H	R	33	FILL: Very-dense brown an gravel (sandstone, siltstone, a little fine sand, trace silt, dry	and shale fragments),						-
655.9		8A	13	44		FILL: Dense brown and gray	y fine to coarse						
		8B	14/1	7		gravel (sandstone fragments) to medium sand, trace coarse	sand, trace silt, dry,	Γ					H=4.5+
-		-	3			FILL: Hard brown with gray	silty clay, little to						
-		9	′ 5 _/	9 20	73	some fine to coarse sand, trac	ce fine gravel, dry.		•	×			H=2.5-40
-	- 15-	-	5,										-
	- 15-	10	6/	7 19	80								H=3.0-
652.1		⊻ _	4	<i>'</i>		FILL: Medium-dense brown	and gray fine to						4.25
-		11	6	26	60	coarse gravel (very-soft shale	e fragments), some						
-		_	1 -			fine to coarse sand, some silt damp.	y clay, cobbles,						G
-		12A	⁴ / ₆	20		aump.							-
649.1		12B_	/	8									
-		13	² / ₂ /	6	87	Loose gray and dark-gray or little to some fine to medium	ganic silt, little clay,						-
-	-20-	15	-/	2	07	intre to some fine to medium	sand, wet.						G
			² / ₃ /										
646.1		14	3/	4 10	47								-
0.0.1		-	sн			Very-loose gray and dark-gra							
644.5		15	′ ¹ /	2 4	47	sand, trace coarse sand, little organic silt, wet.	fine gravel, some			•			G
644.6		-	SӉ			Very-loose gray silt, little cla	y, little fine sand.						-
		16	SH	0	53	wet.	,,						
	-25-		ŚI			SYMBOLS USE	O TO INDICATE TEST RES	ULTS	<u> </u>		<b>_</b>	D-4	0.96
WATE WAT		-		<u>6.0</u> e HSA		- 15.9 G - Gradation Q - Uncon Comp	See H - Penetrom Separate W - Unit Dry	neter (t	sf) 🛛 🕇		Energy l ibration		<u>0.86</u> 02/17/09
		ATE: -		7/09		4/10/09 T - Triax Comp C - Consol.	Curves D - Relative					_	TRUCK 5


# LOG OF BORING NO. CD-PZ-BAP-0904 CARDINAL PLANT ASH POND INVESTIGATION BRU LIANT OHIO

Pa	Page 2 of 3LOG OF BORING NO. CD-PZ-BAP-0904 CARDINAL PLANT ASH POND INVESTIGATION BRILLIANT, OHIOBRICK														X	
LO	CATIO	N: <b>S</b>	ee Plat	te 2 of	Арр	endix A		ELEVA	TION: 668.1		DATE	:		4/	7/09	
DR	ILLING	B MET	HOD:	4-1/	4'' I.I	<b>). Hollow-stem</b>	Auger			C	OMPLE	ETION	DEI	PTH:	6	0.0'
SAMPLER(S):       2" O.D. Split-barrel Sampler 3" O.D. Shelby Tube Sampler         NATURAL CONSISTENCY INDEX       NATURAL CONSISTENCY INDEX																
Ň.	TH,	'LE 3ER	LE LE		SAMPLE REC-%					NAT	URAL C NATUR					TEST
ELEV.	FEE	SAMPLE NUMBER	SAMPLE SAMPLE FFEOPT	N60	AMI		DESCRIPTI	ON		$\nearrow$	`•		—×	<		RESULTS
	$\begin{array}{c c c c c c c c c c c c c c c c c c c $													IQUID 4		_
/4/09		17	'sң	4	53	wet.		, 11000	lie build,			20	30		-	
∞ 641.6	5			3												G
2008 NEW DEFAULT BORING LOG-W/ N60 111497013.GPJ BBCM.GDT 84.09 [1.8829]		18	SH ₁	6	100	organic clayey	to stiff gray mot silt, interbedde arse sand, trace	ed with o	rganic silt,			×				H=0.75- F.25
- 040.1		_	1			Very-soft to so	oft gray mottled	with dar	k-gray							
97013		19	′ 1 _/	3 6	87	organic clayey	silt, trace fine	sand, we	t.				×		$\times \bullet$	H=0.0-0.5
638.1	_			5											<u> </u>	-
09X	+ 30-					Loose to medi	um-dense brow	n and gra	ay fine to							-
06-W						medium sand,	trace coarse san	nd, trace	to some							
<u>e</u> ro			Р				s of gray mottle bottom of strat									_
OKIN						interbedded wi	ith silt, wet.									-
LTB																
SFAU			-													
A DE		20A	⁵ / ₅ /	17												-
8 NE		20B	5/	7												-
200	- 35-															
		21	² / ₃ /	11	93											-
		21	5/	5	95											G
																_
		22	² / ₂ /	10	100											-
		22	-/	5	100											-
	- 40-															
		23	² / ₂ /	10	100											-
		23	-/	5	100											-
			2													-
		24	² /8,	29	100											-
	15		/1	12	100											
	- 45-															
			1													_
621.4	1	25A	⁴ / ₁₁	40			1 .	~								-
		25B		17		Medium-dense	e brown and gra Fine to coarse sa	ly tine to	coarse							-
						Staver, and I		ina, trace	5111, WOL							
610 1	.		12													-
619.1		26	¹² / ₂₉		93	See description	n on the followi	ng nage								-
	- 50-		50-5'	'R												
WAT	- 50- FER LE	EVEL:	<u> </u>	16.0	¥	10.0	SYMBOLS USED G - Gradation	TO INDIC	ATE TEST RESULT H - Penetromete		(f)			ergy R		
	TER N	OTE:	Insie	ie HSA 7/09		Inside Well 4/10/09	T - Triax Comp	Separate Curves	W - Unit Dry Wt D - Relative De	(pcf	) L					02/17/09 TRUCK 55
		ATE:		11.37			C - Consol.	CULVES	2 RELACIVE DE	(2)	1	DEI	u Kl			TRUCK 55
JOR:	v11-1	1497-0	13			-CON	TINUED-							rL/	ATE 1	4






JOB: 011-11497-013




## LOG OF BORING NO. CD-BAP-0906 CARDINAL PLANT ASH POND INVESTIGATION BRILLIANT, OHIO



JOB: 011-11497-013

-CONTINUED-


PLATE 18



JOB: 011-11497-013


-CONTINUED-


PLATE 19








## LOG OF BORING NO. CD-BAP-0907 CARDINAL PLANT ASH POND INVESTIGATION BRILLIANT, OHIO












## Appendix II – 2009 & 2015 Laboratory Testing Results


BORING G'int MC Id.																						-
G'int Id.				GRA	GRADATION	COMP	PACTION	TRIAXIAL	VIAL	DIRE	DIRECT SHEAR	⊃z		DZ UZ		PER	PERMEABILITY	ATLI		Г		-v
G'int Id.			<u> </u>		Hydrometer		Еo	n n o n n n n		чч					-0Z0 =0Z			l a w	-vZv JACF			- e 7 o
	TT	PL	Id	sv o > ¢	shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohs shohsh	מ בים מ איז	ರು – ( ರಿ.	р 1-10 1-10 1-10 1-10 1-10 1 1 1 1 1 1 1	מי– מסים מי– מסים	ø ದ ೧.೧	-ש ב סיד יא ש ד יש ד כ	ドーZ ドーZ		-TX -TX		4 0 0 - > (	poc∕n	-10×e			n≻ ⊢⊃m ∪omm	, – ಇರ ಅ
%	%	%	%	<b>,</b>	*			TEST	^s     CURVES	SE	-			PCF	L.		o o	ט	%	%	ш	x
CD-BAP-1501 4.75				*																		
CD-BAP-1501 9.25				*																		
CD-BAP-1501 12.25 13.9	22	14	~																			
CD-BAP-1502 6.25 9.1	27	16	11	*	*																	
CD-BAP-1502 11.25 8.9	21	14	٢																			
CD-BAP-1502 17.75 12.7	26	16	10	*	*																	
CD-BAP-1502 20.00																					*	
CD-BAP-1502 24.25 22.4																						
CD-BAP-1502 32.50																					*	
CD-BAP-1502 40.75				*																		
CD-BAP-1504 6.25 9.4																						
CD-BAP-1504 10.75				*																		
CD-BAP-1504 12.25 11.6				*																		
CD-BAP-1504 17.25 18.2																						
CD-BAP-1505 9.25 11.6																						
CD-BAP-1505 10.40 19.0																						
CD-BAP-1505 13.75 10.4																						
CD-BAP-1505 15.25 18.3				*																		
S&ME		H	ESTIN	NG SU	TESTING SUMMARY - STANDARD	- STAN	DARD		PROJECT LOCATION JOB NO.	LON.	BOT 7217	BOTTOM ASH POND SUPPLEMENTAL INVESTIGATION CARDINAL PLANT, BRILLIANT, OH 7217-15-007A DATE 12/30/15	SH P 7ARD 7A	ASH POND SUPPLEMENTAL INVES CARDINAL PLANT, BRILLIANT, OH 07A DATE 12/30		PLEME NT, BF DATE		L INVE NT, O 12/3	NVESTIG/ T, OH 12/30/15	NOITION		

PLATE 1


								SUN	SUMMARY	RY OF		LABORATORY	TOR	ΥTE	TEST	RESULTS	ULT	S								
						9	GRADATION	NOL	COMP.	ACTION		TRIAXIAL		DIRECT SHEAR	IEAR	00	SP	βщ		ERME	PERMEABILITY	Ц				~-~
							Hyd	Hydrometer	t s	Eo	ם ם	m n		n a	чo	کط⊃		בט–י		цо	a ≲	a ≰	- 0 20-			- e'7 (
BORING	G'ınt Id.	MC	LL	ΡL	Id	$\infty - 0 > 0$	ч т о म v	- 0 H 20	מ בים מ רים	ט-נייי ה היש	о п - ∞ п - ∞ п - ∞ п - с с с с с с с с с с с с с с с с с с с	den - a b c c c c c c c c c c c c c c c c c c	a- = = 0 = =	ח-ימ-ם		KHHX SSER VHLC	-H-U		д ө «- > ө ДшД	с∕о0до	ہ – ص – ہے – – ا			しつれ日		) ー <del></del> つ ;
		%	%	%	%			* SE		15	AL TEST	- U	VES		1	-		PCF				%	%	<u></u>	니	×
MW-BAP-4	6.25	15.0	25	16	6	*		*																		
MW-BAP-4	9.25	24.3	43	21	22																					
MW-BAP-4	14.50																								*	
MW-BAP-4	32.25					*																				
MW-BAP-4	39.25					*																				
MW-BAP-5	4.75	12.8	30	17	13	*		*																		
MW-BAP-5	9.25	10.3	30	18	12																					
MW-BAP-5	11.00																								*	
MW-BAP-5	21.75	39.9	48	26	22	*		*															5.9	6		
MW-BAP-5	27.00																								*	
MW-BAP-5	29.00																								*	
MW-BAP-5	41.75	29.7																								
MW-BAP-5	51.75			_		*																				
MW-BAP-5	59.25					*																				
	SRMF	5			TEST	5 DNG	SUMM	TESTING SUMMARY - STANDARD	STAN	DARD		PROJECT LOCATION	PROJECT LOCATION			BOTTOM ASH POND SUPPLEMENTAL INVESTIGATION CARDINAL PLANT, BRILLIANT, OH	A PON	AL PL	PPLE ANT,	BRIL	ASH POND SUPPLEMENTAL INVES CARDINAL PLANT, BRILLIANT, OH	IVEST	IGAT	NO		
	3						1		1			JOB NO.	NO	2	217-1	7217-15-007A			DATE	Ë		12/30/15	5			





ALPI-REG





ALPI-REG

































































<b>S&amp;ME</b>		Sample :	Recovery :		eter (tsf) SL - Shrinkage Limit POR - Porosity UDW - Unit Dry Weight MC - Moisture Content er D _R - Relative Density S - Sieve
	S	Boring :	Depth:		H - Hand Penetrometer (tsf) Ds - Direct Shear LOI - Loss on Ignition - Triaxial AL - Atterberg Limits Compression MA - Sieve/Hydrometer Test SG - Specific Gravity
7217-15-007A BOTTOM ASH POND SUPPLEMENTAL INVESTIGATION CARDINAL PLANT, BRILLIANT, OH	LABORATORY LOG OF SHELBY TUBES	Boring : CD-BAP-1502 Sample : ST-2	Depth : 32.5' to 34.5' Recovery : 19.50"	0       - vold         - vold       - our         - our       disturbed - discarded         - our       Stiff to very-stiff brown mottled with gray silty clay, some to "and" fine to medium sand, trace coarse sand. H=2.05         II	- Unconfined Compression Test SG - Triaxial AL Compression MA Test SG
JOB NUMBER : 7217-15-007A PROJECT : BOTTOM ASH POND SUPPLEMI LOCATION : CARDINAL PLANT, BRILLIANT		Boring : CD-BAP-1502 Sample : ST-1	Depth : 20.0' to 22.0' Recovery : 7.00"	0       - VOID         12       - VOID         12       - OUT         disturbed - discarded         12       - OUT         disturbed - discarded         12       - OUT         vith brown silty clay, some fine to coarse gravel (shale sand, little sand, little fine to coarse gr	- Consolidation, Swelling, Incremental C R S - Consolidation, C R S - C - C - C - C - C - C - C - C - C -


**2009 SITE INVESTIGATION** 

60/9							S	SUM	MAR	Y OF	F LA	BO	RA ⁻	ΓOF	r y ı	ES	TR	ES	UL	TS									
-						GF	RADATI	ON	COMPA	ACTION	1	<b>RIAX</b>	[AL	DIRE	ECT SI	HEAR		C S	5 G	U W N E	R	PE	RME	ABII	LITY	R D E E	L	R	S C
BORING	G'int Id.	MC	LL	PL	ΡI	s i e v e	Hydro s h o r t	ometer l o n g	s t n d a r d	m o d f i e d	u u n n c d o r n a s i . n	c u w o n / n d p s r o o a p l i r i n e d s	r a i n e	d r a i n e d	u n d r a i n	r e s 1 d u al	C M O P N R F E	CONSOL FLOOR	G G R A V I T Y	U W I I T G H T R Y	REMOLDED	c o h e s i V e	0 1 n g / 1 c c h e	w a 1 1	f w l a e l x l i b l e	RENSITY E	O I		S C HE B BLB R Y T U BE
· 111		%	%	%	%			* SEI	e indi	VIDUA	AL TE	EST C	URV	ΈS						PCF			s			%	%		
BAP-0901	4.75	16																											
BAP-0901	7.75	16	28	18	10																								
BAP-0901	13.75	13	27	17	10																								
BAP-0901	18.25	14	37	24	13	*		*																					
BAP-0901	22.75	30	NP	NP	NP	*		*																					
BAP-0901	24.50																												*
BAP-0901	29.25	27	37	22	15	*		*																					
BAP-0901	31.25											*																	
BAP-0901	31.75	33	35	28	7	*		*				*																	*
BAP-0901	32.25											*																	
BAP-0901	34.25	42	34	27	7	*		*																					
BAP-0901	36.75	40	45	29	16	*																							
BAP-0901	39.25	42	40	23	17	*		*																					
BAP-0902	2 6.25	13	27	17	10	*		*																					
BAP-0902	2 10.75	20																											
BAP-0902	2 12.25	10	26	17	9	*		*																					
BAP-0902	2 16.75	24	37	19	18																								
BAP-0902	2 18.25	21	35	17	18	*		*																					
BAP-0902	2 19.75	31	29	17	12	*		*																					
BAP-0902	2 21.25	26	NP	NP	NP	*		*																					
			<b>A</b>		, ,	TEGT									PRO				CAF	RDINA	L PI		T ASH			VESTI	GATIO	N	
	DUS TO E		<b>О</b> м			TEST	ING S	UMM	ARY -	STAN	DAR	D			JOB			-114	97-	013						/6/09			_


60/9							S	SUM	MAR	Y OF	F LA	BO	RA	ΓOF	r y ı	ſES	TR	ES	UL	.TS										
10 1/6						GR	ADATI	ON	COMP	ACTION	1	FRIAXI	AL	DIRE	ECT SI	HEAR	U C N O	C	S G P R	U W N E	R	PE	RMI	EABI	LITY	R D E E	L	R	S H	С
BORING	G'int Id.	MC	LL	PL	PI	s i e V e	Hydro s h o r t	ometer l o n g	s t n d a r d	m o d f i e d	uu nn cd or nạ si . n	c u w o n / n d p s r o o a p l i r i n e d s	d r a i n e d	d r a i n e d	u n d r a i n	r e s i d u a l	NCOPRESS NCONFINS	CONSOL I	S GRA EC V I T F I Y C	U WE I G H T R Y	REMOLDED	c o h e s i V e	o h e	r w 1 a g l 1 l d	$ \begin{array}{c} f & W \\ l & a \\ e & l \\ x & l \\ i \\ b \\ l \\ e \end{array} $	RE DE LASITY E	O I		SHELBY TUBE	B R
		%	%	%	%			* SEI	e indi	VIDUA	AL TI	EST C	URV	ES						PCF			s			%	%			
a BAP-0902	2 22.75					*																								
BAP-0902	2 27.25	54	NP	NP	NP	*		*																			10.4			
BAP-0902	2 28.75	43	NP	NP	NP	*		*																						
BAP-0902	2 32.25	38	36	28	8	*		*																						
BAP-0902	2 37.25	22				*		*																						
BAP-0902	2 39.75	24				*		*																						
BAP-0902	2 42.25					*																								
BAP-0903	3 3.25	24	48	24	24	*		*																						
BAP-0903	3 4.75	22																												
BAP-0903	3 7.75	20	36	20	16	*		*																						
BAP-0903	3 9.25	49	41	38	3	*		*																						
BAP-0903	3 14.25	43	NP	NP	NP	*		*																						
BAP-0903	3 16.75	43	37	24	13	*		*																						
BAP-0903	3 19.25	44	35	24	11	*		*																						
BAP-0903	3 21.75	35	34	21	13	*		*																						
BAP-0903	3 24.25					*																								
BAP-0904	4.75	13																												
BAP-0904	9.25	14	25	16	9	*		*																						
BAP-0904	1 13.75	16	35	21	14																							$\square$	1	
BAP-0904	16.75					*																							1	
							·I									JECT			CAI	RDINA	L PL					VESTI	GATIO	N		_
	BC ONS TO E				,	TESTI	ING S	UMM	ARY -	STAN	DAR	D				ATIO NO.	N011	-114	497-	013					оніо 7	/6/09			_	_

							S	SUM	MAR	Y OF	= LA	BO	RA ⁻	TOR	<b>Y 1</b>	ΓES	TR	E	SUL	_TS	1									
Ĩ						GF	RADATI	ON	COMPA	ACTION	1	FRIAXI	AL	DIRE	CT S	HEAR		S	S G P R	U W N E	RE	PE	RM	EABI	LITY	R D E E	L	R	S H	С
BORING	G'int Id.	MC	LL	PL	PI	s i v e	Hydro s h o r t	l o n g	s t n d a r d	m od 1 f 1 e d	l n n	c u w o n / n d p s r o o a p l i r i n e d s	r	d r a i n e d	u n d r a i n	r e s 1 d u a l	C M O P N R E S N S	CONSOLID ·	S GRACVI F T Y C	U W N E I G H D T R Y	KE MOLDED	c o h e s i V e	h e	r W 1 a g l 1 l d	f w l a e l x l i b l e	R D E E A S T I V Y E	O I	R O C K C O R E	S H E B Y T U B E	B R
		%	%	%	%			* SEI	E INDI	VIDUA	AL TH	EST C	URV	ΈS						PCF			s			%	%	1		
BAP-0904	19.75	28	NP	NP	NP	*		*																						
BAP-0904	22.75	26	NP	NP	NP	*		*																						
BAP-0904	25.75	22	NP	NP	NP	*		*																						
BAP-0904	27.25	38	38	24	14	*		*																						
BAP-0904	28.75	47	42	30	12	*		*																						
BAP-0904	36.75					*																								
BAP-0905	5 4.75	17	32	18	14	*		*																						
BAP-0905	5 7.75	22	48	24	24																									
BAP-0905	5 9.85	33				*																								
BAP-0905	5 14.25	45	43	27	16	*		*																			8.4			
BAP-0905	5 16.75	42	40	25	15	*		*																						
BAP-0905	5 21.75	38	38	23	15	*		*																						
BAP-0905	5 26.75					*																								
BAP-0906	5 2.90	11																												
BAP-0906	6 4.75	15	27	17	10																									
BAP-0906	6 12.75					*		*																						
BAP-0906	5 17.25	14	31	19	12	*		*																						
BAP-0906	5 24.75	31	NP	NP	NP	*		*																						
BAP-0906	6 26.25					*																								
BAP-0906	5 27.25	22	NP	NP	NP	*		*																						
																JECT			CA	RDIN/	AL P					IVESTI	GATIC	N		
	BG DNS TO E		ЛЛ		,	TEST	ING S	UMM	ARY -	STAN	DAR	D				ATIO NO.	N011	-11	497	-013			ILLI DAT	ANT, E		/6/09			_	—


							S	SUM	MAR	Y OF	= LA	BO	RA	ΓOF	RY -	ΓES	TR	ES	SUL	TS										
						GR	RADATI	ON	COMPA	CTION	1	FRIAX	IAL	DIRI	ECT S	HEAR		S	S G P R	U W N E	R E	PE	RME	ABI	LITY	R D E E	L	R	S H	С
BORING	G'int Id.	MC	LL	PL	PI	s i e V e	Hydro s h o r t	l o n g	s t n d a r d	m od i f i e d	u u n n c d o r n a s i . n	c u w o n / n d p s r o o a p l i r i n e d s	r a i n e	d r a i n e d	u n d r a i n	r e s i d u a l	NC OP NR ES NS	CONSOLID ·	S GRAVI F I Y C	U W N E I G H D T R Y	RE MOL DE D	c o h e s i V e	h e	rw ia gl il d	f w l a e l x l b l e	R DE LA S T I T E	O I	ROCK CORE	SHELBY TUBE	B R
		%	%	%	%			* SEI	E INDI	VIDUA	AL TH	EST C	URV	ES						PCF			s			%	%			
BAP-0906	31.75	34	33	22	11	*		*																						
BAP-0906	34.25	43	50	30	20	*		*																			7.9			
BAP-0906	36.75	38	43	26	17	*		*																						
BAP-0906	44.25					*																								
BAP-0907	3.25	21																												
BAP-0907	6.25	15																												
BAP-0907	7.75	23	49	26	23																									
BAP-0907	9.25	28	47	29	18	*		*														*			*				*	
BAP-0907	11.75					*		*																						
BAP-0907	14.25	43	44	28	16	*		*																						
BAP-0907	16.75	44	45	29	16	*		*																						
BAP-0907	19.25	40	48	29	19	*																								
BAP-0907	21.75	39	30	24	6	*		*																						
BAP-0907	26.75					*																								
															PRO	JECT	-		CA				T ASI	H PO		IVESTI	GATIC	<u></u> N		
	BC INS TO E		<b>1</b> Ом		,	TEST	ING S	UMM	ARY -	STAN	DAR	D		1	LOC	ΑΤΙΟ		-11				BR	ILLIA DATE	NT, C	оню	/6/09				





ALPI-REG 111497013.GPJ BBCM.GDT 7/6/09





ALPI-REG 111497013.GPJ BBCM.GDT 7/6/09

















































































































































































### JOB NUMBER : 011-11497-013 PROJECT : CARDINAL PLANT ASH POND INVESTIGATION

LOCATION : BRILLIANT, OHIO





## JOB NUMBER : 011-11497-013 PROJECT : CARDINAL PLANT ASH POND INVESTIGATION

LOCATION : BRILLIANT, OHIO



#### LABORATORY LOG OF SHELBY TUBES Boring : CD-PZ-BAP-0906 Sample : 12A Boring : CD-PZ-BAP-0907 Sample : 6A Boring : Sample : Depth : 18.0' to 18.8' Recovery : 0.00" Depth : 8.5' to 9.9' Recovery : 15.00" Depth : Recovery : 0 0 0 Severly Damaged - Could Not Extrude VOID ..... disturbed - discarded 12 12 12 OUT FILL : Hard brown, gray and dark-gray silty clay inter-mixed with organic silt, SAVE Ι trace fine to coarse sand. H=4.5+ **II** 24 Р 24 24 Dark-gray organic silt, little fine to medium sand, few lenses of fine sand. Ш JAR H=2.2 _____ 36 36 36 NOTE: AL/MA on Section II 30.00" tube LEGEND H - Hand Penetrometer (tsf) SL - Shrinkage Limit Swelling, - Consolidation, Wax Ds - Direct Shear POR - Porosity Incremental Test LOI - Loss on Ignition UDW - Unit Dry Weight RS - Consolidation, CRS AL - Atterberg Limits MC - Moisture Content Unconfined - Triaxial

Compression

Test

MA - Sieve/Hydrometer

SG - Specific Gravity

 $D_R$ 

S

- Relative Density


- Sieve

Compression


Test

Permeability,

Vertical / Horizontal



Checked By: JJ




# PERMEABILITY TEST DATA AND COMPUTATION SHEET BBCK




((ASTM D-5084) FALLING HEAD, METHOD C)

Job Number:	011.11497.	015		Date:	5/6-7/200	09	Max	imum Dry Density:	
Project Name:	Cardinal A	sh Pond Inv	estigation	Boring:	CD-PZ-E	BAP-0907	Optimum		
Project Location:	Brilliant, O	hio		Sample:	ST-6A	Sec. II	_	% Compaction.:	
Tested By:	PJM			Depth:	8.5' to 9.	.9'	_	Optimum +/-:	
Remarks:							_	Natural:	Х
Material:	FILL : Hard	brown, gray	and dark-q	ray silty clay	inter-mix	ed with orga	nic silt, trace	Remolded:	
	fine to coars					-	-	-	
							F		
mple:			Tes	st Conditions:		<u> </u>	Noisture Content:	Before Test	After Test
Initial Length:	5.5945 in	= 14.210 cm	Ch	amber Pressure:	62 psi		Pan No. =	D	D
nal Ave. Length (L):	5.6042 in	= 14.235 cm		Back Pressure:	58 psi		Wet Wt. + Pan =	1144.17	1157.03
Diameter:	2.8765 in	= 7.31 cm	Co	nfining Pressure:	4 psi		Dry Wt. + Pan =	896.92	896.92
Area (A):	6.499 sq in	= 41.93 sq cm		Temp. @ Start:	22.5 °C		Wt. of Pan =	0.00	0.00
	36.356 cu in			Temp. @ End:	22.5 °C		Wt. of Dry Soil =	896.92	896.92
	1144.17 grams			Average Temp.:	22.5 °C		Wt. of Water =	247.25	260.11
Unit Wet Wt.:				B Parameter:	0.96		% Moisture =	27.57	200.11
Unit Dry Wt.:					0.00		/ Molature =	21.01	20.00
Unit Dry Wi	93.99 pci		0	oette Pressures Du				00.00	98.30
			<u> </u>				% SATURATION	93.80	
				Top Pipette:	60 psi	= 4220.3 cm	_S.G.(est) =	2.7000	
<u>ette:</u>				Bottom Pipette:	58 psi	= 4079.6 cm	_		
$=\frac{\mathbf{a}\cdot\mathbf{L}}{\mathbf{ln}}$	$\frac{h_1}{h_2}$	a L	= Length of Sar	-Sectional Area		$h_2$ = Head Loss A	(t ₂ - t ₁ ) cross Permeameter cross Permeameter ithm (Base e = 2.7	r/Specimen at t ₂	
$=\frac{\mathbf{a}\cdot\mathbf{L}}{\mathbf{ln}}$	<u> </u>	a L	= Pipette Cross = Length of Sar	-Sectional Area		$h_1$ = Head Loss Ad $h_2$ = Head Loss Ad	cross Permeameter	r/Specimen at t ₂	
$=$ $ \ln  $ $-$	<u> </u>	a L	= Pipette Cross = Length of Sar	-Sectional Area		$h_1$ = Head Loss Ad $h_2$ = Head Loss Ad	cross Permeameter cross Permeameter ithm (Base e = 2.7	r/Specimen at t ₂	Temp. Corr
$=\frac{\mathbf{a}\cdot\mathbf{L}}{\mathbf{ln}}$	<u> </u>	a L	= Pipette Cross = Length of Sar	-Sectional Area nple s-Sectional Area		$h_1 = Head Loss Au h_2 = Head Loss AuIn = Natural Logar$	cross Permeameter cross Permeameter ithm (Base e = 2.7	r/Specimen at t ₂	•
$=\frac{\mathbf{a}\cdot\mathbf{L}}{\mathbf{ln}}$	<u> </u>	a L A	= Pipette Cross = Length of Sar = Sample Cross	-Sectional Area nple s-Sectional Area Hydraulic Head		h ₁ = Head Loss Ar h ₂ = Head Loss Ar In = Natural Logar Hydraulic Head	cross Permeameter cross Permeameter ithm (Base e = 2.7	r/Specimen at t ₂	
$=\frac{\mathbf{a}\cdot\mathbf{L}}{\mathbf{ln}}$		a L A Time Interval	= Pipette Cross = Length of Sar = Sample Cross	-Sectional Area nple s-Sectional Area Hydraulic Head Headwater	Bottom	h ₁ = Head Loss Ar h ₂ = Head Loss Ar In = Natural Logar Hydraulic Head Tailwater	cross Permeameter cross Permeameter ithm (Base e = 2.7 Head Loss	r/Specimen at t ₂	Permeabilit
$=\frac{\mathbf{a}\cdot\mathbf{L}}{2\cdot\mathbf{A}\cdot\Delta\mathbf{t}}\ln\left(\frac{1}{2}\right)$	h2	a L A Time Interval Δt	= Pipette Cross = Length of Sar = Sample Cross Top Pipette	-Sectional Area nple s-Sectional Area Hydraulic Head Headwater H ₁	Bottom Pipette	h ₁ = Head Loss Ar h ₂ = Head Loss Ar In = Natural Logar Hydraulic Head Tailwater H ₂	tross Permeametel cross Permeametel ithm (Base e = 2.7 Head Loss h = H ₁ -H ₂	r/Specimen at t ₂ 1828)	Permeabilit k
$= \frac{\mathbf{a} \cdot \mathbf{L}}{2 \cdot \mathbf{A} \cdot \Delta t} \ln \left( \frac{1}{2} \right)$ Date	Time Readings	a L A Time Interval Δt Seconds	= Pipette Cross = Length of Sar = Sample Cross Top Pipette cc	-Sectional Area nple s-Sectional Area Hydraulic Head Headwater H ₁ cm	Bottom Pipette cc	h ₁ = Head Loss Ar h ₂ = Head Loss Ar In = Natural Logar Hydraulic Head Tailwater H ₂ cm	ross Permeameter cross Permeameter ithm (Base e = 2.7 Head Loss $h = H_1-H_2$ cm	r/Specimen at t ₂ 1828)	Permeabilit k cm/sec –
$= \frac{\mathbf{a} \cdot \mathbf{L}}{2 \cdot \mathbf{A} \cdot \Delta t} \ln \left( \frac{1}{2} \right)$ Date 5/6/2009	Time Readings 9:45 AM 10:51 AM	a L A Time Interval Δt Seconds 0.00	Top Pipette Cross	-Sectional Area nple s-Sectional Area Hydraulic Head Headwater H ₁ cm 4092.08	Bottom Pipette cc 14.20 14.45	h1 = Head Loss Ar         h2 = Head Loss Ar         h1 = Natural Logar         In = Natural Logar         Hydraulic Head         Tailwater         H2         cm         4272.01         4271.73	Head Loss $h = H_1-H_2$ cm -179.93	r/Specimen at t ₂ 1828) ڈn (h ₁ /h ₂₎ –	Permeabilit k cm/sec – 6.740E-08
$= \frac{\mathbf{a} \cdot \mathbf{L}}{2 \cdot \mathbf{A} \cdot \Delta t} \ln \left( \frac{1}{2} \right)$ Date 5/6/2009 5/6/2009 5/6/2009	Time Readings 9:45 AM 10:51 AM 12:15 PM	a L A Time Interval Δt Seconds 0.00 3,960 5,040	Top Pipette Cross = Length of Sar = Sample Cross Top Pipette cc 48.45 48.40 48.20	-Sectional Area nple -Sectional Area Hydraulic Head Headwater H ₁ cm 4092.08 4092.14 4092.36	Bottom Pipette cc 14.20 14.45 14.65	h1 = Head Loss Ar         h2 = Head Loss Ar         h1 = Natural Logar         Hydraulic Head         Tailwater         H2         cm         4271.73         4271.50	Head Loss h = H ₁ -H ₂ cm -179.93 -179.13	r/Specimen at t ₂ 1828) 	Permeabilit k cm/sec - 6.740E-08 7.077E-08
$= \frac{a \cdot L}{2 \cdot A \cdot \Delta t} \ln \left( \frac{1}{2} \right)$ Date 5/6/2009 5/6/2009 5/6/2009 5/6/2009	Time Readings 9:45 AM 10:51 AM 12:15 PM 1:45 PM	a L A Time Interval Δt Seconds 0.00 3,960 5,040 5,400	Top Pipette Cross = Length of Sar = Sample Cross Top Pipette cc 48.45 48.40 48.20 48.05	-Sectional Area nple s-Sectional Area Hydraulic Head Headwater H ₁ cm 4092.08 4092.14 4092.36 4092.54	Bottom Pipette cc 14.20 14.45 14.65 15.00	h1 = Head Loss Ar         h2 = Head Loss Ar         h1 = Natural Logar         In = Natural Logar         Hydraulic Head         Tailwater         H2         cm         4272.01         4271.73         4271.50         4271.09	Head Loss h = H ₁ -H ₂ cm -179.93 -179.13 -178.56	r/Specimen at t ₂ 1828)	Permeabilit k cm/sec - 6.740E-08 7.077E-08 8.280E-08
$= \frac{a \cdot L}{2 \cdot A \cdot \Delta t} \ln \left( \frac{1}{2} \right)$ Date 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/200 5/6/200 5/6/200 5/6/200 5/6/2009 5/6/2009	Time Readings 9:45 AM 10:51 AM 12:15 PM 1:45 PM 3:17 PM	a L A Time Interval Δt Seconds 0.00 3,960 5,040 5,520	= Pipette Cross = Length of Sar = Sample Cross Top Pipette cc 48.45 48.40 48.20 48.05 47.85	-Sectional Area nple -Sectional Area Hydraulic Head Headwater H ₁ cm 4092.08 4092.14 4092.36 4092.54 4092.77	Bottom Pipette cc 14.20 14.45 14.65 15.00 15.25	h1 = Head Loss Ar         h2 = Head Loss Ar         h2 = Head Loss Ar         h1 = Natural Logar         Hydraulic Head         Tailwater         H2         cm         4271.73         4271.50         4271.09         4270.81	Head Loss h = H ₁ -H ₂ cm -179.93 -179.59 -178.56 -178.04	r/Specimen at t ₂ 1828) ln (h ₁ /h ₂₎ - 0.00191 0.00256 0.00320 0.00289	Permeabilit k cm/sec 6.740E-08 7.077E-08 8.280E-08 7.312E-08
$= \frac{a \cdot L}{2 \cdot A \cdot \Delta t} \ln \left( \frac{1}{2} \right)$ Date 5/6/2009 5/6/2009 5/6/2009 5/6/2009	Time Readings 9:45 AM 10:51 AM 12:15 PM 1:45 PM	a L A Time Interval Δt Seconds 0.00 3,960 5,040 5,400	Top Pipette Cross = Length of Sar = Sample Cross Top Pipette cc 48.45 48.40 48.20 48.05	-Sectional Area nple s-Sectional Area Hydraulic Head Headwater H ₁ cm 4092.08 4092.14 4092.36 4092.54	Bottom Pipette cc 14.20 14.45 14.65 15.00	h1 = Head Loss Ar         h2 = Head Loss Ar         h1 = Natural Logar         In = Natural Logar         Hydraulic Head         Tailwater         H2         cm         4272.01         4271.73         4271.50         4271.09	Head Loss h = H ₁ -H ₂ cm -179.93 -179.13 -178.56	r/Specimen at t ₂ 1828)	cm/sec
$= \frac{a \cdot L}{2 \cdot A \cdot \Delta t} ln \left( \frac{1}{2} \right)$ Date 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009	Time Readings 9:45 AM 10:51 AM 12:15 PM 1:45 PM 3:17 PM	a L A Time Interval Δt Seconds 0.00 3,960 5,040 5,520	= Pipette Cross = Length of Sar = Sample Cross Top Pipette cc 48.45 48.40 48.20 48.05 47.85	-Sectional Area nple -Sectional Area Hydraulic Head Headwater H ₁ cm 4092.08 4092.14 4092.36 4092.54 4092.77	Bottom Pipette cc 14.20 14.45 14.65 15.00 15.25	h1 = Head Loss Ar         h2 = Head Loss Ar         h2 = Head Loss Ar         h1 = Natural Logar         Hydraulic Head         Tailwater         H2         cm         4271.73         4271.50         4271.09         4270.81	Head Loss h = H ₁ -H ₂ cm -179.93 -179.59 -178.56 -178.04	r/Specimen at t ₂ 1828) ln (h ₁ /h ₂₎ - 0.00191 0.00256 0.00320 0.00289	Permeabilit k cm/sec 6.740E-08 7.077E-08 8.280E-08 7.312E-08
$= \frac{\mathbf{a} \cdot \mathbf{L}}{2 \cdot \mathbf{A} \cdot \Delta t} \ln \left( \frac{1}{2} \right)$ Date 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009	Time Readings 9:45 AM 10:51 AM 12:15 PM 1:45 PM 3:17 PM	a L A Time Interval Δt Seconds 0.00 3,960 5,040 5,520	= Pipette Cross = Length of Sar = Sample Cross Top Pipette cc 48.45 48.40 48.20 48.05 47.85	-Sectional Area nple -Sectional Area Hydraulic Head Headwater H ₁ cm 4092.08 4092.14 4092.36 4092.54 4092.77	Bottom Pipette cc 14.20 14.45 14.65 15.00 15.25	h1 = Head Loss Ar         h2 = Head Loss Ar         h2 = Head Loss Ar         h1 = Natural Logar         Hydraulic Head         Tailwater         H2         cm         4271.73         4271.50         4271.09         4270.81	Head Loss h = H ₁ -H ₂ cm -179.93 -179.59 -178.56 -178.04	r/Specimen at t ₂ 1828) ln (h ₁ /h ₂₎ - 0.00191 0.00256 0.00320 0.00289	Permeabilit k cm/sec 6.740E-08 7.077E-08 8.280E-08 7.312E-08
$= \frac{a \cdot L}{2 \cdot A \cdot \Delta t} ln \left( \frac{1}{2} \right)$ Date 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009	Time Readings 9:45 AM 10:51 AM 12:15 PM 1:45 PM 3:17 PM	a L A Time Interval Δt Seconds 0.00 3,960 5,040 5,520	= Pipette Cross = Length of Sar = Sample Cross Top Pipette cc 48.45 48.40 48.20 48.05 47.85	-Sectional Area nple -Sectional Area Hydraulic Head Headwater H ₁ cm 4092.08 4092.14 4092.36 4092.54 4092.77	Bottom Pipette cc 14.20 14.45 14.65 15.00 15.25	h1 = Head Loss Ar         h2 = Head Loss Ar         h2 = Head Loss Ar         h1 = Natural Logar         Hydraulic Head         Tailwater         H2         cm         4271.73         4271.50         4271.09         4270.81	Head Loss h = H ₁ -H ₂ cm -179.93 -179.59 -178.56 -178.04	r/Specimen at t ₂ 1828) ln (h ₁ /h ₂₎ - 0.00191 0.00256 0.00320 0.00289	Permeabilit k cm/sec 6.740E-08 7.077E-08 8.280E-08 7.312E-08
$= \frac{a \cdot L}{2 \cdot A \cdot \Delta t} ln \left( \frac{1}{2} \right)$ Date 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009	Time Readings 9:45 AM 10:51 AM 12:15 PM 1:45 PM 3:17 PM	a L A Time Interval Δt Seconds 0.00 3,960 5,040 5,520	= Pipette Cross = Length of Sar = Sample Cross Top Pipette cc 48.45 48.40 48.20 48.05 47.85	-Sectional Area nple -Sectional Area Hydraulic Head Headwater H ₁ cm 4092.08 4092.14 4092.36 4092.54 4092.77	Bottom Pipette cc 14.20 14.45 14.65 15.00 15.25	h1 = Head Loss Ar         h2 = Head Loss Ar         h2 = Head Loss Ar         h1 = Natural Logar         Hydraulic Head         Tailwater         H2         cm         4271.73         4271.50         4271.09         4270.81	Head Loss h = H ₁ -H ₂ cm -179.93 -179.59 -178.56 -178.04	r/Specimen at t ₂ 1828) ln (h ₁ /h ₂₎ - 0.00191 0.00256 0.00320 0.00289	Permeabilit k cm/sec 6.740E-08 7.077E-08 8.280E-08 7.312E-08
$= \frac{a \cdot L}{2 \cdot A \cdot \Delta t} ln \left( \frac{1}{2} \right)$ Date 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009	Time Readings 9:45 AM 10:51 AM 12:15 PM 1:45 PM 3:17 PM	a L A Time Interval Δt Seconds 0.00 3,960 5,040 5,520	= Pipette Cross = Length of Sar = Sample Cross Top Pipette cc 48.45 48.40 48.20 48.05 47.85	-Sectional Area nple -Sectional Area Hydraulic Head Headwater H ₁ cm 4092.08 4092.14 4092.36 4092.54 4092.77	Bottom Pipette cc 14.20 14.45 14.65 15.00 15.25	h1 = Head Loss Ar         h2 = Head Loss Ar         h2 = Head Loss Ar         h1 = Natural Logar         Hydraulic Head         Tailwater         H2         cm         4271.73         4271.50         4271.09         4270.81	Head Loss h = H ₁ -H ₂ cm -179.93 -179.59 -178.56 -178.04	r/Specimen at t ₂ 1828) ln (h ₁ /h ₂₎ - 0.00191 0.00256 0.00320 0.00289	Permeabilit k cm/sec 6.740E-08 7.077E-08 8.280E-08 7.312E-08
$= \frac{a \cdot L}{2 \cdot A \cdot \Delta t} ln \left( \frac{1}{2} \right)$ Date 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009	Time Readings 9:45 AM 10:51 AM 12:15 PM 1:45 PM 3:17 PM	a L A Time Interval Δt Seconds 0.00 3,960 5,040 5,520	= Pipette Cross = Length of Sar = Sample Cross Top Pipette cc 48.45 48.40 48.20 48.05 47.85	-Sectional Area nple -Sectional Area Hydraulic Head Headwater H ₁ cm 4092.08 4092.14 4092.36 4092.54 4092.77	Bottom Pipette cc 14.20 14.45 14.65 15.00 15.25	h1 = Head Loss Ar         h2 = Head Loss Ar         h2 = Head Loss Ar         h1 = Natural Logar         Hydraulic Head         Tailwater         H2         cm         4271.73         4271.50         4271.09         4270.81	Head Loss h = H ₁ -H ₂ cm -179.93 -179.59 -178.56 -178.04	r/Specimen at t ₂ 1828) ln (h ₁ /h ₂₎ - 0.00191 0.00256 0.00320 0.00289	Permeabilit k cm/sec 6.740E-08 7.077E-08 8.280E-08 7.312E-08
$= \frac{a \cdot L}{2 \cdot A \cdot \Delta t} ln \left( \frac{1}{2} \right)$ Date 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009	Time Readings 9:45 AM 10:51 AM 12:15 PM 1:45 PM 3:17 PM	a L A Time Interval Δt Seconds 0.00 3,960 5,040 5,520	= Pipette Cross = Length of Sar = Sample Cross Top Pipette cc 48.45 48.40 48.20 48.05 47.85	-Sectional Area nple -Sectional Area Hydraulic Head Headwater H ₁ cm 4092.08 4092.14 4092.36 4092.54 4092.77	Bottom Pipette cc 14.20 14.45 14.65 15.00 15.25	h1 = Head Loss Ar         h2 = Head Loss Ar         h2 = Head Loss Ar         h1 = Natural Logar         Hydraulic Head         Tailwater         H2         cm         4271.73         4271.50         4271.09         4270.81	Head Loss h = H ₁ -H ₂ cm -179.93 -179.59 -178.56 -178.04	r/Specimen at t ₂ 1828) ln (h ₁ /h ₂₎ - 0.00191 0.00256 0.00320 0.00289	Permeabilit k cm/sec 6.740E-08 7.077E-08 8.280E-08 7.312E-08
$= \frac{\mathbf{a} \cdot \mathbf{L}}{2 \cdot \mathbf{A} \cdot \Delta t} \ln \left( \frac{1}{2} \right)$ Date 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009	Time Readings 9:45 AM 10:51 AM 12:15 PM 1:45 PM 3:17 PM	a L A Time Interval Δt Seconds 0.00 3,960 5,040 5,520	= Pipette Cross = Length of Sar = Sample Cross Top Pipette cc 48.45 48.40 48.20 48.05 47.85	-Sectional Area nple -Sectional Area Hydraulic Head Headwater H ₁ cm 4092.08 4092.14 4092.36 4092.54 4092.77	Bottom Pipette cc 14.20 14.45 14.65 15.00 15.25	h1 = Head Loss Ar         h2 = Head Loss Ar         h2 = Head Loss Ar         h1 = Natural Logar         Hydraulic Head         Tailwater         H2         cm         4271.73         4271.50         4271.09         4270.81	Head Loss h = H ₁ -H ₂ cm -179.93 -179.59 -178.56 -178.04	r/Specimen at t ₂ 1828) ln (h ₁ /h ₂₎ - 0.00191 0.00256 0.00320 0.00289	Permeabilit k cm/sec 6.740E-08 7.077E-08 8.280E-08 7.312E-08

# **Appendix III – Shear Strength Parameter Justification**





### Layer: NEWER EMBANKMENT FILL

BORING NUMBER	SAMPLE NUMBER	SAMPLE DEPTH	NATURAL MOISTURE	LIQUID LIMIT	PLASTIC LIMIT	PLASTIC INDEX	GRAVEL	SAND	SILT	CLAY .002 mm	SILT/CLAY	USCS CLASSIFICATION
			CONTENT	%	%	%	%	%	%	%	%	
BAP-0901	S-3	4.75	16									
BAP-0901	S-5	7.75	16	28	18	10						
BAP-0901	S-9	13.75	13	27	17	10						
BAP-0901	S-12	18.25	14	37	24	13	7	32	49	12	61	SANDY LEAN CLAY CL
BAP-0902	S-4	6.25	13	27	17	10	42	34	16	8	24	CLAYEY GRAVEL with SAND GC
BAP-0902	S-7	10.75	20									
BAP-0902	S-8	12.25	10	26	17	9	32	39	21	8	29	CLAYEY SAND with GRAVEL SC
BAP-0902	S-11	16.75	24	37	19	18						
BAP-0902	S-12	18.25	21	35	17	18	8	37	33	21	54	SANDY LEAN CLAY CL
BAP-0902	S-13	19.75	31	29	17	12	1	20	62	17	79	LEAN CLAY with SAND CL
BAP-0904	S-3	4.75	13									
BAP-0904	S-6	9.25	14	25	16	9	31	39	21	10	31	CLAYEY SAND with GRAVEL SC
BAP-0904	S-9	13.75	16	35	21	14						
BAP-0904	S-11	16.75					47	25			27	
BAP-0906	S-2A	2.9	11									
BAP-0906	S-3	4.75	15	27	17	10						
BAP-0906	S-8	12.75					30	40	22	9	31	
BAP-0906	S-11	17.25	14	31	19	12	18	44	26	12	38	CLAYEY SAND with GRAVEL SC
					-	-				•		
Samp	le Size	18	16	12	12	12	9	9	8	8	9	
Mini	mum	3	10	25	16	9	1	20	16	8	24	
Max	imum	20	31	37	24	18	47	44	62	21	79	
Me	ean	11.7	16.3	30.3	18.3	12.1	24.0	34.4	31.3	12.1	41.6	
Me	dian	13	15	29	17	11	30	37	24	11	31	
Mo	ode	5	16	27	17	10	#N/A	39	21	12	31	
Std	Dev	-	5.4	4.5	2.3	3.2	16.2	7.7	16.1	4.6	18.9	

### Layer: ORIGINAL EMBANKMENT FILL

BORING NUMBER	SAMPLE NUMBER	SAMPLE DEPTH	NATURAL MOISTURE	LIQUID LIMIT	PLASTIC LIMIT	PLASTIC INDEX	GRAVEL	SAND	SILT	CLAY .002 mm	SILT/CLAY	USCS CLASSIFICATION
			CONTENT	%	%	%	%	%	%	%	%	
BAP-0903	S-2	3.25	24	48	24	24	0	8	60	32	92	LEAN CLAY CL
BAP-0903	S-3	4.75	22									
BAP-0903	S-5	7.75	20	36	20	16	0	14	58	28	86	LEAN CLAY CL
BAP-0905	S-3	4.75	17	32	18	14	0	25	53	23	76	LEAN CLAY with SAND CL
BAP-0905	S-5	7.75	22	48	24	24						
BAP-0905	S-6B	9.85	33				5	14			81	
BAP-0907	S-2	3.25	21									
BAP-0907	S-4	6.25	15									
BAP-0907	S-5	7.75	23	49	26	23						
BAP-0907	S-6A	9.25	28	47	29	18	0	5	67	29	96	SILT ML
										-		
Samp	le Size	10	10	6	6	6	5	5	4	4	5	
Mini	imum	3	15	32	18	14	0	5	53	23	76	
Max	imum	10	33	49	29	24	5	25	67	32	96	
M	ean	6.5	22.5	43.3	23.5	19.8	1.0	13.2	59.5	28.0	86.2	
Me	dian	7	22	48	24	21	0	14	59	29	86	
M	ode	8	22	48	24	24	0	14	#N/A	#N/A	#N/A	]
Std	Dev	-	5.1	7.4	4.0	4.4	2.2	7.7	5.8	3.7	8.1	

### Layer: ALLUVIUM SILT AND CLAY

BORING	SAMPLE	SAMPLE	NATURAL	LIQUID		PLASTIC	GRAVEL	SAND	SILT	CLAY	SILT/CLAY	USCS
NUMBER	NUMBER	DEPTH	MOISTURE	LIMIT	LIMIT	INDEX				.002 mm		CLASSIFICATION
			CONTENT	%	%	%	%	%	%	%	%	
BAP-0901	S-15	22.75	30	NP	NP	NP	0	5	89	6	95	SILT ML
BAP-0901	S-16A	24.5										
BAP-0901	S-18	29.25	27	37	22	15	0	9	63	28	91	LEAN CLAY CL
BAP-0901	S-19A	31.25										
BAP-0901	S-19B	31.75	33	35	28	7	0	26	56	18	74	SILT with SAND ML
BAP-0901		32.25										
BAP-0902	S-14	21.25	26	NP	NP	NP	0	13	83	4	87	SILT ML
BAP-0902	S-15	22.75					1	22			78	
BAP-0903	S-10	21.75	35	34	21	13	0	29	51	19	70	LEAN CLAY with SAND CL
BAP-0904	S-15	22.75	26	NP	NP	NP	1	52	45	3	48	SILTY SAND SM
BAP-0904	S-17	25.75	22	NP	NP	NP	0	8	86	5	91	SILT ML
BAP-0905	S-11	21.75	38	38	23	15	2	36	47	15	62	SANDY LEAN CLAY CL
BAP-0906	S-15	24.75	31	NP	NP	NP	0	5	89	7	96	SILT ML
BAP-0906	S-16A	26.25					4	41			55	
BAP-0906	S-17	27.25	22	NP	NP	NP	5	20	70	5	75	SILT with SAND ML
	•				-							·
Samp	le Size	15	10	4	4	4	12	12	10	10	12	
Mini	imum	21	22	34	21	7	0	5	45	3	48	
Max	imum	32.25	38	38	28	15	5	52	89	28	96	
M	ean	25.73	29.0	36.0	23.5	12.5	1.1	22.2	67.9	11.0	76.8	
Me	dian	24.75	29	36	23	14	0	21	67	7	77	
M	ode	22.75	26	#N/A	#N/A	15	0	5	89	5	91	
Std	Dev	-	5.4	1.8	3.1	3.8	1.7	15.2	17.8	8.5	15.9	1
					21 11							—

NP - Non Plastic

### Layer: ORGANIC CLAYEY SILT

BORING	SAMPLE	SAMPLE	NATURAL	LIQUID	PLASTIC		GRAVEL	SAND	SILT	CLAY	SILT/CLAY	USCS
NUMBER	NUMBER	DEPTH	MOISTURE	LIMIT	LIMIT	INDEX				.002 mm		CLASSIFICATION
·			CONTENT	%	%	%	%	%	%	%	%	
BAP-0901	S-20	34.25	42	34	27	7	0	22	62	16	78	ORGANIC SILT with SAND OL
BAP-0901	S-21	36.75	40	45	29	16	11	30			59	SANDY ORGANIC SILT OL
BAP-0901	S-22	39.25	42	40	23	17	0	18	59	22	81	ORGANIC CLAY with SAND OL
BAP-0902	S-18	27.25	54	NP	NP	NP	0	15	69	16	85	ORGANIC SILT OL
BAP-0902	S-19	28.75	43	NP	NP	NP	0	25	61	13	74	ORGANIC SILT with SAND OL
BAP-0902	S-20	32.25	38	36	28	8	2	23	59	16	75	ORGANIC SILT with SAND OL
BAP-0903	S-6	9.25	49	41	38	3	0	33	52	15	67	SANDY ORGANIC SILT OL
BAP-0903	S-7	14.25	43	NP	NP	NP	0	29	56	15	71	ORGANIC SILT with SAND OL
BAP-0903	S-8	16.75	43	37	24	13	0	24	57	19	76	ORGANIC CLAY with SAND OL
BAP-0903	S-9	19.25	44	35	24	11	0	39	45	16	61	SANDY ORGANIC CLAY OL
BAP-0904	S-13	19.75	28	NP	NP	NP	0	8	87	5	92	ORGANIC SILT OL
BAP-0904	S-18	27.25	38	38	24	14	0	21	58	21	79	ORGANIC CLAY with SAND OL
BAP-0904	S-19	28.75	47	42	30	12	0	22	62	17	79	ORGANIC SILT with SAND OL
BAP-0905	S-8	14.25	45	43	27	16	0	19	60	21	81	ORGANIC SILT with SAND OL
BAP-0905	S-9	16.75	42	40	25	15	0	16	60	24	84	ORGANIC CLAY with SAND OL
BAP-0906	S-19	31.75	34	33	22	11	0	19	63	18	81	ORGANIC CLAY with SAND OL
BAP-0906	S-20	34.25	43	50	30	20	0	3	53	44	97	ORGANIC SILT OH
BAP-0906	S-21	36.75	38	43	26	17	1	7	65	27	92	ORGANIC CLAY OL
BAP-0907	S-7	11.75					0	17	66	17	83	
BAP-0907	S-8	14.25	43	44	28	16	0	15	63	22	85	ORGANIC SILT with SAND OL
BAP-0907	S-9	16.75	44	45	29	16	0	15	64	21	85	ORGANIC SILT with SAND OL
BAP-0907	S-10	19.25	40	48	29	19	0	9			91	ORGANIC SILT OL
BAP-0907	S-11	21.75	39	30	24	6	1	43	44	12	56	SANDY ORGANIC SILT OL
						•				•		·
Samp	le Size	23	22	18	18	18	23	23	21	21	23	]
Mini	mum	9	28	30	22	3	0	3	44	5	56	
Maxi	imum	39.25	54	50	38	20	11	43	87	44	97	
Me	ean	23.97	41.8	40.2	27.1	13.2	0.7	20.5	60.2	18.9	78.8	1
Me	dian	21.75	43	41	27	15	0	19	60	17	81	]
Mo	ode	14.25	43	45	24	16	0	15	62	16	81	1
Std	Dev	-	5.2	5.4	3.7	4.7	2.3	9.8	8.8	7.4	10.6	]

### Layer: GLACIAL OUTWASH SAND AND GRAVEI

BORING NUMBER	SAMPLE NUMBER	SAMPLE DEPTH	NATURAL MOISTURE	GRAVEL	SAND	SILT	CLAY .002 mm	SILT/CLAY
			CONTENT	%	%	%	%	%
BAP-0902	S-22	37.25	22	0	70	22	8	30
BAP-0902	S-23	39.75	24	0	83	13	4	17
BAP-0902	S-24	42.25		4	82			14
BAP-0903	S-11	24.25		9	77			14
BAP-0904	S-21	36.75		0	76			24
BAP-0905	S-13	26.75		19	73			8
BAP-0906	S-24	44.25		56	38			7
BAP-0907	S-13	26.75		53	40			7
			-					
Samp	le Size	8	2	8	8	2	2	8
Mini	mum	24	22	0	38	13	4	7
Max	imum	44.25	24	56	83	22	8	30
M	ean	34.75	23.0	17.6	67.4	17.5	6.0	15.1
Me	dian	37.00	23	7	75	18	6	14
M	ode	26.75	#N/A	0	#N/A	#N/A	#N/A	14
Std	Dev	-	1.4	23.7	18.0	6.4	2.8	8.4



DN	Project/Proposal No. 011./1497. 013	Calculated By MITR Date 6-29-09
71 00	Project/Proposal Name CARDINAL ASH PEND	Checked By MAR Date 7-2-09
26 11	Subject STRINGTH ! PERM. PARAMETERS	Sheet / of 8

<	DNLY	1.21	AD	1	A1	- 18A . S	10 0. 200 11	1= 100	- D = 1 - 1			
		LITY AN									-	
10	SIL	ice nl	978.	- CON	STAN	T NORT	TAL S			RDD A		515
4	STR	LENGTH 1	ARAMET	ERS	1 1 -							
		ESMA			IE AA	Mair de	4 INTER	ZNIAI	FRICTU	N.d'	AF	
	T											
		Cottesive	CAYEL	ASY	Conpan	aneg RE	50615	FROM	1876	rohlok	sing	Mer
	D	CORRELATI	onis To	LL,	, CLAY	SIZED F	EXETEOR	1, AND	OVER	BURDER	1 577	RESS
		DEVELOPR	D BY	SNARK								
	2	2-	-12 2.									
	~)	RELATION. BY TERI	EAGIHI,	PECK,	ANID	MESRI,	1996	IN DEX	15	Scher	20152	
		+		-	1-1-0-			1	-	1		1
	3) (	CORRELAT	and 70	CLAY	SIZED	FRACTION	I FOR ,	LORMAL	LY CON	ISOLIDA	TIED	
		CLAY -										
						0 - 0.26						
	1	1		PNE		C.AU			-		1	
		1.1.2.2	1		4-1-0		the second			1 - 1		1.4
	1.						1				-	
	4)	FOR FILL	SOILS,	ESTI	MATE	DRAWIE	D STRE	~1G. 774	VALUE	5 FRE	ster	
	4)	FUR FILL NAVFAC	SOILS, DESIGN	ESTI. MAN	MATE	DRAWIE 7.2 JSIN	ID STRE	AIGITH ABLIE /	VALUE	5 FRU VPICAL	ster.	
	1 1-	NAVFAC	DESIGN	MAN	UAL T	7.2 USIN	is stre	ABLIE 1	VALUE	S FRE	sten	
	1 1-	FUR FILL NAUFAC PROPERTIES	DESIGN	MAN	UAL T	7.2 USIN	id stree	2216771 ABLIE 1	V42UE	5 ARC	ster	
	1 1-	NAVFAC	DESIGN	MAN	UAL T	7.2 USIN	in stree	48LIE 1	V42UE	s ARU YPICAL	shin .	
	1 1-	NAVFAC	DESIGN	MAN	UAL T	7.2 USIN	ID STRE	-21-16-771 4BLIE 1	VALUE. - 'T	5 FRC YPICAL	) Lu	
1	1 1-	NAVFAC	DESIGN	MAN	UAL T	7.2 USIN	il stree	771-15-1771 781_12 /	V42UE,	5 ARU YPICAL	slun	
	1 1-	NAVFAC	DESIGN	MAN	UAL T	7.2 USIN	D STRE	771-G 771 781.02 /	VALUE, - 'T	S ARU YPICAL		
	1 1-	NAVFAC	DESIGN	MAN	UAL T	7.2 USIN	D STRE	48L12 1	VALUE. - 'T	5 PRU YPICAL		
+		NAUFAC PROPERTIES	DESUM OF C	MAN	UAL TED S	7.2 USIA	(4 TF	48LIE /	' — 'T	YPICAL	~	
+	GRA	NAUFAC PROPERTIES	DESIGN OF C	one L	AMERS	7.2 USIN OTLS '	CAL CL	HBLIE 1	5.4~12	Y GRA	VEL)	
+	GRA	NAUFAC PROPERTIES	DESIGN OF C	one L	AMERS	7.2 USIN OTLS '	CAL CL	HBLIE 1	5.4~12	Y GRA	VEL)	-C-Y-St-
+	GRA	NAUFAC PROPERTIES ANULAR F ESTIMATE	DESIGN FOF C	one c	AVIERS	7.2 USIN DILS' S (CYLAN F CURRE	CG TR CAL CXJ	ABLIE 1 ITWASH 5 ANIS	5.4~1D 5.4~1D 5.R~A 11	SIZE	VEL)	-6451
+	GRA	NAUFAC PROPERTIES	DESIGN FOF C	one c	AVIERS	7.2 USIN DILS' S (CYLAN F CURRE	CG TR CAL CXJ	ABLIE 1 ITWASH 5 ANIS	5.4~1D 5.4~1D 5.R~A 11	SIZE	VEL)	.LYSL
+	GRA	NAUFAC PROPERTIES ANULAR F ESTIMATE d'= -TIS	DESIGN 5 OF C 5.4 (NG0	one c	AVIERS	7.2 USIN DILS' S (CYLAN F CURRE	CG TR CAL CXJ	ABLIE 1 ITWASH 5 ANIS	5.4~1D 5.4~1D 5.R~A 11	SIZE	VEL)	
+	GRA	NAUFAC PROPERTIES ANULAR F ESTIMATE	DESIGN 5 OF C 5.4 (NG0	one l sed o	AMERI SALIERI SALIERI SALIERI SALIERI	7.2 USIN ORLS' S (CALAG F CORRE HANTALIAN	CA ANIS	ABLIE 1 SANISH SANIS	5.4~12 E.R.A.112 E.R.A.112 A, 1996	S GRA SIZE	VEL) ANA	
+	GRA	NAUFAC PROPERTIES ANULAR ESTIMATE d'= -TIS	DESIGN OF C S.4 (NGO EQN	one l bright one l break of bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright bright brig bright bright bright bright bright brig	AVIERS SAVIERS	7.2 USIN DILS' S (CYLAN F CURRE	CAL CU LATIONS CAANIS WES E	ABLIE 1 SANISH SANIS	5.4~12 E.R.A.112 E.R.A.112 A, 1996	S GRA SIZE	VEL) ANA	
+	GRA	NAUFAC PROPERTIES ANULAR F ESTIMATE d'= -TIS COMPARE TABLE 7.	DESIGN SOF C S.4 (NGO EQN 1 Relative	r A A A A A A A A A A A A A A A A A A A	MIERS	7.2 USIN ORLS' F (GLAG F CORRE HANTALIAN PICAL VA BSIONLESS S	UAL CU LATIONS CA ANIS WES E OILS	48UE 1 17-WASH 5 ANIS UCHIDA 5774BUSI7	5.4~1D E1R.A.11 4, 1990 460 B.1	d GRA V SIZK SCHRUK	VEL) ANIA	
+	GRA	NAUFAC PROPRETIES ANULAR F ESTIMATE O d'= -TIS COMPARE	DESIGN DESIGN SOF EST SOF SOF SOF SOF SOF SOF SOF SOF SOF SOF	maxi maxi maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxim maxi	AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AMERI AM	7.2 USIN OTLS' F (CLAR F CERRE HANTALIAN PICAL VA BSIONLESS S N60	CAL CU LATIONS CAANIS WES E	48UE 1 17-WASH 5 ANIS UCIHIDA STABLISIT	5.4~1D EqRA11 4, 1990 40 BJ	y GRA J GRA J SIZIS SCHRUNS	VEL) ANIA	
+	GRA	NAUFAC PROPERTIES ANULAR ESTIMATE d' = -TIS COMPARE TABLE 7. Relative D. Designatio	DESIGN DESIGN S. C. C. S. C. C. S. C. C. S. C. C. S. C. C. S. C.	$\frac{\partial n(x)}{\partial x}$	A VIERS	7.2 USIN OTLS' F (CLAR F CERRE HANTALIAN PICAL VA BSIONLESS S N60	CA ANIS CA ANIS CA ANIS WES E oils Standard on Resistan	48UE 1 17-WASH 5 ANIS UCIHIDA STABLISIT	5.4~10 5.4~10 5.7.4.11 4, 1990 4, 1900 4, 1900	SCHRONE degrees	WEL) ANIA DER li tion	
+	GRA	NAUFAC PROPRETIES ANULAR F ESTIMATE d': - 113 COMPARE TABLE 7. Relative D. Designatio Very loose	DESIGN DESIGN S. C. C. S. H. (NGO I Relative ensity n <u>Moust</u> (1) "10-100	maxi maxi maxi maxim server maxim partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice partice	A TERS	7.2 USIN OTLS' F (CLAR F CERRE HANTALIAN PICAL VA BSIONLESS S N60	CA ANIS CA ANIS CA ANIS COES E Oils Standard fon Resistant 0-4	48UE 1 17-WASH 5 ANIS UCIHIDA STABLISIT	5.4~10 E,p.4.11 4, 1990 heD B-1 oximate Au of Soil 4, 25	s GRA SIZIS SCHRUE agle of Frick degrees	WEL) ANIA DER li tion	
+	GRA	NAUFAC PROPRETIES PROPRETIES ANULAR F ESTIMATE d' = -/13 COMPARE TABLE 7. Relative D. Designatio Very loose Loose	DESIGN DESIGN S.4 (NGO 1 Relative ensity n <u>Ymolet</u> (F 70-100 90-115	$\frac{\partial n(d)}{\partial x}$	AMERI AMERI AMERI AMERI SAL SAL SAL SAL SAL SAL SAL SAL	7.2 USIN $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}{2}$ $rac{1}$	CA = CX CA = ANIS CA =	48UE 1 17-WASH 5 ANIS UCIHIDA STABLISIT	5.4~12 <i>E</i> ₁ <i>R</i> .4 <i>A</i> , 1990 <i>A</i> , 1990 <i></i>	SCHRUE SCHRUE agle of Frice degrees -28 -30	WEL) ANIA DER li tion	
+	GRA	MAUFAC PROPRETIES PROPRETIES ANULAR ESTIMATE G' = -TIS COMPARE TABLE 7. Relative D. Designatio Very loose Loose Medium	DESIGN DESIGN S.4 (NGo 15 QN 1 Relative n <u>Y moltri (15</u> NO-100 90-115 110-130	$\frac{\partial n(x)}{\partial x}$	which is the set of th	7.2 USIN ORLS' S (CLAR $T CRRE HANTALIAN PICAL VABSIONIESS SN_{60}Penetrati$	CA ANIS CA ANIS CA ANIS CES E oils Standard on Resistan 0-4 4-10 10-30	48UE 1 17-WASH 5 ANIS UCIHIDA STABLISIT	5.4~12 <i>E</i> ₁ <i>R</i> .4 <i>A</i> , 1996 <i>A</i> , 1996 <i></i>	y GRA SIZIS SCHRONS SCHRONS Agle of Frici degrees -28 -30 -36	WEL) ANIA DER li tion	
+	GRA	NAUFAC PROPRETIES PROPRETIES ANULAR F ESTIMATE d' = -/13 COMPARE TABLE 7. Relative D. Designatio Very loose Loose	DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN DESIGN	$\frac{\partial n(x)}{\partial x}$	viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers viers vi	7.2 USIN ORLS' S (CLAC $T CRRE HANTALIAN PICAL VABSIONIESS SN60Penetrati$	CA = CX CA = ANIS CA =	48UE 1 17-WASH 5 ANIS UCIHIDA STABLISIT	5.4~1D E.R.A.11 E.R.A.11 E.R.A.11 A, 1992 Az D A.4 oximate Ano of Soil of, 25 28 30 36	SCHRUE SCHRUE agle of Frice degrees -28 -30	WEL) ANIA DER li tion	



	Project/Proposal No. 01.11497.013	Calculated By MTR Date	6-29-09
471 000	Project/Proposal Name CARDINAL ASH PUNA	Checked By ML12 Date	7-2-09
226 011	Subject STRENGAT S PERM PARAMETERS	Sheet of8	

+ PERMEABILITY - EMBANKMENT FILL: ESTIMATE PERM BASED ON RESULTS FROM FLER WALL PERMEABILITY TEST DERFORMETS ON UNDISTURBED SAMPLE. ESTIMATE PREM. HEALTCR THAN TEST WHERE D ACCOUNT FOR PERMEABILITY ON A MACRO SCALE, AS WILL AS ACCOUNTING FOR SAMPLES WITTH A HIGHER GRANIULAR CONTIENT. -> ADJUST K, KU/KIA RATIO DURING AMANYSIS TO MATCH MELD CONDITIONS. - ORIGINAL EMBANKMENT FILL ? MATURAL ENTESINE LAVERS ESTIMATE PERM. BASED ON TYPICAL PUBLISITED VALVES USING SOIL DESCRIPTIONS & GRAIN SIZE ANIALYSIS - GRANNLAR FUNDATION LAYERS ESTIMATE PERMEABILITY SASED ON TYPICAL PUBLISHED LALVES BASED ON RELATIVE DENSITY & GRAM! SIZE ANALYSIS. AS A GUIDE, USE K= (100 DID) USEE (cm x10-4/SEC) (HAZEN) ALSO USE dis VALUE AND COMPARIE TYPICAL RANGE OF PERMEABILITY BASTED ON GRAIN SIZE (GEOSYNTEL, 1991) **PLATE 9** 



	Project/Proposal No. 011.11497.013	Calculated By MTR Date 6-29-09
171 )00 26	Project/Proposal Name CARDINAL ASH POULD	Checked By <u>M418</u> Date <u>7-3-09</u>
011	Subject SDENKTH 5 DEPART PARTY	Sheet of8

	NEWE	IC ICTYINGAL	CMRAT	PEILL	- (10	1705)			-	
- DESCR	IPRON! M.	ALTOINE -	7		1					
111	IDTON: Ce		CONTRS	Airles	POCKET	s de	TITE	FOLLOW	Sing	
	· · · · ·	MED DEN	SE TO	DENSK	BRau,	N ANIS	GRA	1 1-121	ERS	
		correst c	TRAVIEL	SOME	FILLE	no con	grst s	AND,	SOME	5 70
		AND SIL	TY CLA	t¥	1				1.1	
	z)	SOFT	TU 141	ard i	Berner	ANID (	GRAY	SILTY	CLAV.	1
		SOME FINIL	E 70	COARSE	SAND,	SOME	FINE	10 00	ARSE	GRA
		A CONTRACTOR OF A CONTRACTOR A CONT	the second second	And the second second	1 - L.					
- N60	VALUES	(IN GRAN	ULAIL	ZONES	5					
	Low	: 16	-							
	HIGH :	50								
-	AVG1 :	26								
- HAND 1	DENETROMET	TR CON	SAMPLIE	S EXITIB	TING C	SHE RO	C			1
	17= 0	0 - 4.5	-+ ts	f						
				1	Ï					-
- STRIENG	TH PARAMET	TER :				1-2-1				
								1		-
1) Corre	ELATION T	O SMARK CI	HARTS		141914	-				
		STARK CI ATTURI, CON	SIDER	DEPTH	Øvo :	50	KPq.	AND	100 1	křa
	ELATION 7 FOR CORREL TO ACCOUNT RESULTS:	S SMARK CI ATTURNI, CON T FOR PR $\Phi_{FS}' = 31^{\circ}$	USIDER DBABLE (SE	DEPTH	Øvo :	50	KPq.	AND	100 1	kin
2) GRA	ELATION T FOR CORREL TO ACCOUN RESULTS:	STARK CL ATURI, CON T Fox PR $\Phi_{FS}' = 31^{\circ}$ S' URS PI	LSIDER DBABLE (SE	DEPTH IE CORR	Øvo = DE FJ	= 50 912025 5 THIS	King . Switch. APAR	AND	100 1	ĸřn
2) GRA	ELATION 7 FOR CORREL TO ACCOUNT RESULTS:	STARK CL ATURI, CON T Fox PR $\Phi_{FS}' = 31^{\circ}$ S' URS PI	LSIDER DBABLE (SE	DEPTH IE CORR	Øvo = DE FJ	= 50 912025 5 THIS	King . Switch. APAR	AND	100 1	kra
- 1 2) GRA - J	ELATION T FOR CORREL TO ACCOUN RESULTS: APH OF Q RESULTS: (	STARK C ATURS, CON (T For PR) $(F_{FS}' = 31^{\circ})$ $S' URS PI (S' = 33^{\circ})$	LSIDER SABLE (SE (SEE	DEPTH IE CORR	Øvo = DE FJ	= 50 912025 5 THIS	King . Switch. APAR	AND	100 1	křa
2) GRA - Ī 3) N/	ELATION T FOR CORREL TO ACCOUN RESULTS: APH OF P RESULTS: ( A FOR ;	STARK C ATUR, CON $(T \ first \ Pr.$ $(F_{fs}' = 31^{\circ})$ $S' \ URS \ PI$ $(S' = 33^{\circ})$ FILL SO'LS	LSIDER SABLE (SE (SEE	DEPTH IE CORR	Øvo = DE FJ	= 50 912025 5 THIS	King . Switch. APAR	AND	100 1	křa
2) GRA - Ī 3) N/	ELATION T FOR CORREL TO ACCOUNT RESULTS: APH OF P RESULTS: A FOR I	STARK C ATURN, CON T For PR $\Phi_{FS}' = 31^{\circ}$ S' URS PI $\Phi' = 33^{\circ}$ FILL SO'LS SLIE 1:	ISIDER SABLE (SE (SEE	DEPTH E CORR CHARI	Øvo = DE FJ	= 50 AILURIE S THIS APPEND	King Swith APAR	AND ACRE. ENDIX	/00 /	
2) GRA - Ī 3) N/	ELATION T FOR CORREL TO ACCOUNT RESULTS: APH OF P RESULTS: A FOR I	STARK C ATURN, CON T For PR $\Phi_{FS}' = 31^{\circ}$ S' URS PI $\Phi' = 33^{\circ}$ FILL SO'LS SLIE 1:	ISIDER SABLE (SE (SEE	DEPTH E CORR CHARI	Øvo = DE FJ	= 50 AILURIE S THIS APPEND	King Swith APAR	AND ACRE. ENDIX	/00 /	
2) GRA - Ī 3) N/	ELATION T FOR CORREL TO ACCOUN RESULTS: APH OF Q RESULTS: ( A FOR GROUP GC	S STARK CL ATUNI, CON T Fox PR $\Phi_{FS}' = 31^{\circ}$ $S' URS PI S' = 33^{\circ}FILL SOILSSULE 1:SOIL TYPECLAYEY C$	SIDER SABLE (SE (SE GRAVEL	DEPTH E CORR CHARI	Øvo = DE FJ	= 50 AILURIE S THIS APPEND	King Swith APAR	AND ACRE. ENDIX	/00 /	
2) GRA - Ī 3) N/	ELATION T FOR CORREL TO ACCOUNT RESULTS: APPH DF Q RESULTS: A FOR GC GC SC	STARK C ATUN, CON (T fix) PR $(F_{fs}' = 31^{\circ})$ $S' URS PI S' = 33^{\circ}FILL SOILSSLE 1:SOIL TYPECLAYEY CCLAYEY$	ISIDER SABLE (SEE GRAVEL SAMDS	DEPTH E CORR CHARI	\$ vo = c) = 1=1 = 1=1 = 77415	= 50 AILURE S THIS APPEND	King Switch APAR STRA '= 0, '= 230	AND ACE. ENDIX MGTH Q'7	200 / ) 3/° (= 3/°	TY (cm/s 7 5x
2) GRA - Ī 3) N/	ELATION T FOR CORREL TO ACCOUNT RESULTS: APPH DF Q RESULTS: A FOR GC GC SC	STARK C ATUN, CON (T fix) PR $(F_{fs}' = 31^{\circ})$ $S' URS PI S' = 33^{\circ}FILL SOILSSLE 1:SOIL TYPECLAYEY CCLAYEY$	ISIDER SABLE (SEE GRAVEL SAMDS	DEPTH E CORR CHARI	\$ vo = c) = 1=1 = 1=1 = 77415	= 50 AILURE S THIS APPEND	King Switch APAR STRA '= 0, '= 230	AND ACE. ENDIX MGTH Q'7	200 / ) 3/° (= 3/°	TY (cm/s 7 5x
2) GRA -7 3) N/ 4) NA	ELATION T FOR CORREL TO ACCOUN RESULTS: APH OF P RESULTS: ( A FOR GC SC CL	S STARK CL ATUNJ, CON UT FOX PR 45' = 31° S' URS PT S' IRS PT S' = 33° FILL SOILS SLE 1: <u>SOIL TYPE</u> CLAYEY TNOKG C	ISIDER SABLE (SEE (SEE GRAVEL SAMDS LAYS S	DEPTH E CORR CHARI	DE FRI DE FRI ELATION - TRAS	= 50 AILURIE S THIS APPEND	King Switch APAR STRA '= 0, '= 230	AND ACE. ENDIX MGTH Q'7	200 / ) 3/° (= 3/°	TY (cm/s 7 5x
2) GRA -7 3) N/ 4) NA	ELATION T FOR CORREL TO ACCOUN RESULTS: APH OF P RESULTS: ( A FOR GC SC CL	S STARK CL ATUNJ, CON UT FOX PR 45' = 31° S' URS PT S' IRS PT S' = 33° FILL SOILS SLE 1: <u>SOIL TYPE</u> CLAYEY TNOKG C	ISIDER SABLE (SEE (SEE GRAVEL SAMDS LAYS S	DEPTH E CORR CHARI	DE FRI DE FRI ELATION - TRAS	= 50 AILURIE S THIS APPEND	King Switch APAR STRA '= 0, '= 230	AND ACE. ENDIX MGTH Q'7	200 / ) 3/° (= 3/°	TY (cm/s 7 5x
2) GRA -7 3) N/ 4) NA DESIG	ELATION T FOR CORREL TO ACCOUNT RESULTS: APH OF 2 RESULTS: A FOR i VFAC TAR GC SC CL IN STRENG	STARK CL ATWAJ, CON TFOR PR G/ = 31° S' URS PI S' URS PI S' = 33° FILL SOILS SLE I: <u>SOIL TYPE</u> CLAYEY CLAYEY TNOKG C	ISIDER SABLE (SEE (SEE GRAVEL SAMDS LAYS SI = 0	DEPTH E CORR CHARI F LOW	Вио : 2 / г.) ELATION - 7745 - МЕД , С. '.	= 50 AILURIE S THIS APPENDE C C PI C = 31°	King Switch APAR (1) STRA (1=0, 1=230	AND ACRE. ENDIX MAITH & 7 TSF, R PSF, Q	200 31° 31° 31° 31° 31° 31° 31° 31°	74 (conds 7 5× 7
2) GRA -7 3) N/ 4) NA DESIG	ELATION T FOR CORREL TO ACCOUNT RESULTS: APH DF Q RESULTS: A FOR GR GR SC CL A STRENG A STRENG	S SMARK CL ATWUL, CON (T FOR PR (FS' = 31° S' URS PI (S' URS PI (S' = 33° FILL SOILS SULE 1: SOIL TYPE CLAYEY CLAYEY INOKG C ITTH: C' BASED ON	ISIDER SARLE (SEE GRAVEL SAMDS LAYS SI = 0, PCRMC	DEPTH E CORR CHARI F LOW PSF ADULITY	Bro : DE F. ELATION - THIS - MED , CORREL CORREL	= 50 AILURE STHIS APPENDI TYP C PI C = 31°	King Switch APAR (	AND ACKE. ENDIX Q'7 PSF, P PSF, Q TIPICAL	100 31° 5'= 31' 5'= 28'	TY (conts 7 5x 7
2) GRA -7 3) N/ 4) NA DESIG	ELATION T FUR CORRELL TUS ACCOUNT RESULTS: APPH DF & RESULTS: A FUR GC SC CL IN STRENG	STARK CL ATWAJ, CON TFOR PR G/ = 31° S' URS PI S' URS PI S' = 33° FILL SOILS SLE I: <u>SOIL TYPE</u> CLAYEY CLAYEY TNOKG C	SILINER SABLE (SEE (SEE GRAVEL SAMDS LAYS OF PERMICE SILIN,	DEPTH E CORR CHARI F LOW PSF ADILITY USK	Вио = 2 / г. 2 / г. 2 / л. - 7745 - 7755 - 7755 - 7755 - 7755 - 7755 - 775 - 7745 - 7755 - 7755	TYP APPENAL APPENAL C PI C ATIONS (10-5 0	KPq SURF. APPA () STRA () STRA () = 230 = 270	AND ACKE. ENDIX STATU SF, R PSF, R PSF, Q NIPICAL SFF	100 ) 31° 51° 51° 51° 51° 51° 51° 51° 51° 51° 5	TY (conts 7 5x 7



	Project/Proposal No. 0/1. 1/497. 0/3	Calculated By 178 Date 6-29-09
471	Project/Proposal Name CARDINAL ASH POND	Checked By Mark Date 1-2-09
226	Subject STRENGATH & PERM PARAMETERS	Sheet _ 4_ of _ 8_

	ek:	ORIGINA	L EMBAN	IKINENT	FILL	LOLDEN	R FILL)		
	- De	SCRIPTION	: 'STIPE SILTY	TO	HARD (USCS	BROWN : LEAN	MOTTLED CLAY)	wmt	GRAY
-	1.1.Ap	UD DEMET.	RUMETER ;	Anchie	: 1.5 -	4.5 ts	P		
-	STRE	ENGTH PA	RAMETER						15
		CONSIDE TO TTY	Thus To $R = \phi_{v_0} = \frac{1}{2}$ $h = \frac{1}{2}$	50 KPM	BANKA	ON RI	ELATION D	1= THIS	LA YE
		- RESULTS	TR		/		No.		
	2	) \$' vas	PI	1		US APPEND			
		- RESU	LTS: Fok	P1 = 2	14, ¢	'= 30°	(SEE C	HART T	HIS APP
	3	) M/A ;	FOR FILL	SOILS					
	4	60	OUP SOIL				THP I STRE	MIDRANIED NGTI+	THE
		CI	- INO	RGANIC VIED PLA	CLANS	of Lo	$\sim$ $c'=$ : $\phi'=$	Topsf	
	DESIC	IN STRIEN	GTH PARAN	ICTER :	C'=1	oo psf	, ¢'= 3	•	
PEX	emier	BILITY :							
	FL	EX WALL BORING	PIERIMIEABUL BAP-0907	ITY TEST	- PERFU	orthed	ON SAM	PLE ST	-6A
1	- Re	sours K	v = 7.42 ;	( 10-8 (	cm/sec				
11	- Dr:	signt: us MA	E KJ = 1 CRO SCAL	×10 ⁻⁷ cn	n/sec ;	rs Accou	INT FOR P	ERM. C	N A
			KU ADDUS			-8 cm/co	C. LITT	Kula	55
			DURINES S	TERNAGE	ANIALY	SIS		nn/Kr	3
	1 1	1 - 4			TO B			Sella de	



Project/Proposal No. 01. 11497. 013 Calculated By MITR Date 6-29-09 Project/Proposal Name CARDINAL ASH PONID Checked By MGR Date 7-2-09 Columbus (614) 793-2226 Dayton (937) 424-1011 Subject STRENGTH & PLEM _____ Sheet 5 of 8

LAYER: ALLUVIUM SILT & CLAY - DESCRIPTION: USEY LOOSE TO MED DEMOSE GRAY SILT, CONTAINS ZOULES OF STIFF TO MADED SILTY CLAY AND THIN'S LAVERS OF VERY LOOSE TO LOOSE FINE TO COARSE SAND - NGO RANGE: O TO 27, AUG = 8 6pf - HAND PENIETROMIETER: O-3,5 ESP ON SICL SAMPLES - STRENGTH PARAMETERS 1) STARK CORRELATION! - CONSIDER BOTH QUO = 100 KPA AND 400 KPA WITH TENDANCY TOWARD ICS KPa - RESULT: \$ = 30" (SEE CORNELATION THIS APPENDIX) 2) \$' URS PI - RESOLTS: FOR PI= 15, \$'= 31.5° (SEE CHART THIS APPENDIX) 3) HALL'S THESIS 4'NC = 36 - 0.2665 (70 CLAY) FOR CF = 10.9, Q'NC = 33° 4) N/A FUR NATURAL SOILS - USE TABLE 3.28 - COMMONDE PROPERTIES OF CONTEFENDINES SOILS ( SAVELIE - FOR 'LOOSE INCORGANIC SILTS' Q'= 27° 14, 5 Design Strength Parameter: Use Onc = 30°, c' = 0 psf - Permeability: Based on soil description. ky = 1x10-5 cm/s (typical published value)



ON	Project/Proposal No. 01/11/497.013	Calculated By MTR Date 6-29-09
471 000	Project/Proposal Name CARDINAL ASH POULD	Checked By Mun Date 1-2-9
226 011	Subject STRENGTH & PERMEABILITY	Sheet _ 6 of _ 8

LAYER: ORGANIC CLAYEY SILT - DESCRIPTION : VERY SOFT TO STIFF ORGANIC CLAYEY SILT, CULIDONS SEAMS OF VERY LOOSE ORGANIC SILT * - LOSS ON EGNIMONS : RANGE = 7.9% TO 10.4% FROM 3 SAMPLES TESTED. - HAND PENKTROMETER: 0.0 - 1.25 Est STRENGTH PARAMETER: 1) STARK CORRELATION : - CONSIDER Qu'S = 100 KPg AND 400 KPg WITH TENDANCY TOWARD 100 KPg - RESULTS: \$ = 26° (SIZE CORRELATION THIS MAPPENDIX) 2) & URS PI - RESULTS: FUR PI = 16, Q'= 31° (SEL CHART THIS APPENDIX) 3) HALLIS THESIS \$'NC = 36 - 0,2665 (2 CLAY) For CF= 16, pric = 31.7° 5) CU TRIAXIAL TEST - SAMPLE WAS NOT DESCRIPTED AS 'ORGANIC', BUT DESCRIPTION BEST MATCHES THIS LAYER RESULTS: \$'=36.9", C'= 110" psf - PERMERBILITY: DIS - LOW = 0.0015 KV = 5 ×10-6 cm/s 141GH = 0.005 (GIEDSYNTEC , SEE AVG = 0.0023 (GIEDSYNTEC , SEE APPENDIX (4 SAMPLES TOO COURSE FOR DIS- VALUE * PER FHNA GEC 5, LOI & 20% SOIL PROPERTIES CONTROLLED 37 NON-ORGANIC PURTION .: REGULAR CORECLATIONS OK \$=30°, c'=0 psf DESIGN STRENGTH PARAMETER:



 Project/Proposal No. 01/. 1/497.013
 Calculated By MITR
 Date 6-29-09

 Project/Proposal Name
 CARDWAL ASH POLID
 Checked By
 MGR
 Date 1-2-09

 Subject
 STRIEMGTH 5
 PERM.
 Sheet 7 of 8

+ LAYER: VERY LO								
- DESCRIPTION : 1	VERY LOOSE	70 L	DOSE BRU	MUN ANIS	GV	FINI	07 3	
	MEDIUM							DOF
	WITH SILT						4.1000	
	1 1 1	,	Greening				1	
- NGS BANGE:				Earl 72	ø'	DON	E 7.1	
	Low	4		27.8		25		
		29		41.1			36°	
	Avg			33.6		30-	1	
		17-		00,0		00	51	1
	USIE	5 =	290	: c'=	0			
		F						
- PERMEABILITY	: USE GI	RAIN SI	ZE ANA	145.5				
· BORING CU-	PZ-BAP- 0	10904	SAMPL	E 21 À	- 20	06		
					5			
k. = 15	×10-2 cm/s	(500	Ganadia	-> Geos	wher I	1100	121.7	
<u>N - 1 - </u>	-10 -15	loce	appendix	GEUS	mee, i	1.117		
							11	
			hard in					
+ LAYER MED DE			ourwash	54112	GRAU	TEL		
+ LAYER : MED DE			ourwash	54~12	: GRAU	152		
	NSC SLA	CIAL			1		WIE ;	6
- DESCRIPTION :	NSC GLA MED DENSC	CIAL .	ENSE BRO	ond And	GIA	Y F	以化 ;	6
- DESCRIPTION :	NSC SLA	CIAL .	ENSE BRO	ond And	GIA	Y F	ihit, j	G
- DESCRIPTION :	NSC GLA MED DENSC	CIAL .	ENSE BRO	VE TO P	GIA	Y F	IAIE ;	ø
- DESCRIPTION :	NSC GLA MED DENSC	CIAL . TS A Equel	ANIS FI	WE TO A	MED SA	Y K INID,	以他; ;	6
- DESCRIPTION :	NSC GLA MED DENSC COARSE GI	TS A REAVEL	EQN	r = r = r	GIRAN MED SA	4 F 12112, 7.1	IXIE ;	6
- DESCRIPTION :	NSIC GLA MED DENSIC COARSE GA	TAL . TO P Equel 14	EQNIE BER ANIS IFIN EQNI 34.7	r $r$ $r$ $r$ $r$ $r$ $r$ $r$ $r$ $r$	GIRAN MED SA TATELE 31-3	4 F 12112, 7.1	INIE ;	6
- DESCRIPTION :	MED DENSE COARSE GA LOW HIGH	CIAL . 75 A EAVEL 14 69	EQN EQN 52.6	r = r = r = r	779782E 31-3: 741	4 F 12112, 7.1	1/1/12 7	CC .
- DESCRIPTION :	NSIC GLA MED DENSIC COARSE GA	TAL . TO P Equel 14	EQNIE BER ANIS IFIN EQNI 34.7	r = r = r = r	GIRAN MED SA TATELE 31-3	4 F 12112, 7.1	UNIE ;	6
- DESCRIPTION :	MED DENSE COARSE GA LOW HIGH	14 32	EQN EQN 52.6 47.2	$r = \frac{1}{2}$	7747525 31-3: 36°	4 F ANID, 7.1 2°	ixie ;	6
- DESCRIPTION :	MED DENSE COARSE GA LOW HIGH	14 32	EQN EQN 52.6	$r = \frac{1}{2}$	779782E 31-3: 741	4 F ANID, 7.1 2°	1/A1E ;	6
- DESCRIPTION :	MED DENSE COARSE GA LOW HIGH	14 32	EQN EQN 52.6 47.2	$r = \frac{1}{2}$	7747525 31-3: 36°	4 F ANID, 7.1 2°	WIE ;	6
- DESCRIPTION :	MED DENSE COARSE GA LOW HIGH	14 32	EQN EQN 52.6 47.2	2112 TO 7 22 7 2 4 - - - - - - - - - - - - -	7747525 31-3: 36°	4 F ANID, 7.1 2°	1XIE ;	6
- DESCRIPTION :	MED DENSE COARSE GA LOW HIGH AVE	14 32	EQN EQN EQN EQN 34.5 52.0 42.2 G' = 3 SATCIPLE	21/2 TO 7 21/2 TO 7 2/ 7 7 7 7 7 7 7 7 7 7 7 7 7	7747525 31-3: 36°	4 F ANID, 7.1 2°	IXIE ;	6
- DESCRIPTION :	MSC GLA MED DENSC COARSE GA LOW HIGH AVG	14 14 69 32 USE	EQN EQN EQN 52.( 42.2 () = 3	2112 TO 7 22 7 2 4 - - - - - - - - - - - - -	GIRAN MED SA 7 TABLE 31-3 741 36° C'=	4 K ANID, 7.1 2°		
- DESCRIPTION :	MSC GA MED DENSIC COARSE GA LOW ItiGIH AVG BOD	ILL ILL ILL ILL ILL ILL ILL ILL	EQN EQN EQN EQN 34.5 52.0 42.2 G' = 3 SATCIPLE	DIS	GIRAN MED SA 7 TABLE 31-3 741 36° C'=	4 K ANID, 7.1 2°	pend	
- DESCRIPTION :	MSC GLA MED DENSIC COARSE GA LOW ItiGIN AVE BOT O	IL IL IL IL IL IL IL IL IL IL	EQNI EQNI EQNI 34.5 52.6 42.2 Ø' = 3 SATCIPLE S-11	215 Dis	GIRAN MED SA 7 TABLE 31-3 741 36° C'=	4 K ANID, 7.1 2°		
- DESCRIPTION :	MSC GLA MED DENSIC COARSE GA LOW ItiGIH AVG BOT O	- 75 A - 75 A EAVEL 14 69 32 USE EINCG 903 905	EQN EQN EQN EQN 34.5 52.0 42.2 G' = 3 SATOPLE S-13	21/2 2/2 2/2 2/2 2/2 2/2 2/2 2/2	GIRAN MED SA 7 TABLE 31-3 741 36° C'=	4 K ANID, 7.1 2°		
- DESCRIPTION :	MSC GA MED DENSIC COARSE GA LOW ItiGIH AVG BO O O	2122	EQNI EQNI EQNI 52.0 47.7 52.0 47.7 52.0 47.7 52.1 52.1 5-13 5-24	Dis 0,09 0,19	GIRAN MED SA 7 TABLE 31-3 741 36° C'=	4 K ANID, 7.1 2°		



Project/Proposal No. 01/. 1/497. 013	Calculated By MTR	Date 7/15/09
Project/Proposal Name CARDILIAL ASH POND	Checked By	Date
Subject SEISMIC STRENGTH PARAMETERS	Sheet <u>8</u> of <u>8</u>	

PERFORM SEISMIC	STABILIN ANK	ALYSIS GUT	74 A	PSEUDOSMATIC	APPROA
USING LIMIT IEG		1			
=7 APPLY	HUKIZONITAL L		ATIC MOD	IEL EQUAL	70
THE PR	SEISMIC HAZARIS	L ACCELERA			
- ASSUMATEN EMA	L AMKMEANT FILL	LAYER W	L EXIM	Set UNIDIRAIN	IED
RESPONSE DURIN	USACE 'R' EN	uake even	7.		
SIRICE No C	U TEST DATA	IS AVAILABLIE	FOR TH	C ORIGINAL	FILL,
	RIGHT (2005) A				
BASED due	comparison, us	ie the follo	مسمدم ع	increase G +74 VAR	LUES
LAYER		C	d		
ORIGINAL EMBA)	SKYAIENT FILL	50 psf	22°		BLE 10.3 -owinor PG
	FURMICD IN BILG HT FOR SUISMIC	CLSI CAYER	2 - 2512	R-ENWELSPE	73
CXCG. CLEI		psf, \$=	240		
DRAINIED STRENG	ACIAL SUTWASH				
FOR PRAILIED AND	+64217	+-++			
NEWER EMBANK	MENT FILL LA	YER HAS SI	SFRICIENTS	GRAMULAR	MATERIAL
	WILL EXAMPLE			and the second se	1. 0.0,14
					PLATE 15

Soil no.	Description and reference	Index properties	<i>c'</i> (psf)	$\phi'$ (deg)	c _R (psf)	$\phi_{R}$ (deg)	dª (psf)	$\psi^b$ (deg)
1	Sandy clay (CL) material from Pilarcitos Dam;	Percent minus No. 200: 60–70 Liquid limit: 45	0	45	60	23	64	24.4
	envelope for low (0–10 psi) confining pressures. (Wong et al., 1983)	Plasticity index: 23	u	SE C:		7 Ø=	NIENT F ZZO	
2	Brown sandy clay from dam site in Rio Blanco, Colorado (Wong et al., 1983)	Percent minus No. 200: 25 Liquid limit: 34 Plasticity index: 12	200	31	700	15	782	16.7
3	Same as soil 1 except envelope fit to 0-100 psi range in confining pressure (Wong et al., 1983)	Percent minus No. 200: 60–70 Liquid limit: 45 Plasticity index: 23	0	34	300	15.5	327	16.8
4 .	Hirfanli Dam fill material (Lowe and Karafiath, 1960)	Percent minus No. 200: 82 Liquid limit: 32.4 Plastic limit: 19.4	0	35	1400	22.5	1716	26.9

### Table 10.3 Summary of Soil Properties Used in Comparison of R and $\tau_{ff}$ vs. $\sigma'_{fc}$ Strength Envelopes

^{*a*} Intercept of  $\tau_{ff}$  vs.  $\sigma'_{fc}$  envelope—can be calculated knowing c',  $\phi'$ ,  $c_R$ , and  $\phi_R$ . ^{*b*} Slope of  $\tau_{ff}$  vs.  $\sigma'_{fc}$  envelope—can be calculated knowing c',  $\phi'$ ,  $c_R$ , and  $\phi_R$ .




Figure 10.6 Slope used to compare simple, single-stage and rigorous, two-stage pseudostatic analyses.

## Table 10.4Summary of Pseudostatic Safety FactorsComputed Using Simple Single-Stage and RigorousTwo-Stage Procedures

	Case dry sl		Case submerge	
Soil	Single-stage analysis	Two-stage analysis	Single-stage analysis	Two-stage analysis
1	0.95	1.06	0.83	0.95
2	1.56	1.77	1.59	1.79
3	1.07	1.19	1.10	1.21
4	2.76	3.42	2.83	3.49




Figure 10.7 Comparison of factors of safety by simplified single-stage pseudostatic and more rigorous two-stage pseudostatic analyses.

used for cases where significant (more than 15 to 20%) strength losses are not anticipated.

#### **POSTEARTHQUAKE STABILITY ANALYSES**

Following an earthquake, the stability of a slope may be diminished because cyclic loading has reduced the shear strength of the soil. The reductions in shear strength are generally treated differently depending on whether or not liquefaction occurs. Stability follow-



DRAINED SHEAR STRENGTH PARAMETER CORRELATION

% Passing Clay Sized

Project No: 011-11497-014 Project: Gavin Plant Bottom Ash Pond Investigation Date: 5/29/09

### Reference:

Drained Shear Strength Parameters for Analysis of Landslides. Timothy D. Stark; Hangseok Choi; and Sean McCone. Journal of Geotechnical Engineering, May 2005. pp 575 - 588

### Purpose:

Estimate effective stress, or drained, shear strength parameters of cohesive soils through emperical correlations using laboratory index testing and the effective normal stress. Secant residual and secant fully softened friction angles can be estimated from charts developed by Stark et al.

### Laboratory Data

Soil Layer: Newer Embankment Fill

Statistical Results from <u>4</u> Borings

				#200 Sieve	Fraction
	<u>PI</u>	<u>LL</u>	MC	<u>(.075 mm)</u>	<u>(.002 mm)</u>
Number in Statistical Sample	12	12	16	9	8
Minimum	9	25	10	24	8
Maximum	18	37	31	79	21
Mean	12.1	30.3	16.3	41.6	12.1
Median	11	28.5	14.5	31	11
Mode	10	27	16	31	12
Std Dev	3.2	4.5	5.4	18.9	4.6
Design Value	10	27	-	-	12

### Adjustment Factor for ASTM Derived Values

ball-milled derived LL	— = .003 (ASTM derived LL) + 1.23	$LL_{ASTM} =$	27
ASTM derived LL	— – .003 (ASTM derived LL) + 1.23	LL _{BM} =	35.4

ball-milled derived CF ASTM derived CF = 0.0003 (ASTM derived CF)2 - 0.037(ASTM derived CF) + 2.254

	CF _{ASTM} =	12
where: LL = Liquid Limit	CF _{BM} =	22.2
CF = Clay-sized Fraction		








Fig. 5. Secant fully softened friction angle relationships with liquid limit, clay-size fraction, and effective normal stress

	-	Effective Normal Stress			
		50 kPa	100 kPa		
Sized tion,	CF ≤ 20	32.5°	31.5°		
Clay Sized Fraction,	$25 \le CF \le 45 \qquad 32.5^{\circ}$		30°		
Design Frict	tion Angle Valu	e	31°		

Secant Fully Softened Friction Angle



DRAINED SHEAR STRENGTH PARAMETER CORRELATION

Project No: 011-11497-014 Gavin Plant Bottom Ash Pond Investigation Project:

Date: 5/29/09

### **Reference:**

Drained Shear Strength Parameters for Analysis of Landslides. Timothy D. Stark; Hangseok Choi; and Sean McCone. Journal of Geotechnical Engineering, May 2005. pp 575 - 588

### **Purpose:**

Estimate effective stress, or drained, shear strength parameters of cohesive soils through emperical correlations using laboratory index testing and the effective normal stress. Secant residual and secant fully softened friction angles can be estimated from charts developed by Stark et al.

### Laboratory Data

Soil Layer: Original Embankment Fill

Statistical Results from 3 Borings

Statistical Results from <u>3</u> Bc	% Passing	Clay Sized			
				#200 Sieve	Fraction
	PI	<u>LL</u>	MC	<u>(.075 mm)</u>	<u>(.002 mm)</u>
Number in Statistical Sample	6	6	10	5	4
Minimum	14	32	15	76	23
Maximum	24	49	33	96	32
Mean	19.8	43.3	22.5	86.2	28.0
Median	20.5	47.5	22	86	28.5
Mode	24	48	22	#N/A	#N/A
Std Dev	4.4	7.4	5.1	8.1	3.7
Design Value	24	48	-	-	28

### Adjustment Factor for ASTM Derived Values

ball-milled derived LL	— = .003 (ASTM derived LL) + 1.23	LL _{ASTM} =	48
ASTM derived LL	— – .003 (ASTM derived LL) + 1.23	$LL_{BM} =$	66.0

ball-milled derived CF ASTM derived CF — = 0.0003 (ASTM derived CF)2 - 0.037(ASTM derived CF) + 2.254

	CF _{ASTM} =	28
where: LL = Liquid Limit	CF _{BM} =	40.7
CF = Clay-sized Fraction		








Fig. 5. Secant fully softened friction angle relationships with liquid limit, clay-size fraction, and effective normal stress

Effective Normal Stress, kPa	50
Secant Fully Softened Friction Angle	30°



DRAINED SHEAR STRENGTH PARAMETER CORRELATION

% Passing Clay Sized

Project No: 011-11497-014 Project: Gavin Plant Bottom Ash Pond Investigation Date: 5/29/09

### Reference:

Drained Shear Strength Parameters for Analysis of Landslides. Timothy D. Stark; Hangseok Choi; and Sean McCone. Journal of Geotechnical Engineering, May 2005. pp 575 - 588

### Purpose:

Estimate effective stress, or drained, shear strength parameters of cohesive soils through emperical correlations using laboratory index testing and the effective normal stress. Secant residual and secant fully softened friction angles can be estimated from charts developed by Stark et al.

### Laboratory Data

Soil Layer: Organic Clayey Silt

Statistical Results from <u>7</u> Borings

				#200 Sieve	Fraction
	<u>PI</u>	<u>LL</u>	MC	<u>(.075 mm)</u>	<u>(.002 mm)</u>
Number in Statistical Sample	17	17	20	21	19
Minimum	3	30	34	56	12
Maximum	20	50	54	97	44
Mean	13.5	40.6	42.5	78.2	19.8
Median	15	41	43	81	18
Mode	16	45	43	81	16
Std Dev	4.6	5.3	4.4	10.7	7.0
Design Value	16	45	-	-	20.0

### Adjustment Factor for ASTM Derived Values

ball-milled derived LL	— = .003 (ASTM derived LL) + 1.23	LL _{ASTM} =	45
ASTM derived LL	003 (AS IN derived LL) + 1.23	$LL_{BM} =$	61.4

ball-milled derived CF ASTM derived CF = 0.0003 (ASTM derived CF)2 - 0.037(ASTM derived CF) + 2.254

	CF _{ASTM} =	20.0
where: LL = Liquid Limit	CF _{BM} =	32.7
CF = Clay-sized Fraction		








Fig. 5. Secant fully softened friction angle relationships with liquid limit, clay-size fraction, and effective normal stress

Secar	nt Fully Softene	Effective No	•
		100 kPa	400 kPa
Sized tion,	CF ≤ 20	27.5°	24°
Clay Sized Fraction,	25 ≤ CF ≤ 45	-	-
<b>Design Frict</b>	tion Angle Valu	e	26°

### cant Fully Softened Friction Angle



DRAINED SHEAR STRENGTH PARAMETER CORRELATION

Project No: 011-11497-014 Project: Gavin Plant Bottom Ash Pond Investigation Date: 5/29/09

### Reference:

Drained Shear Strength Parameters for Analysis of Landslides. Timothy D. Stark; Hangseok Choi; and Sean McCone. Journal of Geotechnical Engineering, May 2005. pp 575 - 588

### Purpose:

Estimate effective stress, or drained, shear strength parameters of cohesive soils through emperical correlations using laboratory index testing and the effective normal stress. Secant residual and secant fully softened friction angles can be estimated from charts developed by Stark et al.

### Laboratory Data

Soil Layer: Alluvium Silt and Clay

Statistical Results from <u>6</u> Bo	% Passing	Clay Sized			
				#200 Sieve	Fraction
	<u>PI*</u>	LL*	MC	<u>(.075 mm)</u>	<u>(.002 mm)</u>
Number in Statistical Sample	4	4	10	12	10
Minimum	7	34	22	48	3
Maximum	15	38	38	96	28
Mean	12.5	36.0	29.0	76.8	11.0
Median	14	36	28.5	76.5	6.5
Mode	15	#N/A	26	91	5
Std Dev	3.8	1.8	5.4	15.9	8.5
*Does not include results from 'Non-Plastic'	samples.				
Design Value	15	36	-	-	10.0

### **Adjustment Factor for ASTM Derived Values**

ball-milled derived LL	– = .003 (ASTM derived LL) + 1.23	LL _{ASTM} =	36
ASTM derived LL	=003 (ASTM derived LL) + 1.25	LL _{BM} =	48.2

ball-milled derived CF ASTM derived CF = 0.0003 (ASTM derived CF)2 - 0.037(ASTM derived CF) + 2.254

where: LL = Liquid Limit CF = Clay-sized Fraction CF_{BM} = 19.1

### PLATE 23

10.0

CF_{ASTM} =









Fig. 5. Secant fully softened friction angle relationships with liquid limit, clay-size fraction, and effective normal stress



### Secant Fully Softened Friction Angle




Figure 74. Relationship between  $\phi'$  and PI (Terzaghi, Peck, and Mesri, 1996).

Report No. FHWA-IF-02-034 Geotechnical Engineering Circular No. 5 Evaluation of Soil and Rock Properties April, 2002

LAYER	<u> </u>	4'
EMBANKMENT EXTANSION FILL	10	33°
ORIGINIAL IEMBANKMENT FILL	24	30°
ALLUNUM SILTAND CLAY	15	31.5
ORGANIC CLAYEN SILT	16	31°

TABLE 3.28 $3/a^3 = \frac{3^2}{62.4}$ COMMON PROPERTIES OF COHESIONLESS SOILS							
Material	Compactness	D _R , %	N*	$\frac{\gamma}{g/cm^3} \begin{pmatrix} \lambda^{r} \\ \rho^{r} \\ \rho^{r} \end{pmatrix}$	Void ratio c	VSAT (PCF)	Strength‡ ¢
GW:well-graded	Dense	75	90	2.21 138	0.22	149	40
gravels, gravel-	Medium dense	50	55	2.08 129,8	0.28	143.5	36
sand mixtures	Loose	25	<28	1.97 123	0.36	139.5	32
GP: poorly graded	Dense	75	70	2.04 127.4	0.33	143	38
gravels, gravel-	Medium dense	50	50	[1.92] 120	0.39	131.5	35
sand mixtures	Loose	25	<20	1.83 /14.2	0.47	134	32
SW: well-graded sands,	Dense	75	65	1.89 /18	0.43	136.8	37
gravelly sands	Medium dense	50	35	(1.79) 111.7	0.49	132.2	34
	Loose	25	<15	11.70 106.1	0.57	128.8	30
SP: poorly graded	Dense	75	50	1.76 /04.9	0.52	131-3	
sands, gravelly	Medium dense	50	30	1.67 104.2	0.60	127.6	33
sands	Loose	25	<10	1.59 9 9.3	0.65	124	29
SM: silty sands	Dense	75	45	1.65 /03	0.62	127	35
	Medium dense	50	25	1.55 27	0.74	123.5	32
	Loose	25	<8	1.49 93	0.80	120,7	29
ML: inorganic silts, very	Dense	75	35	.1.49 93	0.80	120.7	33
fine sands	Medium dense	50	20	1.41 88	0.90	117.6	31
	Loose	25	<4	1.35 84.3	1.0	115.5	27

*N is blows per foot of penetration in the SPT. Adjustments for gradation are after Burmister (1962).¹³ See Table 3.23 for general relationships of D_B vs. N.

†Density given is for  $G_s = 2.65$  (quartz grains).

Friction angle  $\phi$  depends on mineral type, normal stress, and grain angularity as well as  $D_R$  and gradation (see Fig. 3.63).

 $V_{sar} = \frac{(4s + e)V_w}{1 + e}$ 1 3/1m3 = 9.81 KN/m3 YEAT - Yd + CYW

198 INVESTIGATION METHODS AND PROCEDURES

### Newer Embankment Fill: Permeability

D15 Range = 0,002 - 0,080




Figure 91. Range of hydraulic conductivity based on grain size (after GeoSyntec, 1991).

Considering the site geology, the laboratory and field data should be tabulated with other known data for the sample/test location and with depth, soil/rock type, grain size distribution, Atterberg limits, and water content. This table should also include important test information such as: stress conditions, gradients, and test method. Once this table is constructed it will be much easier to group like soil types and k values, to delineate distinct areas within the site, and to eliminate potentially erroneous data. Once these values have been grouped together and potentially erroneous values eliminated, it may be useful to compute an average value for each grouping. When averaging, the log of the hydraulic conductivity value must be taken before performing an arithmetic mean or incorrect results will be produced. First, the logarithm of each value should be taken. Second, an average value should be calculated from these logarithmic values. Finally, the antilog of this average value should be taken to calculate the average hydraulic conductivity value. Table 35 illustrates how to calculate the mean of the log of k data and compares this value with an incorrect direct arithmetic mean.

Geotechnical Engineering Circular No. 5 Evaluation of Soil and Rock Properties Glacial outwash sand and gravel.





Figure 91. Range of hydraulic conductivity based on grain size (after GeoSyntec, 1991).

Considering the site geology, the laboratory and field data should be tabulated with other known data for the sample/test location and with depth, soil/rock type, grain size distribution, Atterberg limits, and water content. This table should also include important test information such as: stress conditions, gradients, and test method. Once this table is constructed it will be much easier to group like soil types and k values, to delineate distinct areas within the site, and to eliminate potentially erroneous data. Once these values have been grouped together and potentially erroneous values eliminated, it may be useful to compute an average value for each grouping. When averaging, the log of the hydraulic conductivity value must be taken before performing an arithmetic mean or incorrect results will be produced. First, the logarithm of each value should be taken. Second, an average value should be taken to calculate the average hydraulic conductivity value. Table 35 illustrates how to calculate the mean of the log of k data and compares this value with an incorrect direct arithmetic mean.


Geotechnical Engineering Circular No. 5 Evaluation of Soil and Rock Properties.




# PERMEABILITY TEST DATA AND COMPUTATION SHEET BBCK




Job Number:	011.11497.	1.11497.013 Date: 5/6-7/2009 Maximum							
Project Name:	Cardinal A	sh Pond Inv	estigation	Boring:	CD-PZ-B	AP-0907	Optimum	Moisture Content:	
Project Location:	Brilliant, Ohio			Sample:	ST-6A S	Sec. II	_	% Compaction.:	
Tested By:	PJM Depth: 8		8.5' to 9.9	9'	_	Optimum +/-:			
Remarks:	marks:						_	Natural:	Х
Material:	FILL : Hard	brown, gray	and dark-g	ray silty clay	inter-mix	ed with orga	nic silt, trace	Remolded:	
	fine to coars					0			
mple:			<u>Te</u> s	st Conditions:		<u> </u>	Moisture Content:	Before Test	After Test
Initial Length:	5.5945 in	= 14.210 cm	Ch	amber Pressure:	62 psi		Pan No. =	D	D
nal Ave. Length (L):	5.6042 in	= 14.235 cm		Back Pressure:	58 psi		Wet Wt. + Pan =	1144.17	1157.03
Diameter:	2.8765 in	= 7.31 cm	Co	nfining Pressure:	4 psi		Dry Wt. + Pan =	896.92	896.92
Area (A):	6.499 sq in	= 41.93 sq cm		Temp. @ Start:	22.5 °C		Wt. of Pan =	0.00	0.00
Volume (V):	36.356 cu in	= 595.77 cu cm		Temp. @ End:	22.5 °C	_	Wt. of Dry Soil =	896.92	896.92
	1144.17 grams			Average Temp.:	22.5 °C		Wt. of Water =	247.25	260.11
Unit Wet Wt.:				B Parameter:	0.96	_	% Moisture =	27.57	29.00
	93.99 pcf			·······					
Chir Dry Wt.	00.00 poi		Di.	pette Pressures Du	urina Test		% SATURATIO	93.80	98.30
			<u></u>			- 4000.0 am			30.30
				Top Pipette:		= 4220.3 cm	_S.G.(est) =	2.7000	
<u>ette:</u>		= 0.8725 sq cm		Bottom Pipette:	58 psi	= 4079.6 cm	_		
$=$ $\frac{\mathbf{a} \cdot \mathbf{L}}{1 - 1} \ln \left( \frac{1}{2} \right)$	$\frac{h_1}{h_2}$	a L	= Length of Sar	-Sectional Area		$h_2 = Head Loss Ad$	(t ₂ - t ₁ ) cross Permeamete cross Permeamete ithm (Base e = 2.7	r/Specimen at $t_2$	
$a = \frac{a \cdot L}{ln} \ln \left( \frac{1}{2} \right)$	<u> </u>	a L	= Pipette Cross = Length of Sar	-Sectional Area		$h_1 = Head Loss Adh_2 = Head$	cross Permeamete	r/Specimen at $t_2$	
l = ln   -	<u> </u>	a L	= Pipette Cross = Length of Sar	-Sectional Area		$h_1 = Head Loss Adh_2 = Head$	cross Permeamete cross Permeamete ithm (Base e = 2.7	r/Specimen at $t_2$	Temp. Cor
$a = \frac{a \cdot L}{ln} \ln \left( \frac{1}{2} \right)$	<u> </u>	a L	= Pipette Cross = Length of Sar	s-Sectional Area nple s-Sectional Area		h ₁ = Head Loss A h ₂ = Head Loss A n = Natural Logar	cross Permeamete cross Permeamete ithm (Base e = 2.7	r/Specimen at $t_2$	Temp. Cor Permeabili
$=$ $\frac{\mathbf{a} \cdot \mathbf{L}}{-1} \ln \left( \frac{1}{2} \right)$	<u> </u>	a L A	= Pipette Cross = Length of Sar = Sample Cross	-Sectional Area mple s-Sectional Area Hydraulic Head		h ₁ = Head Loss Ar h ₂ = Head Loss Ar n = Natural Logar Hydraulic Head	cross Permeamete cross Permeamete ithm (Base e = 2.7	r/Specimen at $t_2$	
$=$ $\frac{\mathbf{a} \cdot \mathbf{L}}{-1} \ln \left( \frac{1}{2} \right)$		a L A Time Interval	= Pipette Cross = Length of Sar = Sample Cross	-Sectional Area mple s-Sectional Area Hydraulic Head Headwater	Bottom	h ₁ = Head Loss Ar h ₂ = Head Loss Ar n = Natural Logar Hydraulic Head Tailwater	tim (Base e = 2.7 Head Loss	r/Specimen at $t_2$	Permeabili
$=\frac{\mathbf{a}\cdot\mathbf{L}}{2\cdot\mathbf{A}\cdot\Delta\mathbf{t}}\ln\left(\frac{1}{2}\right)$	Time	a L A Time Interval Δt	= Pipette Cross = Length of Sar = Sample Cross Top Pipette	-Sectional Area mple s-Sectional Area Hydraulic Head Headwater H ₁	Bottom Pipette	h ₁ = Head Loss Ar h ₂ = Head Loss Ar n = Natural Logar Hydraulic Head Tailwater H ₂	Head Loss h = H ₁ -H ₂	r/Specimen at t ₂ 1828)	Permeabili k
$= \frac{\mathbf{a} \cdot \mathbf{L}}{2 \cdot \mathbf{A} \cdot \Delta t} \ln \left( \frac{1}{2} \right)$ Date	Time Readings	a L A Time Interval Δt Seconds	= Pipette Cross = Length of Sar = Sample Cross Top Pipette cc	-Sectional Area mple s-Sectional Area Hydraulic Head Headwater H ₁ cm	Bottom Pipette cc	h ₁ = Head Loss Ar h ₂ = Head Loss Ar n = Natural Logar Hydraulic Head Tailwater H ₂ cm	Head Loss h = H ₁ -H ₂ cm	r/Specimen at t ₂ 1828)	Permeabili k cm/sec
$= \frac{\mathbf{a} \cdot \mathbf{L}}{2 \cdot \mathbf{A} \cdot \Delta t} \ln \left( \frac{1}{2} \right)$ Date 5/6/2009	Time Readings 9:45 AM	a L A Time Interval Δt Seconds 0.00	Top Pipette Cross = Length of Sar = Sample Cross Top Pipette cc 48.45	-Sectional Area mple s-Sectional Area Hydraulic Head Headwater H ₁ cm 4092.08	Bottom Pipette cc 14.20	h ₁ = Head Loss Ar h ₂ = Head Loss Ar n = Natural Logar Hydraulic Hear Tailwater H ₂ cm 4272.01	Head Loss $h = H_1-H_2$ cm -179.93	r/Specimen at t ₂ 1828) ڈn (h ₁ /h ₂₎ –	Permeabili k cm/sec
$= \frac{\mathbf{a} \cdot \mathbf{L}}{2 \cdot \mathbf{A} \cdot \Delta t} \ln \left( \frac{1}{2} \right)$ Date 5/6/2009 5/6/2009	Time Readings 9:45 AM 10:51 AM	a L A Time Interval Δt Seconds 0.00 3,960	Top Pipette Cross = Length of Sar = Sample Cross Top Pipette cc 48.45 48.40	-Sectional Area mple s-Sectional Area Hydraulic Head Headwater H ₁ cm 4092.08 4092.14	Bottom Pipette cc 14.20 14.45	h ₁ = Head Loss Ar h ₂ = Head Loss Ar n = Natural Logar Hydraulic Head Tailwater H ₂ cm 4272.01 4271.73	Head Loss h = H ₁ -H ₂ cm -179.93 -179.59	r/Specimen at t ₂ 1828) 	Permeabili k cm/sec - 6.740E-08
$= \frac{\mathbf{a} \cdot \mathbf{L}}{2 \cdot \mathbf{A} \cdot \Delta t} \ln \left( \frac{1}{2} \right)$ Date 5/6/2009 5/6/2009 5/6/2009	Time Readings 9:45 AM 10:51 AM 12:15 PM	a L A Time Interval Δt Seconds 0.00 3,960 5,040	Top Pipette Cross = Length of Sar = Sample Cross Top Pipette cc 48.45 48.40 48.20	-Sectional Area mple s-Sectional Area Hydraulic Head Headwater H ₁ cm 4092.08 4092.14 4092.36	Bottom Pipette cc 14.20 14.45 14.65	h ₁ = Head Loss Ar h ₂ = Head Loss Ar n = Natural Logar Hydraulic Head Tailwater H ₂ cm 4272.01 4271.73 4271.50	Head Loss h = H ₁ -H ₂ cm -179.93 -179.13	r/Specimen at t ₂ 1828) 	Permeabili k cm/sec - 6.740E-08 7.077E-08
$= \frac{\mathbf{a} \cdot \mathbf{L}}{2 \cdot \mathbf{A} \cdot \Delta t} \ln \left( \frac{1}{2} \right)$ Date $\frac{5/6/2009}{5/6/2009}$ $\frac{5}{6}/2009}$	Time Readings 9:45 AM 10:51 AM 12:15 PM 1:45 PM	a L A Time Interval Δt Seconds 0.00 3,960 5,040 5,400	Top Pipette Cross = Length of Sar = Sample Cross Top Pipette cc 48.45 48.40 48.20 48.05	-Sectional Area mple s-Sectional Area Hydraulic Head Headwater H ₁ cm 4092.08 4092.14 4092.36 4092.54	Bottom Pipette cc 14.20 14.45 14.65 15.00	h ₁ = Head Loss Ar h ₂ = Head Loss Ar n = Natural Logar Hydraulic Head Tailwater H ₂ cm 4272.01 4271.73 4271.50 4271.09	Head Loss h = H ₁ -H ₂ cm -179.93 -179.13 -178.56	r/Specimen at t ₂ 1828) ln (h ₁ /h ₂ ) - 0.00191 0.00256 0.00320	Permeabili k cm/sec - 6.740E-08 7.077E-08 8.280E-08
$= \frac{a \cdot L}{2 \cdot A \cdot \Delta t} \ln \left( \frac{1}{2} \right)$ Date 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/200 5/6/200 5/6/200 5/6/200 5/6/2009 5/6/2009	Time Readings 9:45 AM 10:51 AM 12:15 PM 1:45 PM 3:17 PM	a L A Time Interval Δt Seconds 0.00 3,960 5,040 5,040 5,520	= Pipette Cross = Length of Sar = Sample Cross Top Pipette cc 48.45 48.40 48.20 48.05 47.85	-Sectional Area mple s-Sectional Area Hydraulic Head Headwater H ₁ cm 4092.08 4092.14 4092.36 4092.54 4092.77	Bottom Pipette cc 14.20 14.45 14.65 15.00 15.25	h ₁ = Head Loss Ar h ₂ = Head Loss Ar n = Natural Logar Hydraulic Head Tailwater H ₂ cm 4272.01 4271.73 4271.50 4271.09 4270.81	Head Loss h = H ₁ -H ₂ cm -179.93 -179.13 -178.56 -178.04	r/Specimen at t ₂ 1828)	Permeabili k cm/sec - 6.740E-08 7.077E-08 8.280E-08 7.312E-08
$= \frac{a \cdot L}{2 \cdot A \cdot \Delta t} \ln \left( \frac{1}{2} \right)$ Date 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/200 5/6/200 5/6/200 5/6/200 5/6/2009 5/6/2009	Time Readings 9:45 AM 10:51 AM 12:15 PM 1:45 PM 3:17 PM	a L A Time Interval Δt Seconds 0.00 3,960 5,040 5,040 5,520	= Pipette Cross = Length of Sar = Sample Cross Top Pipette cc 48.45 48.40 48.20 48.05 47.85	-Sectional Area mple s-Sectional Area Hydraulic Head Headwater H ₁ cm 4092.08 4092.14 4092.36 4092.54 4092.77	Bottom Pipette cc 14.20 14.45 14.65 15.00 15.25	h ₁ = Head Loss Ar h ₂ = Head Loss Ar n = Natural Logar Hydraulic Head Tailwater H ₂ cm 4272.01 4271.73 4271.50 4271.09 4270.81	Head Loss h = H ₁ -H ₂ cm -179.93 -179.13 -178.56 -178.04	r/Specimen at t ₂ 1828)	Permeabili k cm/sec - 6.740E-08 7.077E-08 8.280E-08 7.312E-08
$= \frac{a \cdot L}{2 \cdot A \cdot \Delta t} \ln \left( \frac{1}{2} \right)$ Date 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/200 5/6/200 5/6/200 5/6/200 5/6/2009 5/6/2009	Time Readings 9:45 AM 10:51 AM 12:15 PM 1:45 PM 3:17 PM	a L A Time Interval Δt Seconds 0.00 3,960 5,040 5,040 5,520	= Pipette Cross = Length of Sar = Sample Cross Top Pipette cc 48.45 48.40 48.20 48.05 47.85	-Sectional Area mple s-Sectional Area Hydraulic Head Headwater H ₁ cm 4092.08 4092.14 4092.36 4092.54 4092.77	Bottom Pipette cc 14.20 14.45 14.65 15.00 15.25	h ₁ = Head Loss Ar h ₂ = Head Loss Ar n = Natural Logar Hydraulic Head Tailwater H ₂ cm 4272.01 4271.73 4271.50 4271.09 4270.81	Head Loss h = H ₁ -H ₂ cm -179.93 -179.13 -178.56 -178.04	r/Specimen at t ₂ 1828)	Permeabili k cm/sec - 6.740E-08 7.077E-08 8.280E-08 7.312E-08
$= \frac{a \cdot L}{2 \cdot A \cdot \Delta t} \ln \left( \frac{1}{2} \right)$ Date 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009	Time Readings 9:45 AM 10:51 AM 12:15 PM 1:45 PM 3:17 PM	a L A Time Interval Δt Seconds 0.00 3,960 5,040 5,040 5,520	= Pipette Cross = Length of Sar = Sample Cross Top Pipette cc 48.45 48.40 48.20 48.05 47.85	-Sectional Area mple s-Sectional Area Hydraulic Head Headwater H ₁ cm 4092.08 4092.14 4092.36 4092.54 4092.77	Bottom Pipette cc 14.20 14.45 14.65 15.00 15.25	h ₁ = Head Loss Ar h ₂ = Head Loss Ar n = Natural Logar Hydraulic Head Tailwater H ₂ cm 4272.01 4271.73 4271.50 4271.09 4270.81	Head Loss h = H ₁ -H ₂ cm -179.93 -179.13 -178.56 -178.04	r/Specimen at t ₂ 1828)	Permeabili k cm/sec - 6.740E-08 7.077E-08 8.280E-08 7.312E-08
$= \frac{a \cdot L}{2 \cdot A \cdot \Delta t} \ln \left( \frac{1}{2} \right)$ Date 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009	Time Readings 9:45 AM 10:51 AM 12:15 PM 1:45 PM 3:17 PM	a L A Time Interval Δt Seconds 0.00 3,960 5,040 5,040 5,520	= Pipette Cross = Length of Sar = Sample Cross Top Pipette cc 48.45 48.40 48.20 48.05 47.85	-Sectional Area mple s-Sectional Area Hydraulic Head Headwater H ₁ cm 4092.08 4092.14 4092.36 4092.54 4092.77	Bottom Pipette cc 14.20 14.45 14.65 15.00 15.25	h ₁ = Head Loss Ar h ₂ = Head Loss Ar n = Natural Logar Hydraulic Head Tailwater H ₂ cm 4272.01 4271.73 4271.50 4271.09 4270.81	Head Loss h = H ₁ -H ₂ cm -179.93 -179.13 -178.56 -178.04	r/Specimen at t ₂ 1828)	Permeabili k cm/sec - 6.740E-08 7.077E-08 8.280E-08 7.312E-08
$= \frac{a \cdot L}{2 \cdot A \cdot \Delta t} \ln \left( \frac{1}{2} \right)$ Date 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009	Time Readings 9:45 AM 10:51 AM 12:15 PM 1:45 PM 3:17 PM	a L A Time Interval Δt Seconds 0.00 3,960 5,040 5,040 5,520	= Pipette Cross = Length of Sar = Sample Cross Top Pipette cc 48.45 48.40 48.20 48.05 47.85	-Sectional Area mple s-Sectional Area Hydraulic Head Headwater H ₁ cm 4092.08 4092.14 4092.36 4092.54 4092.77	Bottom Pipette cc 14.20 14.45 14.65 15.00 15.25	h ₁ = Head Loss Ar h ₂ = Head Loss Ar n = Natural Logar Hydraulic Head Tailwater H ₂ cm 4272.01 4271.73 4271.50 4271.09 4270.81	Head Loss h = H ₁ -H ₂ cm -179.93 -179.13 -178.56 -178.04	r/Specimen at t ₂ 1828)	Permeabili k cm/sec - 6.740E-08 7.077E-08 8.280E-08 7.312E-08
$= \frac{a \cdot L}{2 \cdot A \cdot \Delta t} \ln \left( \frac{1}{2} \right)$ Date 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009	Time Readings 9:45 AM 10:51 AM 12:15 PM 1:45 PM 3:17 PM	a L A Time Interval Δt Seconds 0.00 3,960 5,040 5,040 5,520	= Pipette Cross = Length of Sar = Sample Cross Top Pipette cc 48.45 48.40 48.20 48.05 47.85	-Sectional Area mple s-Sectional Area Hydraulic Head Headwater H ₁ cm 4092.08 4092.14 4092.36 4092.54 4092.77	Bottom Pipette cc 14.20 14.45 14.65 15.00 15.25	h ₁ = Head Loss Ar h ₂ = Head Loss Ar n = Natural Logar Hydraulic Head Tailwater H ₂ cm 4272.01 4271.73 4271.50 4271.09 4270.81	Head Loss h = H ₁ -H ₂ cm -179.93 -179.13 -178.56 -178.04	r/Specimen at t ₂ 1828)	Permeabili k cm/sec - 6.740E-08 7.077E-08 8.280E-08 7.312E-08
$= \frac{a \cdot L}{2 \cdot A \cdot \Delta t} \ln \left( \frac{1}{2} \right)$ Date 5/6/2009 5/6/2009 5/6/2009 5/6/2009 5/6/2009	Time Readings 9:45 AM 10:51 AM 12:15 PM 1:45 PM 3:17 PM	a L A Time Interval Δt Seconds 0.00 3,960 5,040 5,040 5,520	= Pipette Cross = Length of Sar = Sample Cross Top Pipette cc 48.45 48.40 48.20 48.05 47.85	-Sectional Area mple s-Sectional Area Hydraulic Head Headwater H ₁ cm 4092.08 4092.14 4092.36 4092.54 4092.77	Bottom Pipette cc 14.20 14.45 14.65 15.00 15.25	h ₁ = Head Loss Ar h ₂ = Head Loss Ar n = Natural Logar Hydraulic Head Tailwater H ₂ cm 4272.01 4271.73 4271.50 4271.09 4270.81	Head Loss h = H ₁ -H ₂ cm -179.93 -179.13 -178.56 -178.04	r/Specimen at t ₂ 1828)	Permeabili k cm/sec - 6.740E-08 7.077E-08 8.280E-08 7.312E-08







### **USGS National Seismic Hazard Maps - 2008**


Peak Horizontal Acceleration with 2% Probability of Exceedence in 50 Years





### **Appendix IV – Limit Equilibrium Analysis**














#### Fine Grained Soil Liquefaction Screening Cardinal Bottom Ash Pond

#### Layer: NEWER EMBANKMENT FILL

BORING	SAMPLE	SAMPLE	NATURAL	LIQUID	PLASTIC	PLASTIC	GRAVEL	SAND	SILT	CLAY	CLAY	SILT/CLAY	USCS	Fines Cont	ent and Plasticity I	ndex Screening	
NUMBER	NUMBER	DEPTH	MOISTURE	LIMIT	LIMIT	INDEX				.005 mm	.002 mm		CLASSIFICATION		% Passing		Is Soil Sample Liquefiable
			CONTENT	%	%	%	%	%	%	%	%	%		LL < 35	0.005 < 15	WC < 0.9LL	(meets all three criteria)
BAP-0901	S-5	7.75	16	28	18	10								Yes	-	Yes	-
BAP-0901	S-9	13.75	13	27	17	10								Yes	-	Yes	-
BAP-0901	S-12	18.25	14	37	24	13	7	32	49	23	12	61	SANDY LEAN CLAY CL	No	No	Yes	No
BAP-0902	S-11	16.75	24	37	19	18								No	-	Yes	No
BAP-0902	S-12	18.25	21	35	17	18	8	37	33	28	21	54	SANDY LEAN CLAY CL	No	No	Yes	No
BAP-0902	S-13	19.75	31	29	17	12	1	20	62	28	17	79	LEAN CLAY with SAND CL	Yes	No	No	No
BAP-0904	S-9	13.75	16	35	21	14								No	-	Yes	No
BAP-0906	S-3	4.75	15	27	17	10								Yes	-	Yes	-
BAP-0906	S-8	12.75					30	40	22	13	9	31		-	Yes	-	-
BAP-0906	S-11	17.25	14	31	19	12	18	44	26	18	12	38	CLAYEY SAND with GRAVEL SC	Yes	No	Yes	No

#### Layer: ORIGINAL EMBANKMENT FILL

BORING	SAMPLE	SAMPLE	NATURAL	LIQUID	PLASTIC	PLASTIC	GRAVEL	SAND	SILT	CLAY	CLAY	SILT/CLAY	USCS
NUMBER	NUMBER	DEPTH	MOISTURE	LIMIT	LIMIT	INDEX				.005 mm	.002 mm		CLASSIFICATION
			CONTENT	%	%	%	%	%	%	%	%	%	
BAP-0903	S-2	3.25	24	48	24	24	0	8	60	45	32	92	LEAN CLAY CL
BAP-0903	S-5	7.75	20	36	20	16	0	14	58	38	28	86	LEAN CLAY CL
BAP-0905	S-3	4.75	17	32	18	14	0	25	53	30	23	76	LEAN CLAY with SAND CL
BAP-0905	S-5	7.75	22	48	24	24							
BAP-0907	S-5	7.75	23	49	26	23							
BAP-0907	S-6A	9.25	28	47	29	18	0	5	67	43	29	96	SILT ML

Fines Content	and Plasticity I	ndex Screening	
	% Passing	Is Soil Sample Liquefiable	
LL < 35	0.005 < 15	WC < 0.9LL	(meets all three criteria)
No	No	Yes	No
No	No	Yes	No
Yes	No	Yes	No
No	-	Yes	No
No	-	Yes	No
No	No	Yes	No

# **Appendix V – 2009 Investigation Report Text**

August 4, 2009 011-11497-013



Mr. Pedro Amaya, P.E. American Electric Power 1 Riverside Plaza Columbus, OH 43215

Re: Subsurface Investigation and Analysis Bottom Ash Pond Embankments AEP Cardinal Plant Brilliant, Ohio

Dear Mr. Amaya:

In accordance with our proposal dated March 23, 2009, and our signed contract dated March 25, 2009, BBC&M Engineering, Inc. (BBCM) has completed a geotechnical assessment of the embankment separating the Bottom Ash Complex from the Ohio River at the Cardinal Generating Plant in Brilliant, Ohio.

BBCM's scope of work, as developed by AEP, consisted of obtaining subsurface data at a total of four cross-sections through the bottom ash pond an recirculation pond embankments, and performing seepage and slope stability analyses to provide an indication as to the level of safety provided by the embankments. The following report is a summary of our investigation.

We appreciate having been given the opportunity to be of service on this project. If you have any questions, please do not hesitate to contact this office.

Respectfully submitted,

**BBC&M ENGINEERING, INC.** Columbus, Ohio

0/~

Michael T. Romanello, E.I. Staff Engineer

Michael G. Rowland, P.E. Senior Engineer

Submitted: 4 bound copies 1 electronic copy on CDROM Cardinal Generating Plant Bottom Ash Pond Investigation

Brilliant, Ohio

Report to

American Electric Power Service Corp. Columbus, Ohio

Prepared by

BBCM Engineering, Inc. Dublin, Ohio

August, 2009

INTRODUCTION	1
SCOPE OF WORK	1
REVIEW OF HISTORICAL PLANS	1
GEOLOGY	2
FIELD WORK	
Soil Borings	2
Undisturbed Soil Samples Borehole Backfilling and Observation Wells	3
Recording of Field Data	
LABORATORY TESTING Index Testing	
Specialty Testing	5
GENERAL SUBSURFACE CONDITIONS	
Groundwater	
SEEPAGE AND STABILITY ANALYSIS	
Cross Sections	8
Seepage Analysis Hydraulic Properties	9
Hydraulic Boundary Conditions Finite Element Discretization and Mesh	
Seepage Analysis Models and General Results Stability Analyses	
Shear Strength Parameters Analysis and Results	11
CONCLUSIONS	.13
REFERENCES	13

# TABLE OF CONTENTS

# LIST OF APPENDICES

#### **APPENDIX A**

Vicinity Map	Plate 1
Plan of Borings	Plate 2
Subsurface Cross Sections	Plate 3
Symbols and Terms Used on Boring Logs	Plate 4
Boring Logs	Plates 5 through 22
Observation Well Logs	Plate 23 through 25

# APPENDIX B

Summary of Laboratory Test Results	Plates 1 through 4
Atterberg Limits Results by Layer	Plates 5 through 9
Gradation Curves	Plates 10 through 66
Laboratory Logs of Shelby Tubes	
3-Point Consolidated-Undrained Triaxial Shear Test Results	
Flex Wall Permeability Test Results	

# APPENDIX C

Historical Cross-Sections	Plates 1 & 2
Index Testing Statistical Summary by Layer	Plates 3 through 6
Slope Stability Shear Strength and Permeability Parameter Justification	
Seismic Hazard Map	Plate 33

# APPENDIX D

Seepage Model Hydraulic Boundary Conditions	Plate 1
Section A Seepage and Stability Analysis Graphical Output	
Section B Seepage and Stability Analysis Graphical Output	

#### INTRODUCTION

The Cardinal Generating Plant is located along the Ohio river between Brilliant, Ohio and Tiltonsville, Ohio, as shown on the Vicinity Map, included as Plate 1 of Appendix A. The Bottom Ash Pond Complex is located along the west bank of the river just to the south of the main plant area. The Bottom Ash Complex consists of two components: the Bottom Ash Pond and the Recirculation Pond. The Bottom Ash Pond is located north of the Recirculation Pond and they are separated by an earthen embankment. The crest elevation for all of the embankments is approximately the same, but vary in Elevation from 668.6' to 669.4' at the surveyed cross sections. The total length of the exterior embankment along the Ohio River is approximately 2,000 feet. For comparison, the normal pool for this stretch of the Ohio River is El. 644. Both ponds are isolated from exterior surface water inflow.

#### SCOPE OF WORK

The purpose of this Geotechnical Assessment was to provide an indication as to the level of safety provided by the dam separating the ponds from the Ohio River. The work which was performed as part of the limited subsurface investigation consisted of 1) review of the original plans; 2) the performance of two soil borings each at four different locations (one at the crest and one at the toe); 3) conversion of four soil borings into observation wells; 4) the completion of laboratory testing on the recovered samples; and, 5) engineering analyses of the existing embankments with consideration to seepage, steady-state slope stability and seismic slope stability.

#### **REVIEW OF HISTORICAL PLANS**

The Site Development Plan for the Ash Storage Area and the corresponding Sections Plan (drawings numbers 3-3017-5 and 3-3027-3, respectively) from the ash pond vertical expansion in the 1970s were made available for review. The plans were developed in 1973 and include 'Record Drawing' information through 1978. The ash pond complex is believed to have been originally constructed in the 1960s when the plant was first brought online. BBCM also received an electronic drawing file of the plant, including topographic data, as depicted in the Plan of Borings presented as Plate 2 in Appendix A. The aerial survey used to develop the drawing file was performed in 1994.

Based on the historical cross-sections extending through both the Bottom Ash Pond and the Recirculation Pond from the vertical expansion, the original ash pond embankments along the Ohio River ranged in height from 4 to 6 feet above the bottom of the ash pond. Historical Sections 'A-A' and 'C-C' detail the vertical expansion plans for the embankment which was assessed during this investigation. These cross-sections are presented as Plates 1 and 2 of Appendix C. Based on the sections, the original embankment was raised by approximately 10 to 12 feet by constructing an earthen embankment on the inboard slope of the original embankments. The construction was intended to raise the crest from an approximate elevation of 658.0 feet to Elevation 670.0 feet. The approximate boundary of the original ash pond embankment is depicted on the historical cross-sections as well as the seepage and stability analysis graphic output.

#### GEOLOGY

The natural soils at the site generally consist of a layer of alluvium silt, clay and fine sand over glacial outwash deposits of variable thickness overlying the bedrock surface. The alluvium clays and silts were deposited in the backwater of the Ohio River, while the outwash materials typically consist of sand, gravel and silt deposits deposited during the last ice age. Based on geological literature, the glacial outwash extends to the bedrock surface, estimated to be roughly 60 feet below the natural ground surface at the pond. The upper most bedrock most likely consists of shale and/or sandstone belonging to the Conemaugh Group of Pennsylvanian Age.

#### FIELD WORK

#### Site Reconnaissance

On March 20, 2009, a Senior Engineer and a Project Engineer from our office performed a Dam and Dike Condition Survey and results were presented in the 2009 Inspection Report for the Ash Impoundment. During the condition survey, the locations of the critical cross sections determined by AEP were observed, and the proposed borings were staked in these areas. Additional information concerning the visual condition of the dam may be found in this report.

#### **Soil Borings**

During the period of April 6 through April 10, 2009, BBCM was on site and performed a total of seven (7) soil borings, designated CD-BAP-0901 through CD-BAP-0907, that were extended to depths ranging from 30.0 to 60.5 feet below existing grade. A 'PZ' designation was added to Borings CD-PZ-BAP-0902, 0904, and 0905 to indicate an observation well was installed within the borehole. For simplicity throughout this report, the borings are typically referred to with the 'BAP' (Bottom Ash Pond) designation only. Borings BAP-0901, 0902, 0904 and 0906 were located at the crest of the pond embankments and Borings BAP-0903, 0905, and 0907 were located at the outboard toe of the embankment slopes, and were placed to correspond with the crest borings. The boring location areas were selected by AEP and field located by BBCM. The boring locations are shown on the 'Plan of Borings' presented on a full size drawing as Plate 2 in Appendix A. All boring locations and elevations, as well as additional ground surface points near the borings were surveyed by AEP personnel to create surface profiles.

All borings were performed with either a truck-mounted drill rig or an all-terrain-vehicle (ATV) mounted drill rig and were advanced between sampling attempts using 3¼-inch or 4¼-inch I.D. hollow-stem augers. Disturbed, but representative samples were obtained by lowering a 2-inch O.D. split-barrel sampler to the bottom of the hole and driving it into the soil by blows from a 140-pound automatic hammer freely falling 30 inches (Standard Penetration Test, ASTM D1586). The automatic hammer used to advance the SPT sampler had previously been calibrated for energy transmission using dynamic pile monitoring methods. The energy calibration factor is included on the boring logs. SPT sampling was performed continuously through the embankment fill and at 2½-foot intervals once the native soil was encountered. Split barrel samples were examined immediately after recovery and representative portions of each sample were placed in air tight jars and retained for subsequent laboratory testing.

#### Undisturbed Soil Samples

In addition to the disturbed samples, thin-walled press tube samples ("Shelby" tubes) were also attempted at various depths in order to obtain relatively undisturbed soil samples for strength testing. The samples were collected by hydraulically pressing a 3-inch diameter thin-walled steel (Shelby) tube at the end of the drill rod stem into the soil at a uniform rate. The samples were preserved inside the Shelby tube sampler and sealed with wax. The sample collection was completed in accordance with ASTM D 1587 Method for Thin-Walled Tube Geotechnical Sampling of Soils. Two Shelby tube samples were obtained in Boring BAP-0901 and one Shelby tube sample was obtained in each of borings BAP-0903 and BAP-0906. It should be noted that several other attempts were made to obtain additional undisturbed samples but resulted in crushing the tube or no recovery.

#### Borehole Backfilling and Observation Wells

During and at the completion of drilling, groundwater readings were measured and recorded in each boring. In Borings CD-PZ-BAP-0902, 0904, and 0905, wells were installed to permit future groundwater readings. The wells consist of 2-inch diameter PVC, well casings and screens. Screens are nominal 10-foot lengths with 10-slotted openings. Quartz sand was used as a filter (where the surrounding soil does not consist of sand and gravel) and was placed to a level approximately 2 feet above the top of the well screen. A well seal consisting of approximately 2 feet of granular bentonite (3/8-inch hole plug) was set above the filter pack and the remainder of the annular space was filled with a bentonite slurry (benseal). A lockable steel cover was installed over the well and a 3 foot by 3 foot concrete pad was constructed to protect the exposed portion of the well which extends above the ground surface. Three to four steel bollards were installed around each concrete pad to protect the well.

During the installation of the wells, a surge block was used to densify the sand pack. Upon completion, each well was developed. Well development includes an attempt to hand bail 10 well volumes of groundwater from each well. Well Completion Diagrams are presented as Plates 23 though 25 of Appendix A. BBCM understands that all follow up groundwater level measurements will be obtained by AEP personnel. It is also understood that AEP will formally survey in the top of pipe for the three wells.

#### Recording of Field Data

In the field, the following procedures and specific duties were performed by a Staff Engineer or a Field Geologist from our office:

- examined all samples recovered from the borings;
- cleaned soil samples of cuttings and preserved representative portions in airtight glass jars;
- made seepage observations and measured the water levels in the borings;
- prepared a log of each boring;
- made hand-penetrometer measurements in soil samples exhibiting cohesion; and,
- provided liaison between the field personnel and the Project Manager so that the field investigation could be modified in the event that unexpected subsurface conditions were encountered.

At the completion of drilling, all samples were transported to the BBCM laboratory for further examination and testing.

### LABORATORY TESTING

#### Index Testing

Laboratory testing was performed on selected representative soil samples obtained during the field investigations to determine natural moisture content (ASTM D2216), liquid and plastic limits (BBCM adjustment to ASTM D4318), and grain size analyses (ASTM D422). The results of these and other tests permit an evaluation of the strength, compressibility and permeability characteristics of the soils encountered at this site.

The results of the moisture content testing and of the liquid and plastic limits are graphically displayed on the individual boring logs presented in Appendix A. The results of all grain size analyses are also displayed graphically and presented as Plates 10 through 66 in Appendix B. All laboratory test results and a summary of laboratory test results are presented in Appendix B.

Table 1 summarizes the results of the index testing for the each layer except for the glacial outwash sand and gravel, where only a limited number of index testing was performed. For a comprehensive summary of all index testing performed, see Plates 3 through 7 of Appendix C.

Statistic	MC	LL	PL	PI	CF
Sample Size	16	12	12	12	8
Minimum	10	25	16	9	8
Maximum	31	37	24	18	21
Mean	16.3	30.3	18.3	12.1	12.1
Median	15	29	17	11	11
Mode	16	27	17	10	12
Standard Deviation	5.4	4.5	2.3	3.2	4.6

#### Newer Embankment Fill

#### Original Embankment Fill

Statistic	MC	LL	PL	PI	CF
Sample Size	10	6	6	6	4
Minimum	15	32	18	14	23
Maximum	33	49	29	24	32
Mean	22.5	43.3	23.5	19.8	28.0
Median	22	48	24	21	29
Mode	22	48	24	24	N/A
Standard Deviation	5.1	7.4	4.0	4.4	3.7

# Alluvium Silt and Clay

Statistic	МС	LL	PL	PI	CF
Sample Size	10	4	4	4	10
Minimum	22	34	21	7	3
Maximum	38	38	28	15	28
Mean	29.0	36.0	23.5	12.5	11.0
Median	29	36	23	14	7
Mode	26	N/A	N/A	15	5
Standard Deviation	5.4	1.8	3.1	3.8	8.5

Organic Clayey Silt

Statistic	МС	11	PL	PI	CF
			•		
Sample Size	22	18	18	18	21
Minimum	28	30	22	3	5
Maximum	54	50	38	20	44
Mean	41.8	40.2	27.1	13.2	18.9
Median	43	41	27	15	17
Mode	43	45	24	16	16
Standard Deviation	5.2	5.4	3.7	4.7	7.4

MC = Moisture Content; LL = Liquid Limit; PL = Plastic Limit; PI = Plasticity Index; CF = Clay-sized Fraction (% finer than 0.002 mm)

# **Specialty Testing**

In addition to the above index tests, a three-point isotropically consolidated-undrained (CU) triaxial shear test (ASTM D4767) and a flex wall permeability test was performed on undisturbed soil samples obtained from Shelby Tube sampling. Results of all laboratory testing are included in Appendix B. Difficulties were encountered in obtaining undisturbed samples within the newer embankment fill due to the granular nature of the material. The CU triaxial test and permeability test were performed on undisturbed samples obtained within the alluvium and original embankment fill layers, respectively.

# **GENERAL SUBSURFACE CONDITIONS**

# Stratigraphy

Based on the descriptions of the samples recovered in the borings and laboratory testing, the subsurface stratigraphy for each section can generally be described in descending order from the top of the embankment as follows:

 The four borings which were performed from the crest of the embankments encountered 1.0 to 3.0 feet of roadway base consisting of bottom ash/boiler slab at the ground surface overlying 18.0 to 22.0 feet of embankment fill consisting of very stiff to hard silty clay and medium-dense to dense fine to coarse sand and gravel. Hand penetrometer measurements on samples exhibiting cohesion within this layer ranged from 2.5 to 4.5+ tons per square foot (tsf), while SPT N-values (corrected for 60% energy) ranged from 6 to 50 with an average of 26. Index testing results, including liquid limit and plasticity index of samples tested within this stratum are summarized in Table 1 of the previous section. The material was predominantly classified as Lean Clay (CL) to Clayey Gravel with Sand (GC) under the Unified Soil Classification System. Boring CD-PZ-BAP-0901 encountered a 4.5 foot thick zone of very-soft to very-stiff silty clay at the bottom of the fill. Hand penetrometer measurements within this zone ranged from 0.0 to 2.25 tsf.

- The three borings which were performed from the outboard toe of the embankments encountered 8.5 to 11.5 feet of embankment fill consisting of very-stiff to hard brown mottled with gray silty clay. The fill encountered in these borings is believed to be associated with the original pond embankments, and is denoted throughout this report as the 'Original Embankment Fill'. Hand penetrometer measurements on samples within this layer ranged from 1.6 to 4.5+ tons per square foot (tsf), while SPT N-values (corrected for 60% energy) ranged from 11 to 48 with an average of 22. Index testing results, including liquid limit and plasticity index of samples tested within this stratum are summarized in Table 1 of the previous section. The material was predominantly classified as Lean Clay (CL) under the Unified Soil Classification System.
- Underlying the embankments, the borings encountered 4.5 to 10.5 feet of alluvium consisting of very-loose to loose silt with few zones of stiff to hard silty clay and thin seams of very loose to loose fine to coarse sand. Hand penetrometer measurements on samples exhibiting cohesion within this layer ranged from 1.6 to 4.5+ tons per square foot (tsf), while SPT N-values (corrected for 60% energy) ranged from 0 to 33, with an average of 8. Index testing results, including liquid limit and plasticity index of samples tested within this stratum are summarized in Table 1 of the previous section.
- Beneath the alluvium silt and clay, the borings encountered 3.5 to 14.5 feet of very-soft to stiff organic clayey silt. Hand penetrometer measurements on samples exhibiting cohesion within this layer ranged from 0.0 to 1.25 tons per square foot (tsf), while SPT N-values (corrected for 60% energy) ranged from 0 to 20, with an average of 5. Index testing results, including liquid limit and plasticity index of samples tested within this stratum are summarized in Table 1 of the previous section. Loss on Ignition (LOI) values ranged from 7.9 to 10.4%. The material is predominantly classified as organic clay with sand (OL) under the Unified Soil Classification System. Throughout the report, this layer was identified as a clayey silt based on its consistency even though the PI often indicated the material would be classified as a silty clay
- All borings were terminated after penetrating 7.0 to 30.0 into feet very-loose to loose fine to coarse sand and/or medium-dense to dense brown fine to coarse sand and gravel. SPT N₆₀-values in the very-loose to loose sand ranged from 4 to 29 bpf with an average of 12. SPT N₆₀-values in the medium-dense to dense sand and gravel ranged from 14 to 69 bpf with an average of 32. The percent passing the 200 sieve ranged between 6 and 24, with an average of 12.2.

The newer embankment fill consisted of silty clay, sand, and gravel and was considered as a uniform stratum although the main descriptor varied based on the small variations in the percent by weight of each material. Strength parameters associated with this layer are discussed in the **Seepage and Stability Analysis** section. For a more detailed description of the stratigraphy, including the presence of minor variations and inclusions, the logs of the individual borings should be examined in conjunction with the summary above.

#### Groundwater

Groundwater observations were made as each boring was being advanced and measurements were made at the completion of drilling. The groundwater observations are graphically displayed on the boring logs and also noted at the bottom of the log. All water level readings indicated on the borings logs are referenced from the ground surface, as the top of pipes have not yet been formally surveyed. Extended groundwater measurements were made in the observation wells while on site and are summarized in Table 2.

	Elevation During	Elevation at	Elevation on	Elevation on
Boring	Drilling	Completion	4-7/8-09	4-10-09
CD-BAP-0901	635.2	654.9		-
CD-PZ-BAP-0902	655.0	657.3	657.3	659.6
CD-BAP-0903	627.6	633.6		-
CD-PZ-BAP-0904	652.1	652.1		652.2
CD-PZ-BAP-0905	632.1	642.1	642.1	644.7
CD-BAP-0906	648.6	658.3		-
CD-BAP-0907	627.3	634.0		-

Elevation Datum: NAD 27 / NGVD 29

# SEEPAGE AND STABILITY ANALYSIS

Embankment dams must exhibit adequate factors of safety against a slope stability failure for static and seismic conditions. As part of this project, BBCM considered four areas of the ash pond embankment along the river as deemed critical by AEP to analyze for stability. Each section was developed by performing one boring through the crest of the embankment and one boring at the outboard toe, with the exception of the southernmost section through the recirculation pond embankment, where the location of the proposed boring at the toe was inaccessible. The following sections of this report discuss the analyses that were performed, explain the rational supporting parameter selection and present the results.

Based on visual observations, the Recirculation Pond embankments appeared to be in 'Fair' condition while the Bottom Ash Pond appeared to be in "Good' Condition. The principal item which came out of this inspection relative to this report is that no evidence of slope failure or seepage was observed on the embankment slope between the pond and the river. It should be noted however, that the toe of the slope is inundated by the ordinary high water level of the Ohio River. The 2009 Inspection Report should be consulted for the complete assessment of the visual observations made for the Bottom Ash Complex.

#### Methodology

The seepage and stability analyses were performed with the aid of the computer program Slide (Version 5.0) developed by Rocscience, Inc. The program performs 2-D limit equilibrium slope stability analyses and steady-state unsaturated seepage analysis; the latter using the finite element method. Pore pressure values produced from the seepage analysis are used in the slope stability computations for each model.

Static and seismic slope stability analyses were performed on the outboard embankment slopes for Cross-Sections B and D using Spencer's method (Spencer, 1973) with a deterministic approach. Both methods provide solutions for given cross sections based on limit equilibrium theory. The five critical slip surfaces corresponding to the lowest factor-of-safety are shown in the graphical output. Seismic slope stability analyses were performed based on a pseudo-static slope stability approach. Stability calculations were performed in general accordance with the US Army Corps of Engineer's Engineering Manual 1110-2-1902 entitled *Slope Stability*.

# **Cross Sections**

Cross-sections showing the general subsurface conditions encountered in the borings were developed based on the survey data provided by AEP. Table 3 summarizes the borings used to develop the four cross sections, which are shown individually on the Subsurface Cross Sections shown on a full size plan sheet as Plate 3 of Appendix A. Two cross-sections were chosen to carry out the seepage and stability analysis, and are considered representative of the cross-sections not used. It should be noted that no bathymetric data was available. As such, the portion of the slope located below the Ohio River normal pool was estimated. If bathymetric information becomes available in the future, it is recommended that the analysis cross-sections be reviewed.

Cross-Section	Location	Crest Boring	Toe Boring
Section A	Recirculation Pond	CD-BAP-0901	-
Section B	Recirculation Pond	CD-PZ-BAP-0902	CD-BAP-0903
Section C	Bottom Ash Pond	CD-PZ-BAP-0904	CD-PZ-BAP-0905
Section D	Bottom Ash Pond	CD-BAP-0906	CD-BAP-0907

#### Table 3: Cross Section Data

Although four separate cross-sections were examined, the parameters selected to represent the permeability and strength of both the original and newer embankment fill layers were kept the same between sections. Although there are minor differences when comparing the two layers between borings, it is believed that there is insufficient evidence to support delineating the parameters from section to section. Therefore, for the purposes of the seepage and slope stability analyses, the permeability and shear strength parameters used to represent the fill layers were based on the totality of test data available for the embankment across the entire site.

The natural alluvium soils underlying the pond embankments are somewhat variable, consistent with the depositional environment of such soils. As with the embankment fill, it is difficult to justify developing specific parameters for an individual cross-section, as the properties of this stratum may vary over short distances. As such, the parameters used to represent the alluvium, and similarly the organic clayey silt and glacial outwash layers, were based on the totality of test data available for these layers across the entire site.

At the time of the survey performed March 27, 2009, the pool levels in the recirculation pond and bottom ash pond were at EL. 663.1, and EL. 664.4, respectively. The resulting freeboard from the surveyed pool levels range from 4.3 - 5.1 feet and 5.6 - 5.8 feet for the recirculation and bottom ash ponds, respectively. It is understood that these levels represent the approximate normal operating pool level. The pool level in the Ohio River was recorded as Elevation 644.4 feet. The ordinary high water level of the river is believed to be EL. 644 at the site.

#### Seepage Analysis

The location of the groundwater table within the embankments was estimated based on extended groundwater readings taken from the observations wells and conditions encountered during drilling. Groundwater conditions used in the finite element model were then calibrated to match the observed conditions. Results from the seepage analysis provided pore pressure values within the model to be used in the Stability Analysis.

#### Hydraulic Properties

As previously indicated, the same modeled permeability values for the various soil layers were taken for both cross-sections based on the totality of information available for the site. A flex wall permeability test was performed on an undisturbed sample obtained within the original embankment fill layer yielding a vertical permeability of  $7.4 \times 10^{-8}$  cm/sec. The design value for permeability was increased to  $5 \times 10^{-7}$  cm/sec as a result of the calibration of the seepage models. Permeability values for the other strata were estimated from typical published values based on material description or correlations to grain size. Permeability values and anisotropic ratios were then adjusted during the seepage analysis to best match the observed groundwater conditions. Supporting calculations for the development of the permeability values are included in the *Slope Stability Shear Strength and Permeability Parameter Justification* section of Appendix C.

Permeability values assigned to the model layers are shown in the table below. Several layers were modeled with anisotropic permeability functions. The horizontal permeability ( $k_h$ ) of the original embankment fill soils were estimated as 10 times the vertical permeability ( $h_v$ ), to best model the stratification of the soil as a result of compacting the fill in horizontal lifts (Casagrande, 1937), but was adjusted to a ratio of 5 times during the analysis. Similarly, a  $k_h/k_v$  ratio of 2 was used for the newer embankment fill soils. The alluvium and organic clayey silt foundation layer were modeled with a horizontal permeability twice the vertical permeability to simulate the natural stratification and inclusion of fine sand seams. The remaining soil layers were defined as a granular material and were assigned isotropic permeability functions.

Material Description	Permeability		Reference	
	k _v (cm/sec)	k _h / k _v	Relefence	
Newer Embankment Fill	1x10 ⁻⁵	2	Grain Size Correlation	
Original Embankment Fill	5x10 ⁻⁷	5	Permeability Test	
Alluvium Silt and Clay	1x10 ⁻⁵	2	Typical Published Values	
Organic Clayey Silt	5x10⁻ ⁶	2	Typical Published Values	
Loose to Med Dense Glacial Outwash Sand and Gravel	1x10 ⁻²	1	Grain Size Correlation	
Med Dense - Dense Glacial Outwash Sand and Gravel	1x10 ⁻³	1	Grain Size Correlation	

Table 4: Permeability	Values
-----------------------	--------

#### Hydraulic Boundary Conditions

Topographic contours from the most recent survey as well as from historical construction drawings were used to expand the surface profile created from the AEP survey in order to develop a full scale model. The following boundary conditions were assigned to the finite element based models.

- A 'Constant Head' boundaries of 663.0 and 664.5' were used to represent the level of water in the recirculation pond and ash pond, respectively.
- The model was extended on the downstream side to the approximate middle of the Ohio River, and a 'Constant Head' boundary of 644.4' was used to represent the normal flow level of the river at this point (water level recorded by AEP).
- A 'No-Flow' boundary was placed on the upstream end of the model, as flow should become predominantly downward near the middle of the pond.
- A 'No-Flow' boundary was placed on the bottom of the model at Elevation 550' representing the approximate bedrock surface, which is assumed impermeable for this analysis.
- 'Unknown' boundary conditions were set on the remainder of the model to allow the program freedom to calculate values at these locations. These locations include the downstream slope face and the downstream ground surface.
- For Section D, the Constant Head Boundary of 644.4' was extended up the downstream slope to the location of the toe boring in an effort to model the observed groundwater conditions within the original embankment fill.

#### Finite Element Discretization and Mesh

The following steps were performed during the development of the seepage model:

- 6 Noded Triangles were used to generate the finite element mesh for the models (see Plates 2 and 7 of Appendix D).
- The density of nodes was manually increased to minimize the number of 'Poor Quality Elements' based on the Mesh Quality function available in Slide.
- Poor quality elements were defined as elements with one of the following characteristics:
  - 1. Maximum side length to minimum side length ratio greater than 10.
    - 2. Minimum interior angle less than 20 degrees.
    - 3. Maximum interior angle greater than 120 degrees.
- Prior to final computational runs, a sensitivity analysis was performed to determine if an adequate number of total finite element nodes were used in the analysis.
- A sensitivity analysis was performed on the tolerance of the computational iteration.

#### Seepage Analysis Models and General Results

Graphical output from the seepage analyses for Sections B and D are presented in Appendix D as Plates 3 and 4 for Section and B and Plates 8 and 9 for Section D. The calibrated seepage models produced phreatic surface shapes close to what was expected based on the water levels measured in the observation wells.

Although a typical phreatic surface extending from the ash pond level to the Ohio River was generated, much of the seepage emanating from the ponds is moving downward through the newer embankment fill and thin stratum of alluvium soils and into the glacial outwash sand and gravel stratum.

#### **Stability Analyses**

#### Shear Strength Parameters

In order to perform slope stability analyses, it was necessary to estimate appropriate parameters to represent the existing soils. The shear strength and unit weight values used for the slope stability analyses were based on a combination of the laboratory index test results, triaxial shear tests, published values and judgment, and are intended to be representative of long-term conditions. Table 5 lists the strength parameters used in both static and seismic analyses for each stratum. Supporting calculations for the development of these strength values are presented in the *Slope Stability Shear Strength Parameter Justification* section of Appendix C.

The percent of organic content in the Organic Clayey Silt layer was determined by performing Loss on Ignition (LOI) tests; results ranged from 7.9 to 10.4 percent. For LOI-values of less than 20 percent, the soil properties are controlled by the non-organic portion of the soil (FHWA, 2002).

Material Description	Ywet	Strength		Reference
	(pcf)	φ'	c' (psf)	Relefence
Newer Embankment Fill	125	31°	0	SPT and Index Testing Correlations
Original Embankment Fill	125	30°	100	Index Testing Correlations
Alluvium Silt and Clay	125	30°	0	Index Testing Correlations
Organic Clayey Silt	125	30°	0	Index Testing Correlations and CU Triaxial Test (BBCM 2009)
Very Loose to Loose Glacial Outwash Sand and Gravel	115	29°	0	SPT and Grain Size Correlations
Medium Dense Glacial Outwash Sand and Gravel	120	34°	0	SPT and Grain Size Correlations

Table 5: Strength Values for Static Conditions

In addition to the static steady-state stability analyses, strength parameters were developed for use with the pseudo-static seismic analyses. With respect to seismic loading, it is believed that the newer embankment fill soil is sufficiently granular that drained strengths values will be exhibited during seismic loading. However, as the original embankment fill is more cohesive in nature, it will likely exhibit an undrained response. As the embankment fill has come to equilibrium under the present steady-state seepage conditions, the shear strength envelope used in the analysis was based on the "R" test, as recommended in the Army Corps of Engineer's Manual 1110-2-1906 "Laboratory Soils Testing," and suggested by Duncan and Wright in their 2005 publication. This is essentially the slope and y intercept of the CU strength envelope. Unfortunately, CU triaxial tests were not performed in the newer embankment fill layer as all Shelby tubes attempted in this layer failed to recover an adequate sample size (however, a permeability test was performed). The seismic strength values for the newer embankment fill layer has been estimated based on values given by Duncan and Wright (2005) for soils with similar index properties (See Plate 16 of Appendix D). CU Triaxial test data was available for the Organic Clavey Silt laver, and the corresponding R envelope was used to model the shear strength. As there is a significant amount of sand within the alluvium strata, drained strength values were used for seismic loading.

#### Strength Ywet Material Description Reference (pcf) c (psf) ø SPT and Index Testing 0 Newer Embankment Fill 125 31° Correlations 22° Original Embankment Fill 125 50 Duncan and Wright (2005) Alluvium Silt and Clay 125 30° 0 Index Testing Correlations Organic Clayey Silt 125 24° 180 CU Triaxial Test (BBCM 2009) Very Loose to Loose Glacial 115 29° 0 SPT and Grain Size Correlations Outwash Sand and Gravel Medium Dense Glacial 34° 120 0 SPT and Grain Size Correlations Outwash Sand and Gravel

# Table 6: Strength Values for Seismic Conditions

# Analysis and Results

Static and seismic analyses were performed on Sections B and D to determine the factor of safety against rotational failure for the outboard slopes using drained soil strength parameters. The graphical computer outputs for these analyses have been included with this report in Appendix D.

Seismic analyses were performed using a pseudo-static analysis with a horizontal seismic coefficient of 0.06g. This coefficient was determined from the 2008 USGS National Seismic Hazard Maps for the "Peak Acceleration (%g) with 2% Probability of Exceedance in 50 Years". This chart is provided as Plate 33 of Appendix C.

Graphical results of the slope stability analysis for static and seismic conditions are shown in Appendix D. Table 7 summarizes the lowest factors of safety determined for each analysis case.

Analysis Case	Required Minimum	Computed FS		
Analysis Case	Factor of Safety	Section B	Section D	
Static (Steady-State Seepage)	1.50	1.57	1.52	
Pseudo-Static	1.00	1.05	1.09	

The critical failure surfaces were located through a deterministic search, with no limitations on failure depth. The failure surface locations were restricted to find only surfaces associated with a global failure through the composite embankment (original plus newer embankment fill) or through the original embankment only. Shallow sloughing failures along the river bank were not considered for this analysis. The results are based on the pool level recorded at the time of the survey, extrapolated bathymetric data, and the groundwater measurements recorded from the observation wells.

# CONCLUSIONS

As part of this report, BBCM examined the stability of the outboard embankment slopes at 4 locations under steady-state seepage and seismic loading conditions using the results of 7 soil borings. The analyses suggest that at the four cross sections examined, the embankments exhibit adequate factors of safety relative to those recommended by the US Army Corps of Engineers (COE).

# REFERENCES

United States Society on Dams (USSD). *Strength of Materials for Embankment Dams*. February, 2007.

U.S. Army Corps of Engineers. *Slope Stability*: Engineering Manual 1110-2-1902. October, 2003.

U.S. Army Corps of Engineers. *Laboratory Soils Testing*: Engineering Manual 1110-2-1906. August, 1986.

Casagrande, A. "Seepage Through Dams." *Journal of New England Water Works Association*, 1937, LI, 2, pp. 295-336.

Naval Facilities Engineering Command (NAVFAC) (2005), "Geotechnical Engineering Procedures for Foundation Design of Buildings and Structures", Unified Facilities Criteria (UFC) 3-220-01N.

Federal Highway Administration. <u>Geotechnical Engineering Circular No. 5: Evaluation of Soil</u> and Rock Properties. Report No. FHWA-IF-02-034, April, 2002.

United States Geological Survey (USGS) Earthquake Hazards Program. Preliminary National Seismic Hazards Maps – Accessed April 2008. http://earthquake.usgs.gov/research/hazmaps/products_data/2008/

Stark, T.D., Choi, H. and McCone, S. "Drained Shear Strength Parameters for Analysis of Landslides." Journal of Geotechnical Engineering, ASCE, Vol. 131, No. 5, pp. 575-588.

Hall, G.A. "The Development of Design Criteria for Soil Slopes on West Virginia Highways." Dissertation, West Virginia University, 1974, Ch. VII.

Appendix VI – Excerpt from 2010 Follow-Up Investigation Report

#### INTRODUCTION

BBCM previously performed a limited subsurface investigation and slope stability analyses of the Cardinal Bottom Ash Pond Complex, the report of which was dated August 4, 2009. This report consisted of obtaining subsurface data at a total of four cross-sections through the bottom ash pond and recirculation pond embankments, and performing seepage and slope stability analyses to provide an indication as to the level of safety provided by the embankments.

The purpose of this follow-up work was to supplement the analyses performed as part of the original work in an attempt to fulfill the AEP action plan requirements in response to the USEPA inspection report. The follow-up slope stability analyses are solely based on existing subsurface data, as no additional field or laboratory work was performed as part of this project. Also as part of this follow-up work, hydraulic and hydrologic (H&H) analyses were performed to determine the capacity and freeboard of the Bottom Ash Pond related to current requirements. A summary of the work performed is contained in this report. This report should be considered an addendum to our August 4, 2009 Bottom Ash Pond Complex report.

#### SLOPE STABILITY ANALYSIS

#### Follow-Up Embankment Stability Analysis

Additional slope stability analyses were performed on Sections B and D to determine the factor of safety against rotational failure for the following conditions:

- 1.) Inboard slopes under steady-state seepage conditions;
- 2.) Pseudo-static seismic analyses under steady-state seepage conditions for the inboard slopes;
- 3.) Surcharge pool conditions (outboard slopes); and,
- 4.) Rapid drawdown analyses for the inboard slope.

The previously developed cross-section (B and D) geometry, permeability values, and shear strength parameters were used in the follow-up analysis. Please refer to the '*Subsurface Investigation and Analysis – Bottom Ash Pond Embankments*' report by BBCM dated August, 2009 for a complete discussion of these parameters.

Seismic analyses for the inboard slopes were performed using a pseudo-static analysis with a horizontal seismic coefficient of 0.06g, consistent with the original report. The surcharge pool was modeled using a distributed line surcharge load, as it is not expected that the phreatic surface within the embankment will change during this temporary loading condition.

A rapid drawdown analysis was also completed for the bottom ash pond inboard embankment slopes utilizing the previously developed cross-sections. It is the understanding of BBCM that the ponds are typically filled with ash which would tend to support the inboard slopes. However, on an occasional basis, during times of ash removal and subsequent re-filling, a full pool of water could be established and a rapid drawdown scenario could occur if the pond were suddenly emptied. While not impossible, a large scale rapid drawdown event with unsupported interior slopes is unlikely. Notwithstanding, a rapid drawdown analysis was completed using the conventional method whereby the phreatic surface is positioned at the ground surface (inside the pond) and extended up into the slowly-draining embankment layers to the normal pool elevation. Drained strength parameters are used in this scenario. The drawdown level for the

analysis was considered to occur from the normal operating pool El. 664.4 down to the natural ground surface on the inboard side of the embankment. During the subsurface investigation it was determined that there are two types of fill present in the embankments, identified as *newer embankment fill* and *original embankment fill*. The *newer embankment fill* contains a high percentage of sand and gravel (58%), as determined from previous laboratory testing. While pockets of this layer are cohesive and will exhibit a slowly-draining response during a rapid drawdown event, the layer as a whole likely will not maintain a consistent phreatic surface on the inboard slope. As a result, the phreatic surface was modeled to maintain its elevated level only within the *original embankment fill* and not within the *newer embankment fill*. Please see the analysis of the *newer embankment fill* layer submitted in Appendix B.

Graphical results of the slope stability analysis for static and seismic conditions are shown in Appendix A. Table 1 summarizes the lowest factors of safety determined for each analysis case.

Analysis Case	Required Minimum	Computed FS	
Analysis Case	Factor of Safety	Section B	Section D
Static (Steady-State Seepage) – Inboard Slope	1.50	1.70	1.65
Pseudo-Static – Inboard Slope	1.00	1.39	1.34
Maximum Surcharge Pool – Outboard Slope	1.40	1.55	1.52
Rapid Drawdown – Inboard Slope	1.30	1.55	1.52

Table 1: Stability Analysis Summary

The critical failure surfaces were located through a deterministic search, with no limitations on failure depth. The failure surface locations were restricted to find only surfaces associated with a global failure through the embankment. Shallow sloughing failures along the river bank were not considered for these analyses.

#### Liquefaction of Foundation Alluvium

A liquefaction screening analysis was performed for the soft alluvium soils underlying the embankments. There is concern that areas of this layer could potentially liquefy during seismic excitation and ultimately cause a failure of the embankments. The screening analysis was performed using the five techniques listed in the Federal Highway GEC No. 3:

- 1.) Geologic Age and Origin,
- 2.) Fines Content and Plasticity Index,
- 3.) Saturation,
- 4.) Depth Below Ground Surface, and
- 5.) Soil Penetration Resistance.

The five screening techniques are described in detail in the hand calculations provided in Appendix B. Due to the fines content and plasticity index, as well as the geologic age and origin, the screening analysis suggests that liquefaction will not occur for the alluvium silt and clay layer.